

Middlesex University Research Repository

An open access repository of

Middlesex University research

<http://eprints.mdx.ac.uk>

Kobliha, Bohumil Augustin (1988) Computer aided factory layout planning (CAFLAP). PhD thesis, Middlesex Polytechnic. [Thesis]

This version is available at: <https://eprints.mdx.ac.uk/6472/>

Copyright:

Middlesex University Research Repository makes the University's research available electronically.

Copyright and moral rights to this work are retained by the author and/or other copyright owners unless otherwise stated. The work is supplied on the understanding that any use for commercial gain is strictly forbidden. A copy may be downloaded for personal, non-commercial, research or study without prior permission and without charge.

Works, including theses and research projects, may not be reproduced in any format or medium, or extensive quotations taken from them, or their content changed in any way, without first obtaining permission in writing from the copyright holder(s). They may not be sold or exploited commercially in any format or medium without the prior written permission of the copyright holder(s).

Full bibliographic details must be given when referring to, or quoting from full items including the author's name, the title of the work, publication details where relevant (place, publisher, date), pagination, and for theses or dissertations the awarding institution, the degree type awarded, and the date of the award.

If you believe that any material held in the repository infringes copyright law, please contact the Repository Team at Middlesex University via the following email address:

eprints@mdx.ac.uk

The item will be removed from the repository while any claim is being investigated.

See also repository copyright: re-use policy: <http://eprints.mdx.ac.uk/policies.html#copy>

MX 7172114 2



Polytechnic Library

COMPUTER AIDED FACTORY LAYOUT PLANNING
(CAFLAP)

Bohumil Augustin K o b l i h a

A thesis submitted to the C.N.A.A. in partial fulfilment
of the requirements for the degree of Doctor of Philosophy.

Faculty of Engineering, Science and Mathematics
M I D D L E S E X P O L Y T E C H I C

JULY 1988

Site HE BG	MIDDLESEX POLYTECHNIC LIBRARY
Accession No.	7172114
Class No.	670.427 KOB
Special Collection	Reference The size Collection

B. A. K O B L I H A

Computer Aided Factory Layout Planning (CAFLAP)

A B S T R A C T

This Thesis addresses Factory Layout Problems, and reviews and evaluates the available layout techniques.

Manufacturing as a system has been studied and reclassified for factory layout: space demands and spatial relationships have been considered as main principles of Factory Layout Planning. This forms a basis for the introduction of a new, more efficient Factory Layout Planning Methodology, denoted as SPACE MANAGEMENT. A new COMPUTER AIDED FACTORY LAYOUT PLANNING system is formulated as a tool for:

- preparing 3-D templates of Work Station Modules and Equipment Modules;
- drawing a requested interior of an industrial hall/bay in 3-D;
- positioning any 'objects' (spaces), via manual interactive programs in 3-D;
- automatic positioning of work stations and equipment in the bay, in 'technological' order (in 3-D), using an automatic positioning program, with a facility for:
 - collision course finding (with objects within the bay),
 - manual override for corrections, and
 - finding an optimum size (width) of the bay.

The resulting layout scene can be observed from any required position and distance.

The system includes a set of auxiliary programs for Manual Feeding of lines of work stations in 'technological' order and for basic capacity calculations.

CAFLAP also opens a new way of economic evaluation of projects and alternatives.

CAFLAP is implemented in FORTRAN 77 and uses the Computer Graphics System PICASO.

A C K N O W L E D G E M E N T S

In the very special first place I would like to thank The Wolfson Foundation for financial support without which this Project could not have been started, and personally to Mr.W.B.H. LORD, who was so helpful in the formulation of the task.

I would also like to thank Middlesex Polytechnic and its friendly staff for any technical support and especially to Prof.Dr.Frank TYE who allowed me to finish the Project in extra time needed to partially recover losses caused by unforeseen circumstances.

My absolute thanks to Dr.Roger A. WHITAKER, for all his work as Director of Studies and much more than that.

My genuine thanks to Dr.John VINCE for his sincere and friendly tutorials, consultations and interest in my work, going beyond the professional responsibility of a Supervisor.

My friendly thanks to Dr.Peter HOLMES and Dr.Y.B.KAVINA for consultations, and Mr.Don KNIGHT for his hospitality at CAD area.

Many warm thanks to programmers Mr. Paul HUGHES and Mr. Mark HURRY for practical and expert advice.

Cordial thanks to ELTRON (London) Ltd. and namely to Production Director Mr.David SWIFT and Production Manager Mr.Mike TURNER for offering their valuable opinions and opportunity to carry out the Project work in their factory.

Many thanks to students, particularly to Herr Martin Wiegman and Mr.Wai Peng Foo, for testing my programs and ideas in their 3rd year Projects.

My love and endless gratitude to my wife Mrs. Miroslava KOBLIHOVA, M.A., for all her support, patience and intelligent comments, and my daughter Miloslava for creating an atmosphere of loving harmony without which this Project could never have been finalised.

Thanks to you ALMIGHTY GOD for giving me health and strength so much needed for this task.

CONTENTS

ABSTRACT	i
ACKNOWLEDGEMENTS	ii
1. INTRODUCTION	1
2. FACTORY LAYOUT PLANNING AND EXISTING TECHNIQUES	9
3. COMPUTER AIDED SYSTEMS PRESENTLY AVAILABLE	28
4. COMPUTER AIDED FACTORY LAYOUT PLANNING	68
4.1 ENUNCIATION OF THE PROBLEM	68
4.2 SYSTEM MANUFACTURING	72
4.3 LAYOUT STRATEGY	95
4.4 LAYOUT USING INTERACTIVE COMPUTER GRAPHICS	108
4.5 PROGRAMS AND THEIR SOLUTIONS	110
5. THE TESTING OF PROGRAMS	129
6. DISCUSSION OF RESULTS	132
7. INDUSTRIAL APPLICATION OF CAFLAP	136
8. PRESENT LIMITATIONS OF THE SYSTEM AND RECOMMENDATIONS FOR FURTHER DEVELOPMENT	140
9. CONCLUSIONS	142
10. REFERENCES	145
APPENDICES	
I Terminology	
II Computer Programs Printouts	
III Computer Graphics Prints/Drawings	

1. INTRODUCTION

The purposeful arrangement of machine tools and equipment on the shop floor is of equal importance for competitive manufacturing as machining itself. It is very well documented in history how the wealth of nations grows as their manufacturing standards improve. A very good example of this is the Republic of Venice [7]. Manufacturing was one of the pillars of the Republic's success, and was so advanced that in 1474 it led to the enactment of the first formal patent law. The "heart of the state of Venice" was the Arsenal [24]. Here was also the largest centre of production and the greatest concentration of workmen before the industrial revolution. The plans of the Arsenal, founded in 1104, were in fact an early example of planned plant layout!

'Plant Layout' and 'Factory Layout Planning' are terms (see Appendix I-1) most commonly used for labelling activities concerned with a feasible location of manufacturing or processing facilities in a suitable region, site, complex of buildings, industrial hall and finally in an industrial bay.

By definition, 'Plant Layout' is the most effective arrangement and coordination of the physical plant facilities, to allow greatest efficiency in the combination of man, materials, machines and equipment necessary for the

operation of any unit of a plant or business [1]. The activity in Factory Layout Planning could be expressed symbolically as in Fig.1.




Fig. 1. ACTIVITY IN FACTORY LAYOUT PLANNING
RESULTS IN EFFICIENT OPERATION

As the main interest of this project is focused on mechanical engineering manufacturing, the term Factory Layout Planning [22] has been chosen. This term also clearly distinguishes activities in mechanical engineering production from chemical and other similarly specialised plants (i.e. food processing, earth products etc.), and from the design of individual equipment.

Factory Layout Planning is closely interrelated with

Mechanical Engineering, Production Engineering, Mechanical Technology, Material Handling, Management and Organisation, Industrial Psychology and Sociology, Civil Engineering, Architecture and Town Planning on one side, and with Ventilation and Heating, and Electrical Engineering etc., on the other side. The requirements and demands of these professions together with legislative measures like the Health and Safety Act, and the regulations of the Ministry of Defence, Ministry of Transport and Civil Aviation can be very restrictive. Further factors related to the protection of nature, springs and water, historic monuments, etc., have to be carefully considered, and can sometimes, even become ruling factors in Factory Layout Planning. All that is indispensable, as the construction of a new plant or modernisation and reconstruction of an older factory may have a substantial influence on the environment and on the lives of the inhabitants within a relatively large area.

In Factory Layout Planning there are usually two main types of situation to be encountered:

- The change of layout within an existing factory,
- or
- A layout for a new factory on a 'green field site'.

In the first case the object is to try to utilise the existing areas in the most economical manner in order to accommodate efficient production. In the second case, the civil engineering part can be designed to fit exactly the

technological needs. These two different situations can result in a different emphasis in layout techniques. ✓

Other situations and complications follow from the type of manufacturing/production (single product, multi-product, parallel) and from the further division of production according to the quantity of products to be manufactured e.g. job production, batch production, flow production and mass production.

The type of production usually conditions the type of layout, i.e.:

- Process (or Functional) Layout,
where the main factor for work stations arrangement is considered to be the technological process (similarity of operations, e.g. drilling machines in one area, milling machines in another area, etc., often creating departments, i.e. milling department, drilling department, etc.).
- Product (or Line) Layout,
where the main factor for work stations arrangement is the product. Work stations are arranged to suit the sequences of operations (e.g. prodn. line). [1]

As a special sub-group could be considered Group Layout (Group Technology and Flexible Manufacturing Systems).

- Fixed-Position Layout,
where the product is stationary and material,
men and equipment are brought together
to work on the product (ships, bridges).`

The initial considerations and calculations for new layout very often form the basis for the long-term prosperity of the whole company. A plant must be profitable and the profit must be maximised, so that the plant layout /consulting engineer has to approach the task with this in mind and take care to avoid any possible losses in future, which may affect not only the investor, but the public as well. Therefore the future situation must be assessed already in the preliminary stage.`

Here the layout engineer faces a dilemma. At this stage he is not in possession of sufficient amount of data and information of requested accuracy and depth to design a new layout. But still, the decision making must be as precise as possible. In some cases even the most essential information, e.g. the volume of production, is lacking and must be acquired by the engineer via an analysis of statistics, typical products, indirect indicators, and qualified guesses. The technique of Typical Products is used when there is a lack of information regarding the future actual products. Typical products have similar specifications and characteristics to those of the future

planned products.

As this is a very demanding exercise, some companies and consulting engineering firms have developed up to five stages of project to avoid losses. For example, the Ford Motor Company has three 'project' stages: Programme Study, Study, and Project. (This will be discussed later in Chapter 2.)

In this complicated situation it is quite difficult to find a way to ease the work of the Factory Layout Planning Engineer. According to Francis and White [16] (published in 1974!) there were some five hundred papers written on the topic.

Moor in his survey [30] in the same year (1974) analysed twenty five programs and concluded that the layout planner must still do almost all the adjustments. He considered the facility design problems to be complex and ill-structured, and as such they were handled in a variety of ways, such as: total enumeration, computerised techniques, interactive programming, heuristic programming and by intelligent machines. He also observed that a great majority of programs fell into the construction or improvement class, only five programs were found to fit into graph theory or other [30- Fig.3].

Lewis and Block [32] in 1980 noted that 'despite much

research activity there is widespread failure to use available computer programs for planning the layout of manufacturing facilities'.

According to Lewis and Block this happened for two reasons: opinion that an experienced planner can produce acceptable layout based on his own subjective judgement; and ignorance of the potential benefits of computer-aided techniques.

The writer's own experience from Ford-Dagenham, Plant Layout Department (1973-75) was similar to that of Lewis and Block, but the reasons for the failure to use computer programs are seen differently. There were serious attempts made at Ford's to use the programs available at that time, but these failed to help efficiently in practical plant layout work. The main reason could be seen in the fact that the programs were covering only a tiny portion of the planner's tasks. The manual method of templates on 'skins' (see Appendix I-12) continued in use instead, until 1987 as documented by Mike Farish [33] (See Chapter 3.).

In the second half of the seventies the number of published work titles on Factory Layout Planning seems to have dropped. However between 1980 and 1988, there were over forty new titles in the field (according to Applied Science and Technology Index, January 1980-March 1988). Contrary to Moor's survey findings and his classification [30] it seems

that some entirely new aids are now appearing combining simulation and computer graphics, for example Hollocks [25]; and interactive computer graphics, for example O'Brien and Barr [34] (See Chapter 3.).

The present work introducing Computer Aided Factory Layout Planning (CAFLAP) also uses interactive computer graphics principles. Moreover CAFLAP is pioneering some new principles of layout planning (3-D space management), which are used in combination with computer graphics in order to assist the layout engineer in a more creative way mainly in detailed layout planning.

CAFLAP offers planners a very simple, cheap and easy-to-learn-and-use practical tool for everyday layout work; a tool which would be always available for any production engineer or planner to use as and when the need occurs. \

2. FACTORY LAYOUT PLANNING AND EXISTING TECHNIQUES

2.1 FACTORY LAYOUT PLANNING

According to Reed [1] a good factory layout should satisfy the following basic requirements:

- Improvement of the manufacturing process
- Improvement of Material Handling (M.H.)
- Most effective use of available area
- Improved utilisation of labour
- Improved efficiency in plant services
- Improved employee morale
- Improved production management, quality and production control
- Minimum capital investment

Main objectives of a good layout could be formulated from experience, using the above as a lead:

- effective and safe operation
- comfortable and safe access to work stations for operation and maintenance
- straight Material Flow
- work stations as close to each other as possible
- work stations positioned in inter-related positions (in straight lines or groups)
- work stations in positions requesting minimum space

- in an industrial bay
- and
- work stations in positions with no interference
- with other 'spaces' (see 4.2, 4.3 and 4.4).

Observing the situation in Factory Layout Planning Bestwick and Lockyer [3] conclude that "there are a number, and sometimes conflicting requirements, which should be satisfied" if "most effective arrangement and co-ordination of physical plant facilities" is to be achieved.

In the writer's view there are two different categories of basic requirements': conflicting and complementary.

Considering first the complementary criteria it can be seen that:

Firstly, improvements in the manufacturing process can be achieved if in the layout planning area provisions are made for smoother material flow and reduction of delays. This, projected on the shop floor, can be achieved by improved Material Handling (M.H.). The main generally recognised principle of M.H. is DON'T (i.e. don't move). Apple [35] and others are stressing the importance of elimination of movements. If movements cannot be eliminated they should be simplified, shortened and straightened. Any congestion should be avoided.

These M.H. principles are in agreement with the requirement for closeness of facilities as formulated by Muther [4]. The principles of closeness and reduction of movements are aimed at greater cost effectiveness.

Shorter distances between facilities result in improved utilisation of labour, not only in the M.H. area, but also in manufacturing services; e.g. faster supply of tools (this depends on accessible positioning of Tool Crib).

Secondly, closeness of sufficient facilities for health and welfare (lavatories, drinking water, sitting facilities, rest rooms, etc.) in connection with Health and Safety at Work requirements [36,57] eliminates the excessive Relaxation Allowance [51] and improves the quality of relaxation time for the labour force. These measures directly contribute to employees' contentedness, and this improves their moral. The aesthetic effect of well arranged layout also makes an all round positive contribution.

Thirdly, closeness of facilities is complementary to the requirement of the most effective use of the available (or designed) area, therefore the yield of shop floor space (t/m sq., number of products per m sq., etc.) may be increased. This positively influences capital investment which can be minimised, especially in 'green fields' projects. Size of buildings, and therefore cost of buildings, could be reduced with consequent reduction of cost of maintenance, reduction

of cost of heating, ventilation, lighting and other overheads. The resulting compact layout is more controllable and therefore supports in a better way production management functions; management control, identifying and counting of W.I.P. and products is simplified.

Fourthly, from operation management and utilisation of labour point of view, the achievement of the proper plant layout allows the most effective design of individual operations, the process and the flow.

Fifthly, the achievement of a proper facilities layout incorporating correct inspection locations in the process should positively influence quality control.

Sixthly, layout planned for ease of maintenance allows for the use of maintenance time effectively and reduces personnel requirements.

\All of the above complementary criteria show the profitable advantages of proper Factory Layout Planning.\

\Contrary to this, are conflicting combinations of criteria, which are making the task of the layout planner more difficult. The sources of conflicts occur among the needs of production technology, space requirements, space available and the overriding economic criteria.

Firstly, a conflicting situation may arise between the requirements of an ideal technological position of work stations and the real space of an industrial hall/bay.

For example, a sophisticated calculation [5,6,7,8,9] can recommend positioning work stations in a cluster to achieve the shortest possible distances between them. Theoretically this seems to be a perfect recommendation, but it could prove an unacceptable one if the width of the existing industrial bay cannot accommodate the cluster! In the same way the cluster arrangement may conflict with the spatial demands of Material Handling.

Secondly, a conflict may also arise with the width of the bay when a group or line arrangement of work stations, each of which has a different size, has to be accommodated.

Thirdly, different sizes of work stations in recommended positions may conflict with the requirements for the most economic utilisation of the shop floor area. There could also be a collision of work stations with supports/columns of maintenance steelwork etc.

Fourthly, the interrelated positions of departments, services, stores, tool cribs and the relative positions of foremen, etc., could be sources of conflict.

In order to achieve the best possible results in the final layout it is essential to compromise and establish

priorities. But priorities could vary from case to case and from planner to planner.

From the point of view of overall economy, it is the distance between the interrelated places that plays the main role. It was probably for this reason that most research effort has so far been concentrated on understanding the flow of material, in an attempt to shorten the distance of travel of Work in Progress (W.I.P.) between operations. A number of methods and relationship charts, studying mostly 'from - to' material handling, have been developed. The most widely recognised method is Muther's [4] Systematic Layout Planning. He also gives priority to the closeness of facilities, combined with the importance of relationships among facilities, rated by a unique AEIOUX rating system.

These techniques improve the quality of the layout engineer's work, but have very little impact on his productivity. New ways have only been opened by the wider implementation of computers (see Chapter 3.).

As already mentioned in Chapter 1., each project is usually divided into several project stages. Reasons could be found in the necessity of approval procedures for financing the project, strategic planning, regional planning etc., as well as in technical methodology of approximation, i.e. from theoretical outline ideas of the system, to detailed complex design and installation of the "recommended system" [4, 40].

\ Another category in Factory Layout Planning are design phases. These are logical steps in layout design methodology and could be seen represented by some well known procedures like Muther's Systematic Layout Planning, Apple's Plant Layout Procedures or Reed's Plant Layout Procedures as summarised by Tomkins and White [39].

The distinguished reality of project stages and design phases as parallel categories is unfortunately not stressed enough in Factory Layout Planning literature. Very often they are intermixed. But for the sake of methodological clarity this should be avoided.

\ The distinct differences between project stages and design phases could be seen clearly from the following definition and description of project stages; which is then followed (for comparison) by design phases. \

\ Definition of project stages:

Project stages (see Appendix I-2) are graded steps in the preparation of project documents (i.e. reports, calculations, drawings etc.). Each step gradually goes into more depth and detail of factory layout. \

In an ideal situation engineers would have the capacity, the time and the information to solve detailed problems in the early stages, as these could often influence the final economic aspects of the project.

To see more clearly the extent of the problem it is useful to describe in outline the project stages:

Stage 1.

FEASIBILITY STUDY (see Appendix I-3) defines the most economical approach to the plant layout. The production programme should be defined at this stage, sometimes with the help of typical products. The main Flow of Material, the number of machines and equipment needed, and the main areas and building(s) required should be established here, as well as manning and services. In drawings main areas and buildings are presented as block layout. A programme of all building and layout works and with the relevant economic considerations should be worked-out. Two or more alternatives are usually considered.

Stage 2.

INVESTMENT PROJECT (Appendix I-4)

studies the size of the main industrial hall(s), dimensions of bays and annexes of the plant; determines the requested production programme and flow of material; designs departments in inter-related positions, but without detailed shop floor layout and the positions of work stations and equipment. In drawings the departments are often presented as more accurately specified block layout. In the case of a new factory on 'green field', a site is selected. As above, two or three alternatives are usually considered.

Stage 3.

PROJECT and WORKING DRAWINGS

In this final project stage (Appendix I-5) all final 'capacity' calculations are made, work stations (machines and equipment) are determined and their positions are fixed in the layout of the defined building.

The project layout drawings show e.g. work stations in realistic shape, with details like anchoring bolts, and position of power supply, electrical accessories, connection to gas, water, coolant supply, etc. The Working Drawings (Appendix I-6) include all the details necessary for work stations installation and any necessary civil engineering works, e.g. if foundations are requested. The industrial halls are positioned in the general layout.

In some commercially and technically complicated cases intermediate stages are introduced, usually after the Investment Project. For example, in an 'Introductory Project' (Appendix I-7) almost everything is defined except the final and exact position of work stations inside the industrial halls. The intermediate stage is also used when the project and detailed final drawings are prepared in another country where the project is located and local subcontractors are employed. In this way the investor is saving on the cost of design work, using local draftsmen and engineers. He only hires the experts from the consulting firm or supplier who designed the previous stages of the

project. The experts, consulting engineers, supervise local staff and advise on site. This helps to secure higher employment for local people. The experts also pass on the 'know-how', which is very valuable especially for the 'Third World' countries.

\Design phases (represented here by Muther's Phases of Systematic Planning [4]) are following:

Phase I

LOCATION

Determine the location of the area to be laid out.

Phase II.

GENERAL OVERALL LAYOUT

Establish the arrangement of the area to be laid out.

Phase III.

DETAILED LAYOUT PLANS

Locate each specific piece of machinery and equipment.

Phase IV.

INSTALLATION

Plan the installation, seek the approval of the plan, make the necessary physical moves.~

To illustrate the difference : In Feasiblity Study it is

not necessary to use all design stages. Overall layout or a block layout in drawing presentation is all that is needed. In the Investment Project the situation would be similar.'

The difference in the position of 'Location' in project stages and design phases can easily be seen. Muther [4] places the 'Location' first, while the present work places the 'Location' in project stages, in Stage 2. - Investment Project.

The approach here is different for the following reason: Prior to the selection of any plot or place (location) the main capacity calculations, requirements of areas, and a block layout of facilities have to be completed. The engineer responsible for the selection of a plot must have this information in hand together with details of max.loads (bearing loads) etc., otherwise the selection of the plot cannot be carried out with full responsibility. Not furnishing the information to the engineer could be costly: completely inadequate plot could be selected, which could result in expensive alterations e.g. foundations of heavy machines and building columns might have to be supported by piles etc..

Hence project stages are influencing the activity in design phases. This is apparently the reason why Tompkins and White ([39] - Fig 1.1) are putting their Facility Location in facility planning hierarchy on a completely independent

level and position.

Further, in contemplating the design methodology and procedures only, for every layout, Muther [4] lays down three fundamentals:

Relationships - the relative degree of closeness desired or required among things;

Space - the amount, kind and shape or configuration of the things being laid out;

Adjustment - the arrangement of things into a realistic best fit.

The above three fundamentals have a special place in CAFLAP development.

In CAFLAP, the relationships are seen in dynamic and spatial terms (see 4.2).

From the production point of view, the dynamic/activity relationships are expressed in the 'technological' positioning of work stations to suit best the Flow of Material (requirements of the most economical production).

With the help of Nugent, Wollman and Ruml's [38] ideas, 'Technological' positioning can be defined as the optimal specification of which facilities are to be adjacent in the final layout without regard to the area or shape of the

individual facilities.

The spatial demands are seen as the total amount of spaces to be accommodated in the building, which include the space needed for work stations and equipment, and some other spaces.

NOTE:

Here and in the rest of the thesis the terms 'space' and 'spaces' are used. In 3-D CAFLAP connotations (contrary to Muther's [4] spaces which are actually 2-D areas) they have been used to express the situations and spatial relationships (see 4.2).

The arrangement of work stations and equipment in the 'technological' order and realistic spatial position in an industrial bay, is the main task in Factory Layout Planning. Here also lies a source of conflicting situations and requirements, as dicussed above, and more:

Firstly, the work station itself has to be designed as a safe and comfortable place allowing and supporting all functions of the machine tool or equipment, and effective work of the operator(s). The design itself carries conflicts between safety and the requirements for most effective operation.

Secondly, the requested position of work station in the real

space (building) could be in conflict with maintenance requirements.

Thirdly, the requirement for closeness of facilities could be a trigger for collision among functions, operations and maintenance of other facilities.

CAFLAP has been developed with all this in mind (see Chapter 4.).

2.2 EXISTING TECHNIQUES USED

For the study and design of Activity Relationships and the Flow of Material, a number of methods, mostly charts, have been in use (e.g. From-To charts, REL charts etc.).

On the basis of these charts, in relation to 'technological' (Appendix I-8) positioning of work stations, some computerised methods have been developed. The most important of them are discussed in Chapter 3.

From the point of view of graphical presentation of the arrangement of work stations in work shop situations the Space Relationships are the most important. Here below are outlined the main techniques for design of Space Relationships as historically developed, and as also presented even in the most recent literature ([39]-published in 1984 and [58] published in 1985).

Originally ordinary 2-D drawings were used for Factory Layout Planning. Work station after work station, position after position, had to be drawn individually. This often meant repeating similar shapes and situations, in the same way as in the days of the Venice Arsenal, or in the manner of Michelangelo Buonarroti's civil engineering layouts. There were no facilities to ease the draftsmen's work. This demanding and slow technique was improved by the use of two dimensional templates of work stations. These were either

copied (under tracing paper) into a layout, or held in position by magnetic 'operators' on a magnetic table where a drawing of the industrial hall was fixed. Where the magnetic table technique was used, a photograph of the layout was taken by an overhead camera. This process was repeated after each change, introducing alternative layouts. This technique was much faster than drawing layouts with templates under tracing paper. But all the extra equipment like cameras, special overhead stands, lighting and finally engaging a qualified photographer on the job made this method expensive. Also the extra space needed and time lost by the layout engineer involved, e.g. queuing for the magnetic table and the photography, led to this method being abandoned.

The two dimensional methods had some disadvantages especially when presented to customers or non professional top management lacking knowledge of reading drawings. Also, these methods are not able to show some of the space utilisation problems. Neither are they sufficient for collision course finding among work stations and building, maintenance steel-work, columns footings (foundations), ducts, etc.. Therefore 3-D model 'templates' were introduced.

This 3-D method, deploying wooden, plastic, or metal models, is still in use for some specialised cases, e.g. piping. This, however, is a very slow and expensive method. To

manufacture models of work stations and equipment, usually in 1:50 scale, is a straightforward job if wood or plastic materials are used. But storing and issuing them to layout engineers, as well as the manipulation of models of work stations within a 3-D model of an industrial hall is complicated. Plastic models of work stations, equipment, operators, etc., are usually subcontracted. For wooden models of industrial halls, maintenance steel-work, pipelines, etc., there have to be adjacent workshop facilities. This can be a very undesirable mixture of activities : design work vs. manufacture. According to good engineering practice, and ergonomic and synergetic rules (see 4.2), such activities should be kept separate.

When a 3-D model is finally built, photographs of the arrangement are taken in a similar manner to that needed for the magnetic table method.

With the development of plastic drawing sheets (Mylar) known as 'skins', a relatively very good technique, using 2-D templates fixed after manual positioning by double-sided sellotape, has been invented. This template on 'skins' technique, (see Appendix I-12), enables the engineer to change position of work stations several times to investigate alternatives. The templates of work stations are usually drawn in 1:50 scale on a thinner plastic tracing foil. The 'skins' have a pre-printed grid (250x250mm in 1:50 scale) to ease the positioning of templates. For

buildings, pre-printed sellotapes, indicating walls, etc., are used.

The 'skins' are reproduced in the same way as ordinary tracing paper drawings. These 'skins' remain relatively durable. However, the dust catching residue of the sellotape creates stains. Because of their relative weight and stiffness, the 'skins' are stored hanging in purpose-designed steel cases. Overall ease of manipulation of 'skins', so similar to familiar tracing paper, makes this inexpensive method of producing 2-D layout models, sometimes called 'templates and tapes', very popular. Tompkins and White ([39-published in 1984!]) stated:

"The most common method of creating layout plans for larger facilities is to use templates and tapes."

Also Konz [58] published in 1985, described this technique in great detail.

Unfortunately none of the above discussed manual methods is fast enough, and none of them assists the layout engineer in the direction of providing economic space utilisation. They do not help in the coordination of layout tasks (system - Hall, Bay, Work Station ... Mechanical, Civil, Piping, Electrical, etc.); nor do they facilitate collision course finding.

All the layout work must currently be carried out intelligently and unaided by the layout engineer. The quality of projects therefore depends on his experience, level of education and ability to consider, assess, and foresee the technological situations in a spatial context. This also requires great engineering imagination!

The methods, described above, show how inadequate are the tools which the layout engineer is using for his highly creative and, at the same time, complicated yet repetitive assignments.

Even in a new factory situation there must be a continuous re-layout and re-arrangement activity in progress [2]. The repetitiveness of layout tasks, the need for changes of layout to be carried out in the shortest possible time, and the requirement for finding the most effective arrangement by consideration of alternative layouts, have led to the development of new methods and techniques in Factory Layout Planning.

3. COMPUTER AIDED SYSTEMS PRESENTLY AVAILABLE

3.1 INTRODUCTION

In order to avoid any duplicity of research and with the view of a possible utilisation of some of the existing computer programs for CAFLAP, an extensive literature search has been undertaken. (See Chapter 10.)

One of the sources quoted is Location and Layout Planning bibliography [48] by Domschke and Drexl, in which the authors include layout planning and any relevant systems in a wide field of "location theory".

According to them, location theory can be divided into macroeconomic and microeconomic location theories.

In macroeconomic location theories industries, economic sectors, etc., are placed 'in space'. The microeconomic location theories are further divided into plant location and plant layout theory.

Publications whose authors regard transportation cost or travel time as main location factors are described in the bibliography as transportation orientated, and of a normative (quantitative) type. This group is further divided into publications dealing with plant location and

those which deal with public facility location problems.

According to Domschke and Drexler the main objective in plant location is to minimize the sum of cost (minisum problem). In public facility location the objective is to minimize the maximum distance, time, etc., which a user of a facility has to accept (minimax problem). Within both types the factor of different distances occurs. Dealing with this there are network orientated models (where the shortest distance between two points is considered - Operation Research), and models assuming that travel takes place on a plane (all points on the plane are potential locations).

Plant layout theories try to optimize the location of facilities within a building or plant, e.g. location factors are studied.

Authors have divided publications on location and layout planning into 13 chosen subjects. (The current work would fit into the class "M"-Thesis). Future trends in the development of the microeconomic location theory are predicted by the authors as mainly concerned with the development of software tools based on computer graphics. (This is the line which CAFLAP follows.)

Nugent, Vollmann and Ruml [38] are considering "the optimal specification of which facilities are to be adjacent in the final layout without regard to the area or shape of the

individual facilities", as most important step in the complete layout process.

With the expansion of the use of computers, many attempts have been made to find the algorithms for the most suitable 'technological' positioning of work stations, related to each other in the sense of the most economic flow of material. Relationship charts of activity areas (based on the flow of material and service departments) have created the basis for a number of computerised methods in Factory Layout Planning.

According to Tompkins and White [39], techniques for computer aided layout may be classified by the method of recording flow among departments and by the method of generating the layout. The flow may be expressed as a quantitative record in a FROM-TO chart, or as a qualitative one recorded in an activity relationship chart.

The method of generating layout may vary from computerised algorithm developing block layout, presented by symbolically marked squares, to computer graphic presentation of detailed facilities in 3-D.

Moore in his international survey [30] in 1974 is using Wollmann's [41] classification of computer programs for facilities design as either 'construction' type or 'improvement' type. According to him the construction

algorithms build or construct a solution from raw data; the improvement algorithms require a feasible solution as part of the input.

In Moore's survey eighteen programs are classified by authors as construction type, seven as improvement type, but five are not classified either way. (As Moore's classification fits better for block plan plant layout algorithms, it is less suitable for classification of other systems. If Moore's approach should be applied to CAFLAP it would fit in his class 'Others', although this class was originally created for a different purpose.)

Below are reviewed and evaluated some classical types of methods/programs from the past, which are still quoted in recent literature. Tompkins and White in 1984 [39] are actually presenting CRAFT, COFAD, PLANET, CORELAP AND ALDEP. Their selection is identical with programs chosen in Computer Aided Layout: A User's Guide [57], which quotes them as "techniques already proven to be usable to the facility designer". Konz in 1985 [58] also finds it useful to include in his book CRAFT, COFAD, CORELAP, ALDEP AND PLANET.

These classical types of program are followed by new tendencies and ways in tackling Factory Layout Planning problems.

3.2 COMPUTER AIDED SYSTEMS

Many programs and commercial software packages currently in the field are approaching plant layout as a pure operation management problem of 'sequencing' the departments or work stations, in order to receive a final block layout with shortest possible distances between the interrelated facilities. As described in the following, many of them are building on the original ideas of Armour-Buffer [5,6], Lee-Moore [8] or Apple-Deisenroth [9].

3.2.1 CRAFT

In 1962 G.C.Armour and E.S.Buffer presented their work "A Heuristic Algorithm and Simulation Approach to Relative Location of Facilities" which resulted in CRAFT (Computerised Relative Allocation of Facilities Technique - 1964), a typical improvement type program for block plan plant layout [5,6,7]. The program was developed for process (functional) layout. This method is based on the algorithm to minimise Material Handling (M.H.) costs incurred among all departments. M.H. cost is defined as the product of flow, distance, and unit distance travel cost, which are the main input data. An initial layout has to be given and must consist of a group of unit squares to represent each department. The procedure first determines the centroids of departments. Then CRAFT evaluates the given layout, calculating the rectilinear distances between the

departments and stores it in a distance matrix. Then M.H. cost is calculated as product of data from FROM-TO chart (flow), distance matrix and move cost matrix.

Production departments are identified by assigned capital letters. CRAFT next considers departmental interchanges and evaluates what the effect will be if locations are interchanged. The program switches the positions of the departments to achieve, through an approximation process, maximum economy in Material Handling. M.H. costs are compared. The process continues until no more improvement can be made by pairwise exchanges. Only departments with common borders or of the same area are considered for exchanges of locations.

On final computer prints the inter-related positions of departments are marked by lines, composed of the assigned capital letters, delimiting the areas of individual departments. CRAFT program does not guarantee that the layout with lowest M.H. cost will be found unless all possible interchanges are considered.

Some assumptions made in the CRAFT algorithm could be viewed critically. Francis and White [16] commented that:

Firstly, the use of centroid locations in measuring distances, might not be realistic for some practical applications. This way some unusual layout designs could be obtained, resulting in crooked aisles.

Secondly, the assumption that M.H. costs are significant,

known and linear in distance travelled. In the real layout this could sometimes be of small significance.

The comments on problematic assumptions are important for the user. He should see CRAFT as a conceptual tool for the design of block layout in some early stages of projects or search phase of design.

Nugent, Vollmann and Ruml in 1967 [38] compared CRAFT with newly developed similar programs H63 and HC63-66. They compared the goodness of the solutions reached and computational efficiency. The results obtained by the authors show that CRAFT runs more slowly than HC63-66; the latter produces solutions of slightly higher quality. Despite some positive results achieved by programs H63 and HC63-66, none of them were quoted in literature studied and failed to appear even in Moor's survey [30].

In spite of the above criticism Francis and White in 1974 [16] finally have a word of praise for CRAFT:

"Although there are other improvement algorithms, in general none have been shown to be superior to CRAFT in layout design."

3.2.2 COFAD

From the family of similar improvement programs, at least COFAD should be mentioned here. Developed by Tompkins and

Reed [43], COFAD -Computer Facility Design- is basically a modification of CRAFT.

COFAD allows the use of move cost for a variety of M.H. systems, i.e., each alternative layout is also considered from the point of view of the M.H. method to be selected.

Input requirements are the same as for CRAFT, expanded by the cost of M.H. system, and a percentage of utilization of M.H. equipment per move. COFAD enables the selection of the least-cost layout and in parallel the selection of M.H. method with minimal cost of M.H. equipment.

The program starts with procedures identical to CRAFT, i.e., improving the initial layout. Then the cost of each move with M.H. method alternatives is determined. Flow (FROM-TO chart data) is constant. Next comes determination of a minimal cost M.H. system which is followed by a search for M.H. equipment whose utilization is good.

In the next phase reduction in total cost is sought. If in the COFAD process no reduction of total cost can be achieved, the program is terminated or flow volume inputs are changed. This is done for following reasons: to confirm that the found solution is a steady-state solution, and to check the sensitivity of design to the flow data. If the steady-state is not confirmed, COFAD is restarted with a new apportioning of cost of M.H. system to individual

moves. This loop continues until the requested (steady-state) solution is obtained.

The assumptions inherited from CRAFT (as discussed above in this connection) are inevitably sources of the same critical comments. Here the situation is made even more complicated by the variety of M.H. methods considered, and their costs due to the variation of market prices. Another complication arises in connection with the collection of data regarding the realistic percentage of utilization of equipment, which is always difficult to establish.

Further programs of a similar type in the improvement class quoted by Moore [30] are: GRASP, KONUVER, LAYADAPT, OFFICE, PREP and The Terminal Sampling Procedure. In 1978 Tompkins and Moore [57] are adding to this list another two: COSFAD and SET.

3.2.3 CORELAP

As a classical example of construction type program [30] could be seen the digital computer program CORELAP [8]. CORELAP-Computerised Relationship Layout Planning- was developed by R.C.Lee and J.M.Moore in 1967 to design block plan plant layout economically. It is a job shop orientated procedure.

In comparison with CRAFT, which is using flow consideration for its procedures, CORELAP procedures are based on activity relationships (originally suggested by Apple[10]). Activity relationship (REL) charts are using A, E, I, O, U, X, rating convention [4, 10].

For input the following data are required:

- the number of departments (N)
- the data from REL chart
- the area requirements for each of the departments
- the ratio of maximum length of the building to width.

The heuristic algorithm starts with areas having the greatest sum of relationships. The departments with the highest total closeness rating (TCR) is placed in the centre of layout matrix. The program then interactively adds other areas, one at a time, in such a way as to maximize the attainment of the desired relationship. The final output is in the form of layout matrix. On the print of the final layout, whole areas of departments appear covered by identifying numbers, each representing the unit square it occupies. The areas which are available but not occupied are marked up by zeros. Layouts designed by CORELAP are often of an irregular shape. To fit a conventional shape of a building, this has to be adjusted manually.

Similarly to CRAFT, CORELAP should be considered as a conceptual tool for the design of block layout in some early

project stages or research phase of design.

3.2.4 PLANET

Another construction type program often quoted in literature is PLANET - Plant Layout Analysis and Evaluation Technique- developed by J.M.Apple and M.P.Deisenroth in 1972 [9,7,39]. PLANET was also developed for design of block layout.

For input the following data are required:

- material flow data (i.e.entries from the FROM-TO chart)
- move cost matrix
- distance matrix

PLANET uses three alternative methods for specifying material flow data. In the design procedure three different layout construction algorithms are used.

The three methods of specifying material flow data are following:

The first one specifies product sequence by department for each part, together with cost per move per unit of distance for each part. The cost is often input as unity, because it may not be determined. PLANET then develops a flow-between cost chart, which indicates the cost of movement between pairs of departments. This is then used in the construction algorithm.

The second method inputs material data directly from FROM-TO chart, which is then converted to a flow-between cost chart.

The third method of inputting flow data is that using a penalty matrix. The penalty input between two departments is an indicator of the importance of closeness of the departments. The matrix can also indicate the difficulty and relative frequency of material movements between departments, or indicate the relationship data. A placement priority scale 1 to 9 is used (9 is the lowest priority). The layout is not predetermined.

The three construction algorithms used in PLANET are best described as follows:

Method A selects departments according to flow-between costs, starting with pairs of highest priority group with the highest flow-between costs. The next department to be selected is that from the highest priority group and with the highest flow-between cost with any department already placed. In this fashion the procedure continues until there is no department left unplaced within the layout.

Method B starts in a similar way to that of A, but the next department to enter is chosen from the highest priority group and has the highest sum of flow-between costs with all selected departments. This continues until no department is left unpositioned.

Method C starts with the department in the highest priority group that has the highest sum of flow-between cost with all other departments. As the next entry, method C selects the department in the highest priority group that has the highest sum of flow-between cost among all other departments. The procedure continues until no department is left unpositioned.

The layout routine always starts with the two top selected departments placed in the centre of the layout. Any following department is placed in a manner which will minimize the M.H.cost, using a trial-and-error method.

PLANET often generates layouts that do not suit a uniform building shape, so deficiencies are similar to those of CORELAP. Layout must be manually adjusted but this cannot be evaluated by PLANET as feedback. PLANET can be considered as another conceptual technique for initial stages of projects or search phase of design.

3.2.5 ALDEP

ALDEP -automated layout design program- was presented by Seehof and Evans in 1967 [54]. As classified by Tompkins and Moore [57] this is another construction type routine.

First the authors studied the attributes which condition a better layout. They suggested a scoring technique, and used

a matrix of weighting factors which indicated a desirable closeness of departments. The layout score is the summation of the preference values for the adjacent departments. No details of preference values (factors), or scoring techniques have been published by the authors. However, Tompkins and Moore [57] used in their assessment of ALDEP Muther's [4] A,E,I,O,U,X relationship rating.

The main input data are:

- number of departments and their square footage,
- relative departments location preference,
- layout of the building (building dimensions, etc).

ALDEP creates a random layout and scores it. This is repeated several thousand times to reach the best scores. Compared with CORELAP, ALDEP produces many layouts and rates them leaving the selection of the best alternative to the user; while CORELAP attempts to produce one best layout. Block layouts are produced by a plotter. Selection and adjustments for the final layout are done manually. ALDEP can be only used for block plan layouts with predetermined aisles, stairs and other amenities. ALDEP cannot be utilised for a detailed layout or 'technological' positioning of work stations, and therefore cannot be used as an entry programme for CAFLAP.

It is worth quoting that, in 1979, Rosenblatt suggested a new algorithm [60] which, as he claims, could be used with

ALDEP. He uses a combined quantitative and qualitative (subjective) approach to the plant layout problem. His supposition is that quantitative and qualitative approaches are formulated as a quadratic assignment problem. Both have the same feasible region, therefore the two methods can be combined. His multi-objective formulation, minimizing total flow cost and maximizing total closeness rating, is made possible by the introduction of weight assigned to the total cost flow and total rating score. Rosenblatt suggests a graphical solution to find the 'best' layout. The 'best' layout lies on the intersection of a line, established by the weights, with a point on a 'discrete efficient frontier', given by positions of efficient layouts in the graph.

Moore in 1974 [30] quotes in this class of programs (using construction algorithms) another 16 programs. They are: CASS, COLO2, COMP2, COMSBUL, DOMINO, GENOPT, IMAGE, KONUVER, LAYADAPT, LAYOPT, LSP, MUSTLAP2, PLAN, SISTLAP AND SUMI. In 1978 Tompkins and Moore [57] added another two: Hiller-Conners and RMA Compl.

A number of further programs based on the above mentioned classical types have been developed. Some authors tried to eliminate the disadvantages mentioned above, some tried to develop the system in a more universal way or to extend their use into other areas.

Examples of the latter intentions are MODULAP and SPACECRAFT.

3.2.6 MODULAP

Real situations, influenced for example by transport routes, were not considered previously. The development of new more practical methods was then begun, e.g. MODULAP [11].

MODULAP, contrary to CRAFT or CORELAP, measures the real distances alongside the transport routes. However, it still cannot guarantee the positioning of all the departments along the transport routes, and the layout engineer has to define the required additional routes intelligently. MODULAP first designs an ideal layout and then, in a second round, converts the ideal layout into a feasible alternative. Similarly as all the above quoted methods, MODULAP is also more suitable for block layout and the positioning of departments, rather than for the more detailed positioning of work stations.

3.2.7 SPACECRAFT

SPACECRAFT was developed in 1982 by Roger V. Johnson [44]. It is a construction type program based partly on CRAFT method. Johnson is trying to minimize the total variable cost of movements (M.H.) between facilities in multi-floor

buildings.

The aim of the program is to locate the departments in a feasible way, and the total time of journeys on N floors is minimized. Johnson considers the volume or number of journeys from department 'i' to department 'j' as constant, but the time of a journey will depend on the location of departments 'i' and 'j'. The main difference between the multi-floor problem and the single-floor problem is, according to him, the nonlinearity of transportation times.

For input, SPACECRAFT requires:

- building size data (number of floors, number of floor types, number of columns, rows of modules and definition of floor types),
- travel times between each pair of floors, for each inter-floor access route,
- travel times between each pair of modules within each floor type,
- travel times between each module on a particular floor type and each access point,
- department information (number of departments, a code number of departments, department titles, volume of movements between each pair of departments),
- Initial layout and its restrictions and any requirements, or restrictions of any department.

SPACECRAFT, in a procedure very similar to CRAFT but with

the difference caused by the nonlinearity of transportation times between floors, produces:

- table of movement times between each pair of floors,
- table of movement times between each pair of modules on each floor type,
- table of movement times between each module and each vertical movement point on each floor type,
- table of volume of movement per period between each pair of departments,
- table of single journey movement times between each pair of departments,
- table of single journey movement times between each pair of departments which have a nonzero volume of movements,
- table of the dollar cost of a single journey between each pair of departments which have a nonzero volume of movements,
- table of total per period movement time between each pair of departments,
- table of dollar cost of the total per period movement time between each pair of departments,
- summary of total per period time and cost of movements originating from each department,
- location data listed for each department,
- location data listed for each floor,
- layout grid of the building.

The graphical presentation of layout designed by SPACECRAFT is similar to that of CRAFT. But the positions of

departments are indicated by symbolic numbers instead of the letters used for CRAFT. The numbers are printed in a grid given by column numbers, module row numbers, and floor numbers. This grid feature could be seen as an improvement on CRAFT and the method can, similarly to CRAFT, be used for the development of block layouts. However, SPACECRAFT cannot guarantee an optimal solution. A poor layout will result in higher utilization of elevators.

This method was commented upon by Jacobs in 1984 [45]. He compares SPACECRAFT to a program known as CRAFT-3D developed already in 1975 [46]. Jacobs considers the programs as very similar, with the following difference. SPACECRAFT considers all the travelling distances parallel to the department edge, not diagonally, while CRAFT-3D calculates with rectilinear distances measured between department centroids.

In spite of their discussion of space and 3-D programs, SPACECRAFT and CRAFT-3D are both actually only solving 2-D layouts on different floor levels.

In comparison with CAFLAP (see Chapter 4.) they are actually only 2-D and symbolic in presentation. They also have no facility for 'space management', automatic positioning in 3-D space with collision course finding, etc.. This comment is also true for CRAFT, COFAD, CORELAP, PLANET and MODULAP programs.

3.2.8 SHAPE

SHAPE -Selection of material handling equipment and area placement evaluation- program [47], was presented by Hassan, Hogg and Smith in 1986. The aims of Shape resemble those of CORELAP (3.2.3) or PLANET (3.2.4). The intention was to develop a functional layout with minimum interdepartmental movement costs. SHAPE tried to find the 'best arrangement and configuration of departments' [47]. This was considered in terms of a real area shape.

SHAPE used warehousing methods for locating a new single item in existing stores. This was a new approach to plant layout design. SHAPE divides the layout into a mesh consisting of numbered unit squares (1 to N). Constraints are:

- Departments (n) are occupying a number (compact collection) of unit squares (A_i),
- Each unit square in the mesh is to be occupied by only one department.

SHAPE allocates the unit squares for each department and tries to minimize interdepartmental movement costs. In a similar way to CRAFT and PLANET, SHAPE uses a quantitative departmental relationship (FROM-TO chart), with the difference that each flow value is classified as major or minor and is defined by the user. SHAPE determines the order in which departments enter the layout according to the

sum of the major flow values. The first selected department is placed in the centre of mesh. The rest of departments are placed around according to their flow values. Departments with the largest flow values are near the centre; those with decreasing values are placed in the direction towards the perimeter.

Similarly to CRAFT, centroids of departments are established and the rectilinear distances between the centroids are used. The movement cost here is the product of average distance and flow between placed departments. The placement procedure is similar to PLANET and is extended by a process orientating departments in the layout according to the minimum movement cost. The process allows the shape of departments to be changed by influencing objective functions of the model; i.e. the flow-distance product controls the selection of unit squares and therefore changes the shape of the departments. In the final layout every department is of an optimum shape, while the least movement costs between departments are secured.

In spite of the authors' original claim about SHAPE dealing with "selection of material handling equipment..." no selection is discussed in the paper presented [47]. SHAPE is also compared in the paper with PLANET and CRAFT, but if selection of M.H. equipment is considered it should rather be compared with COFAD (3.2.2). The comparison with PLANET, provided by authors in detail, shows SHAPE's advantage of up

to 23% reduction in movement cost.

The final layout is presented as a 2-D layout matrix of unit squares. Each unit square represents a particular area of the department, coded by a number. Thus SHAPE can be used, similarly to the previously described programs, as a conceptual technique for the initial stages of project or search phase of design.

Unlike CAFLAP and in company with the other programs discussed here it also has no facility for 3-D presentation, no facility for detailed layout or collision course finding, etc.. Because of its otherwise unique ability of changing the layout shape it can be used for block layout, but is not suitable for 'technological' positioning of individual work stations and therefore cannot be used as an entry program for CAFLAP.

The disadvantages of SHAPE for practical layout are similar to CORELAP, PLANET and CRAFT. Unusual layout designs can sometimes be generated by SHAPE and the resulting crooked aisles cause difficulties in practical M.H. Moreover, placement of the work stations in the detailed layout may prove to be difficult, if not impossible, because of the changed shape of departments.

SHAPE should be seen as a most recent attempt to improve the existing line of heuristic construction algorithms based on

the classic ideas of Lee and Moore in the sixties.

3.2.9 RUGR

In parallel with the construction and improvement types of programs, Moore introduced, in his survey [30], another class of programs: graph theory [50]. A classical representative of these types of program is RUGR, already presented by Krejcirik in 1969 [12]. Using the graph theory Krejcirik tried to consider the plant layout problems within the limits of an existing building and given areas. His RU-Program is designed for finding the optimum arrangement of spaces which lie alongside a corridor. He was partly inspired by Armour-Buffa's CRAFT program but, contrary to this program, his arrangement of spaces (e.g. departments) follows a direct line, distributing them evenly within the building, without any waste of space available.

Krejcirik's RG-Program is intended to find mutually related locations of spaces on one plane, while the RR-Program is designed for the minimization of total area of the layout, in order to achieve the most economic size of the building. RUGR is suitable for 2-D plant layout block plans.

Seppänen and Moore in 1975 [53] reviewed the graph theory. They found that it is not always possible to represent the plant layout situation as a planar graph. String processing algorithms, using Novelty Luggage problem method, were

suggested as an alternative approach. But this method has not been further developed and implemented using a computer.

3.2.10 MATHANDL

Very important techniques for the 'technological' positioning of work stations have been developed by the University of Strathclyde.

Program MATHANDL [13] introduces a new technique of arranging work stations into lines instead of clusters, as it is in CRAFT and CORELAP, and removes the shop floor limitations which are inherent in these methods. To achieve this, Numerical Taxonomy, a computerised approach to biological classification has been adopted to develop a computerised algorithm. However, the developed program is at present not available for multiple machine departments. The method of numerical taxonomy was further studied by Carrie [51]. He also observed [55] that the technique of numerical taxonomy provided an analytical procedure similar to the intuitive one of the plant layout engineer. For the Layout of Multi-Product Lines [14], he has proposed a computer method of preparing alternative line layout designs. The method considers work flow and work load and proposes a three stage procedure:

- 1) Construction of a 'complex' line which contains enough work stations at appropriate positions to allow every part to be processed without back-tracking;

- 2) Identification of those machines which do not have an economic work load, and eliminate them by re-routing the operations planned to be performed on them to other machines in the line. This is done in an interactive manner producing several possible designs;
- 3) Comparison of the alternative designs by computer simulation.

The simulation model was written using the GPSS package [26].

3.2.11 PLANTAPT

PLANTAPT - a prototype integrated package for layout planning analysis- was presented by Carrie in 1977 [54]. This general purpose package is intended for medium size plant layout and group technology applications. PLANTAPT's file system holds following data:

- for a number of independent projects,
- on component parts,
- on plant resources, machines or processes;

it is designed to:

- permit variations in the data,
- permit max. flexibility in the data layout in input documents,
- store and retrieve results of application programs.

PLANTAPT's application programs are designed for:

- specifying the component parts to be examined,
- specifying the machines to be considered in the analysis,
- analysing group technology code numbers (Opitz),
- analysing the operations carried out on parts,
- developing the layout of group flow lines and rationalising operation sequences,
- analysing material flow or activity relationships for planning overall layout or detailed layout.

PLANTAPT programs first analyse the situation and then, in a grouping operation, design parts groups, and corresponding groups of machines. If no grouping is necessary, each item becomes a group of one. A facility for operation sequences is provided. If a multiple-product flow line is being considered, machines for the flow line are selected by a specialised program.

Integral parts of PLANTAPT are programs called TRAVEL and LAYOUT. TRAVEL computerises relationship data, while LAYOUT develops a maximal planar subgraph (the theoretical ideal layout) from which a practical plant layout can be designed.

A graphical extension of PLANTAPT was described by Carrie in 1980 [55]. He used PLANTEC, an interactive package for plant layout, developed by National Engineering Laboratory [56]. PLANTEC stores and supplies 2-D shapes of buildings and machine templates. Coordinates of the shapes, relative to a convenient origin, are measured and filed. This can

also be done by digitising the shapes. Similarly, positions of machines in the layout are given by coordinates and scale factors can be given. The layout is presented on VDU and manually adjusted according to engineer's discretion. When the layout reflects the theoretical ideal layout best, the engineer can instruct the computer to provide a large size plot of the layout drawing.

Utilisation of Strathclyde's techniques MATHANDL and PLANTAPT is suggested for the benefit of CAFLAP (section 4.3).

3.2.12 A large-scale spatial allocation problem

A large-scale spatial allocation problem was formulated in 1980 by Liggett [61]. He used a quadratic assignment approach combined with a 'partitioning scheme'. This very interesting method allows the efficient solution of layout problems, positioning up to 1000 departments, shortening the computing time substantially. The 'partitioning' approach solves a layout at a set of nested levels. The highest level (master partitioning problem) assigns activity modules to subsets of locations. These are grouped into zones or 'partitions'. The method used for selecting the assignments in levels considers the immediate costs of assignments (activities to locations) and the restrictions imposed on possible choices for future assignments. Probability theory is used to predict which assignment would most likely

lead to an optimum solution, and therefore which is the most suitable as a possible future choice.

This partitioning method is said to be very effective and computer time saving. It is appropriate for architectural space allocation but unfortunately it leads to irregular shapes of departments, and on a much higher scale than in CRAFT (which is the program used by Liggett for comparison). The method is therefore much less suitable for mechanical engineering application.

3.2.13 INLAYT, S-ZAKY (an interactive approach)

An interactive approach to construction and improvement procedures was described by O'Brien and Barr in 1980 [34]. They tried to overcome some problems which are inherent in the above quoted procedures, by introducing the user's participation in the selection process. Program INLAYT is designed for the construction of initial layout for a new factory, or improvements in an existing one. The improvement procedure, based on program S-ZAKY, is asking the user to evaluate the 2-D layout on VDU.

INLAYT analyses the flow of material between facilities and suggests to the user groups of facilities and priorities to select for positioning. The user then has to position the facilities in the layout manually. The procedure disregards the actual areas required, and is concerned with relative

location only. INLAYT does not produce the final layout, it only provides the initial input to the improvement procedure S-ZAKY.

Input data into program INLAYT are following:

- The number of facilities, their names and identification numbers.
- The spatial array of building or site.
- The weighted flow of material between facilities.
- A flow factor (a control variable specified by the user).

The order of departments is produced by the program and stored in a matrix organised according to maximum values of weighted flows. Facilities are assigned to a space location grid by the light pen.

The improvement procedure S-ZAKY must start from an initial layout. This can be produced by INLAYT, or the existing layout or any other proposal can be used.

Input data required:

- The name of each facility.
- The area of each facility.
- The relative location of all facilities.
- Details of fixed facilities.
- The coordinate positions of all machinery.
- The coordinate position of material set-down and pick-up.
- The orientation of set-down and pick-up with each facility.

- Estimates of cost of relocating each facility.
- The cost of investment capital.
- The lifespan of the programme being considered.
- Control variables.

The authors claim that the improvement algorithm S-ZAKY is superior to other available algorithms. The main reason is that they interchange three pairs of facilities instead of two, as CRAFT and other programs do.

The 2-D layout is presented on the screen together with the total M.H. cost. Material flow pattern between set-down and pick-up can be superimposed on the layout. Series of questions are asked regarding further procedures required. In the case of exchanging facilities the program will reposition aisles. The rearrangement of facilities is left to the experience of the user, who can move facilities (2-D templates) manually by the light pen. The improvement layout is assessed by computer. The procedure continues until no more improvement can be achieved. Total M.H. cost which is the prime factor in this procedure is compared with the cost of physical repositioning of facilities. The ratio of these costs indicates the economy achieved by the changes. If no requested economic effect is achieved, the relay layout procedures could be resumed and the process is repeated. The procedure can handle up to 100 facilities but all areas must be rectangular, and the system of aisles must be rectilinear, which is a substantial limitation.

The INLAYT-S-ZAKY method has certainly brought a new approach to factory layout planning. Unfortunately there does not seem to be any independent assessment of the method yet published. There are also limitations similar to other comparable methods e.g. the inaccuracy of the input data on M.H. cost, installation costs, etc..

Kaltnekar in 1980 [62] considers three groups of criteria for layout decision making: limiting, mutually influencing, and marginal conditions. These criteria dictate approaches and Kaltnekar reminds the reader that most of the literature mainly considers the relationship between layout and material flow while other factors are ignored. To balance this he suggests it appropriate to study the above three groups of criteria:

Limiting conditions are those which cannot be changed (i.e. market, sources, etc.).

Mutually influencing conditions are those which can be changed (i.e. M.H., flexibility of layout, outside transport, building construction, conditions for the employees, the mutual influence of different parts of production system, etc.).

Marginal conditions are all conditions surrounding the production system (i.e. the social order, disposable workforce, financial possibilities etc.).

Because of the large number of different influencing

factors, the criterion of minimization of particular functions or their costs is used. Kaltnekar's critical observation that every method offered optimizes a model, and not the real state, is a crucial one. His improving algorithm only emphasizes that the result is still far from a satisfactory solution.

Prof. Lockyer [21] in 1981, when assessing the existing computer aided layout planning systems, is quoted as saying that:

"...computer programs may assist the planning function by avoiding an oversight and this is a common experience when using computers, in that the preparation of input data enforces a discipline which is often useful. It is the author's experience that layouts are currently, in fact, prepared entirely manually, and his belief that the use of the computer in this area will, for many years, be extremely limited."

In this rather unsatisfactory situation, new attempts to ease the layout engineer's work were made, especially in the area of simulation and systems using computer graphics.

3.2.14 SEE WHY (FORSIGHT)

In 1984 B.H. Hollocks [25] suggested a new approach to plant layout problems through computer simulation. His

program FORSSIGHT experiments on 'real world' layout situations. The engineer may change the layout situations and the program finds out the influences of the options, before any decisions (changes, purchase of equipment etc.) are made.

The method was originally developed at British Steel for reflecting a course of activity on physical mimic displays. The computer simulation run was valuable for giving a fuller understanding of the behaviour of mimic displays in specific circumstances. It is claimed [25] that the FORSSIGHT program "enables an accurate computer model of real world production plant to be constructed quickly and easily". It gives production statistical results and can produce an animated view of the model in operation. FORSSIGHT also enables the user to change operating parameters and to observe the results. Departments or work stations are presented as 2-D blocks (as is usual in mimic diagrams), but without any real shop floor area or space considerations. FORSSIGHT has recently been renamed SEE WHY: it is a good package for the study of cost effective production flow.

3.2.15 UA1, UA2, UA3

From the range of other simulation programs it is worth mentioning programs presented by Driscoll and Sayers in 1985 [68]. The authors have studied a dynamic facility relay layout, and developed three new programs:

Program UA1 undertakes data validation. For static layout design program UA2 is used, while UA3 is designed for changeover simulation. The programs have the facility for evaluating alternatives on a financial basis.

Static 2-D layout (in UA2) is determined by coordinates of the building outline; facilities are represented by rectangular or circular shapes/areas. Facilities (workcentres) are grouped into sets and the placement of facilities is done manually. The relay layout starts with the existing layout, the new arrangement, and with the support of M.H. information. The changeover simulation model (UA3) operates subject to a number of assumptions which define the changeover situation, e.g.: specified life-span, times of relocation, limits on the number of relocated workcentres, limits on relocation moves (within a period), etc.. There are three types of changeover:

- instant changeover (at time zero)
- slow changeover (with intermediate layouts)
- changeover while stopping production for early benefit from the new layout.

UA3 evaluates the changeover, on the basis of M.H. costs and workcentres relocation costs. M.H. distances are calculated as straight-lines, where no traffic routes exist, or as the shortest distances around the traffic system. In comparison with CRAFT and PLANET, UA3 considers not only the cost of journeys but also extra costs i.e. M.H. fixed

costs, consisting of pick-up and set-down costs. A priority rating expressing the order of potential gain from changeover is used. Program UA3 prints details of M.H. costs throughout the simulation.

The authors are fully aware of the vulnerability of M.H. criteria if considered in isolation. The dynamic facility layout draws a comparison between M.H. cost and the rate of profit from production in the new changeover situation on, on the one hand, and the cost of the relocation of facilities, on the other hand: this produces a better picture of the changeover.

The simulation model is designed as an aid for decision making regarding changes of layout, rather than as a tool for actual detailed workshop layout.

In the class of major and expensive simulation packages programs MAP and CDAS were introduced.

3.2.16 MAP

MAP -Manufacturing Automation Protokol, was developed by General Motors in cooperation with Boeing, and introduced in 1986 by Baer [69]. The system is able to handle 3-D CAD data, NC tool paths, robots, automatic guided vehicle instructions and shop traffic instructions. The MAP package can be integrated with CAD/CAM system. According to Baer,

the MAP system is very expensive and currently beyond the means of medium and small-sized companies. MAP enables communication and control of the shop floor. Operations in this particular application include loading, cleaning, soldering and stacking. Using MEDUSA CADD software, the system was used to draw the cell configuration, but the levels of manual/automatic drawing or any specialised factory layout facilities are not documented.

MAP is clearly orientated as a large scale process control system, including MRPII (material requisitioning) programs. Therefore any comparison with CAFLAP, which is a special purpose, plant layout orientated system, can hardly be made.

3.2.17 CDAS

Immediately after MAP, Rockwell's Configuration Design Analysis and Simulation Environment System (CDAS) was introduced by Tice [70]. It was primarily designed for the simulation of future human or robotic on-orbit servicing procedures during space flight. Low fidelity computer graphic visual simulation was used. All positions and motions of objects were calculated ahead of time and could be recalled in 3-D presentation, frame by frame. Tice claims that CDAS can be used for:

- designing spacecraft, tool and cradle hardware,
- analyzing remote manipulator system
- checking effectiveness and feasibility of design

-simulating design, redesign, feasibility and efficiency operations.

At the present time, CDAS has no collision detector.

Grant and Weiner [71] evaluated ten Animated Simulation Systems in worldwide use. This included the "See Why" system already described in paragraph 3.2.14. The systems evaluated were:

AutoGram, BEAM, Cinema, Modelmaster, PCmodel, RTCS, See Why, SimFactory, Simple 1 and TESS.

The features compared are:

- simulation model building system
- animation graphics
- operational consideration

The model building system is most important both for the model builder and for the user. Five of the above systems are special purpose with manufacturing orientation and five are general purpose systems. All but one system uses two dimensional animation graphics. Only AutoGram uses 3-D and the graphics display allows observation of the designed system from different perspectives. AutoGram allows the creation of layout from drawings, via a digitiser. The other systems offer mouse driven menus of characters or shapes.

The listing of these features reveals that none of the simulation systems are similar to CAFLAP.

The Buyer's Guide to CAD systems [72] was studied and it shows that although different CAD system offer various and sometimes very sophisticated facilities, none of them is similar in operation or presentation to CAFLAP (see also Chapter 4.2.).

3.2.18 GRASP

Another interesting package recently developed is GRASP [29]. This is a practical tool for the visualisation and study of relative positions of work stations with respect to robotics and movements of parts in 3-D Computer graphics. GRASP was designed predominantly for:

- 1) Programming robots;
- 2) Process purposes (showing what the robot is doing and finding movement paths.
A Clash detector menu can indicate,
by flashing, the clash of parts
or equipment);
- 3) Robot purchase.

The system is orientated on Flexible Manufacturing Systems (FMS) and on relatively small areas or spaces of

manufacturing cells. At present it has no facility for labelling the work stations with tag numbers and dimensions, although this may be a feature of a new program GRASP 6.1 which is now being developed. GRASP is certainly a very powerful system and could in future be expanded into other specific areas.

Parallel to the above mentioned new approaches, research still continues in the field of 'technological' positioning of facilities (considering mainly flow factors and desirability rating). This can be seen documented by the works of Foulds, Giffin and Cameron in 1984 [63, 64 and 65] and Foulds, Giffin and Evans in 1985 [66].

The last word in block layout design is apparently the study of Evans, Wilhelm and Karwowski [31] presented in 1987. Instead of the previously mentioned techniques, they suggest the use of the theory of fuzzy sets. The authors consider flow rates and REL charts as vague concepts, yet the inexact data could be handled with the use of fuzzy methodology in a mathematically strict way.

However, Herroelen and Van Gils, in 1985 [67], in a similar manner to Kaltnekar [62], critically examined the main stream of research following the ideas of flow dominance. Assessing the stream of studies following the concept of CRAFT, they come to the following conclusion:

"Using flow complexity measures to decide on the

particular layout configuration to be installed ... is a mere neglect of the many complexities involved in designing a plant layout and materials handling system..."

"...the layout complexity issue is in desperate need of further research..."

All the above references show methodical differences in approach to solving layout problems and a genuine effort to find a way of facilitating the industrial/layout engineer's work. Despite all this effort, Lockyer's claim [21] that the layouts still have to be designed entirely manually, persists. The Writer believes that this failure to find a better method was not only caused by the fact that in Factory Layout Planning "there are a number, and sometimes conflicting requirements" (as claimed by Lockyer [3]) or by methodology of approach, but also by the state of computer science. As in many other engineering fields, it is the recent development of the techniques in computer graphics that is generally opening new horizons. In this particular work it is these techniques which have made CAFLAP possible!

4. COMPUTER AIDED FACTORY LAYOUT PLANNING

4.1 ENUNCIATION OF THE PROBLEM

Factory Layout Planning "is at best an imprecise craft" and "layout planning never developed into a clear procedure" stated Muther ([57-Preface], [4]). Nugent [38] and others see its combinatorial nature. "Factors influencing layout are numerous" says Kaltnekar [62]. Order, product, production programme, production planning, production, manufacturing systems, cost of product, and capital investment are just the main factors influencing Factory Layout Planning (Fig.2.) to be quoted.

Only with all the digested knowledge of what Factory Layout Planning involves (see Chapter 1,2 and 3) is it possible to select the area of layout planning which is suitable for methodological improvements with the use of computers. Hence the area of space demands and space relationship has been selected as the main topic for this Thesis. Contrary to all the above mentioned packages, CAFLAP solves SPACE RELATIONSHIP AND SPACE REQUIREMNT problems.




Fig. 2. MAIN FACTORS INFLUENCING FACTORY LAYOUT PLANNING

CAFLAP considers the relative positions of 'spaces' (Manufacturing Space, Product Space...see section 4.2) conditioned by the technological requirements and demands of optimum utilisation of building space (Civil Engineering Space).

To fulfil the task, the following particular areas and steps are considered:

- a) Manufacturing, as a system, is re-defined for the purpose of Computer Aided Factory Layout Planning in dynamic and spatial terms.
- b) The definition of a Work Station Module as a new 3-D 'template' for the use in computer graphics is established. (A Specimen of a Work Station Card which can also be used for the purposes of a complete computer aided Production/ Industrial/Project Engineering control and planning system, is developed.) Material Handling studies, regarding space and its 'filling' are pursued.
- c) A specific computer graphics system, PICASO (see section 4.4), is selected.
- d) The principle of a 'continuous industrial bay' and 'Product Space Zone', as an aid for layout planning, is defined.

- e) Programs for the design of individual Work Station Modules, Buildings, and for Manual Positioning of Work Station Modules are written.
- f) A program for the manipulation of the whole scene to allow the user to observe the layout from a required position is written.
- g) The development of the system into an automatic positioning system, considering mainly the interdependence/interaction of spaces, is contemplated: programs using a combination of automatic and manual positioning are developed.
- h) The criteria for the automatic collision course finding of work stations with building elements are established.

The end product is an automated tool, assisting engineers to design/optimise the layout, in terms of most economic space utilisation, while maintaining 'technological' positioning.

Alongside the main layout problems it was also found essential to consider:

- Production Management conditions (see 4.2).
- Material Handling problems influencing the Layout and

the size of the Industrial Bay (see 4.2).

- Retrieving work stations for a suggested production line from a chronological list. This happens after the 'technological' position of work station has been determined.
- Capacity calculation for Feasibility Study and Investment Project (e.g. number of work stations needed etc.).

The CAFLAP system was originally aimed at layout and re-layout of a medium-size engineering company with batch type production and with a maximum product weight 60kN.

4.2 SYSTEM MANUFACTURING

In the last decade manufacturing has ceased to be observed as a pure mechanical technology problem. The increase in overall production output is no longer considered to be purely a matter of the introduction of more advanced machining or other technological methods. Studies of machine break-down, for example, have led to a new approach to maintenance. Similarly, concern about the human factor failure in fulfilling the requested tasks accurately and in the shortest possible time and consequently, studies of the

relationship between workers and their environment, have brought about the development of a new discipline: i.e. Human Factor Engineering, or Ergonomics. Attempts to optimise the operator's output have resulted in the development of the subject of Synergetics.

Maintenance:

To avoid excessive wear and tear and break-down of machines a system of 'Planned Maintenance' has been developed. The principles of planned or preventive maintenance have been known for many years, but were formulated methodically in the sixties in the studies of the Ministry of Technology [73]. Since then the interest in Planned Maintenance has been growing steadily: the works of Clifton [74], Heintzelman [75] and Patton [76] are of note.

Planned Maintenance creates conditions for diminishing the losses resulting from machines down-time. In an attempt to minimise the maintenance demands and costs, a new discipline in machine design, 'Design for Maintenance', has been developed.

Planned Maintenance is defined as an activity including all necessary works on, and services of, work stations (machines), organised in pre-planned time cycles, to maintain them in good working order.

Maintenance requirements are also described in many factory

management books e.g. Lockyer's 'Factory and Production Management' [21]. It should be said that maintenance practice and maintenance cycles vary from industry to industry, and with the type of machinery installed. However, there is an underlying general pattern of planned cycles of improvement and of preventive and corrective maintenance, as formulated by Patton [76].

Larger time scale cycles (years) usually contain provision for:

- Preventive Maintenance (Appendix I-9) (greasing, cleaning, adjusting, repairs taking less than 3 hours, etc.);
- Major Overhaul (complete inspection, parts replacement, renovations);
- Safety Inspections (elimination of safety hazards);
- Modification and Modernisation (alteration of present machines for more demanding functions, e.g. gearing);
- and
- Emergency Repairs to keep equipment operative (taking more than 3 hours).

From the above mentioned types of maintenance services, Preventive Maintenance is the most important for CAFLAP. It is itself organised within smaller cycles (day or week):

- during shifts - oiling, greasing, adjusting;
- between shifts - inspection, adjusting, oiling;
- during night shift (24 hrs interval) - cleaning, small repairs taking less than 3 hrs, etc.

As the services are performed in the area of the work station, they create demands on Maintenance Space. In the past, when importance of Planned Maintenance was not widely recognised, the space needed for maintenance was often overlooked or neglected at the design stage. Losses resulting from this were evident. It is important to note that in the CAFLAP system developed here, the provision for Maintenance Space is embodied.

Design for Maintenance means giving the necessary support to all the functions of the machine. For example, an easy access to all oiling, greasing and inspection points must be guaranteed. Assembly procedures/provisions should serve easy replacement of parts and for all other maintenance purposes. Energy supply lines (pipes, cables), should be designed in such a way as to avoid crossing problems during maintenance. Lubrication and cooling should always be on the opposite side of the operator's post. Where possible, maintenance free material (e.g. plastic, sintered bronzes) should be used. Swarfing (cleaning of machine tools from all scrap of machining process) should be designed for most ease of removal [22].

Both Design for Maintenance and Planned Maintenance are determining factors influencing the demands on space around any work station. This, denoted in CAFLAP as MAINTENANCE SPACE, is further discussed in paragraph 4.2.1.1 and 4.5.1.

Human Factor Engineering - Ergonomics:

Human Factor Engineering is a branch of technology that helps to design machines, operations, and environment to match human ability and limitations. Human Factor Engineering is a term used mainly in the USA [82].

The term Ergonomics is used mainly in Europe [21,81] and the definition is slightly different from that of Human Factor Engineering. Ergonomics is seen as scientific study of the relationships between man and his work environment. The first studies in what is now called Ergonomics, started as early as in World War Two. Explanations were sought as to why bombs and bullets often missed their targets, planes crashed and friendly ships were sunk without apparent reason: it was discovered that a human factor had frequently to be blamed. After the war research continued in manufacturing industry where the reasons for a high percentage of faulty products were studied.

Again the human factor was found responsible. The main sources of problems were:

- Monotony of work (especially on assembly lines);

- Fatigue from heavy tasks;

- Badly designed machine tools, equipment and instruments;

- Badly designed work station layout;

- Influence of shortcomings in the immediate environment
(Lighting, Noise, Ventilation, Heating, etc.).

From the above factors it can be seen that the design of Work Station Layout is very relevant to CAFLAP, and especially to the design of a Work Station Module - Man

Space (see 4.2.1.3).

The physical factors of Work Station Layout, which have a dominating influence on the operation are:

- maximum physical comfort of the operator;
- good view, enabling the operator to see all phases of the manufacturing process;
- good access to all important parts of work station;
- a reduction of physical strain to a minimum.

Mental factors of Work Station Layout, which are of equal importance to physical ones from the control point of view, are:

- operator should be able to exercise control easily and with accuracy;
- sources of mental strain that distract the operator's attention from making judgements and decisions needed for the job should be eliminated;
- stress from lack of space or unsafe working practices should be prevented.

These ergonomic factors are determining the demands on space in which the operator is working. This, denoted in CAFLAP as MAN SPACE, is discussed further in paragraph 4.2.1.3.

Synergetics:

Synergetics is a relatively new science which is studying sets of effects of work environment on operators [27,28].

It is trying to establish the best configuration and combination of sets of elements and their influences, to achieve optimum performance. From the Synergetics point of view, CAFLAP is trying to find the best arrangement of work stations in detail layout (see 4.3).

A study of all the above aspects has, in the present CAFLAP work, led to a new appreciation of dynamic and spatial relationships within a manufacturing system, and to their reconsideration for the puposes of CAFLAP.

But, before the system is analysed in detail, the shop floor situation, as it is recognised in today's factories, has to be summed up.

A classical Plant Layout (shop floor space) usually comprises the following Areas:

- a) Manufacturing Area
- b) Manufacturing Services Area
- c) Non-Manufacturing Area
- d) Stock Area
- e) Aisles Area
- f) Unrehabilitated Area

Other areas include:

1. Administration Offices
2. Employee Facilities
3. Factory Offices

4. Garages

5. Services (Energy)

etc.

CAFLAP could, of course, consider the layout of all areas, but because the Manufacturing Area is the most important (sometimes it occupies over 50% of all other areas), the present work is concentrated on this area.

As from the point of view of system approach, complex problems can be seen more clearly, this methodology has been used in the following classification.

4.2.1 SYSTEMS

A manufacturing system expressed in dynamic organisation terms for the purposes of CAFLAP {see Fig.3.} can be classified [15] as follows:

A) Higher Systems - region, state, continent, world.. etc.

B) Wider System - Plant, Factory, Company.

Systems, within the wider system, are:

a) System Management and Administration:

- Management control level (Personnel, Purchasing, Financial, Sales, Marketing, Prodn. control,

Prodn. planning, Industrial eng., etc.);

b) System Research and Development, Drawing Office;

c) System Services:

- Health and Safety, Catering, Maintenance, Stores, Swarfing, Scrap control, Plant and Building Services, Power, Energy Supply etc.;




Fig. 3.

MANUFACTURING SYSTEM EXPRESSED IN DYNAMIC ORGANISATION TERMS

1. The first part of the document is a letter from the President of the United States to the Congress, dated January 3, 1862.

2. The second part is a report from the Secretary of the Treasury, dated January 3, 1862.

3. The third part is a report from the Secretary of the Interior, dated January 3, 1862.

4. The fourth part is a report from the Secretary of the Navy, dated January 3, 1862.

5. The fifth part is a report from the Secretary of the War, dated January 3, 1862.

d) System Manufacturing:

Here Sub-systems can be distinguished:

- Manufacturing (incl. Work Stations, Swarfing, Manufacturing (Auxiliary) Services etc.)
- Man (Operators, Fitters etc.)
- Material (incl. Material Handling, Intermediate Stores etc.)

The above dynamic organisation systems have to be physically accommodated (in spatial terms) and it is obvious that the systems and sub-systems would have their own specific requirements on physical properties of buildings (floors, areas, spaces).

Hence the Wider System, expressed in spatial terms {Fig.4.}, will comprise:

- a. Offices (System Management and Administration, Drawing Office, R+D)
- b. Special Areas (System Services, Laboratories, etc.)
- c. Shop Floor/Space (Layout)
which has to accommodate the system Manufacturing and its sub-systems:




Fig. 4.

MANUFACURING SYSTEM EXPRESSED IN SPATIAL TERMS

- Manufacturing Space
- Product Space
- Man Space
- Manufacturing Services (Appendix I-10) Space
(Tool Crib, Cutter Grinders etc.)
- Services (Appendix I-11) Space (Power, Water etc.)

The design of offices and similar areas is usually the domain of architects. The industrial or layout engineer furnishes them with information relevant to administration and production requirements, for example, the number of staff to be accommodated, the office equipment needed, etc.. Special areas are usually designed through co-operation between architects and engineers. In respect of manufacturing areas it is the factory layout engineer who is principally involved. Architects or other professionals also try to exercise their influence in these areas, but such approaches must be considered as secondary because they cannot guarantee technologically orientated, cost effective production.

It is the intention here to highlight the special features of manufacturing areas from a Factory Layout Planning point of view, and a discussion of the spaces of main concern

follows.

4.2.1.1 MANUFACTURING SPACE

Manufacturing Space is defined as the whole space where product [84] manufacturing is performed, i.e. it is the space occupied by:

- Work Stations [84] (incl. accessories), Work Centres including assembly, inspection, painting etc.
- Operational Space (space for all movements of work station parts, essential for smooth production flow e.g. robotics, and movements of Material or Work in Progress (W.I.P.) [84] within the work station).
- work station Maintenance and Repair Space.

The smallest, self-contained unit of Manufacturing Space is a WORK STATION MODULE which is a sum total of all three spaces and includes Man Space (see below). It is simulated as a 3-D computer drawn template {see Fig.5.}. See also program 'WSBUILDR.FOR', Chapter 4.5.1, and Appendix II.

The WORK STATION MODULE is also part of the Work Station Card containing manufacturing and other information regarding the work station (Appendix III, Drawing No. 1, sheets 1 to 6).




Fig. 5.

WORK STATION MODULE

4.2.1.2 PRODUCT SPACE

Product Space is defined as the space occupied by the Flow of Material, W.I.P., Product, Swarf and Scrap. It includes the space needed for Material Handling equipment and Intermediate Stores.

NOTE: For machine interfaces (deployment of robots etc.) Product Space ends from the very moment when/where the W.I.P. is attached to the work station. A moving work station is considered as a special case of Manufacturing Space.

4.2.1.3 MAN SPACE

Man space is defined as the space necessary for operator(s), fitter(s), etc. to perform all the duties regarding the manufacturing process, and is designed in accordance with the ergonomic principles.

4.2.1.4 MANUFACTURING SERVICES (AUXILIARY) SPACE

Manufacturing services (Auxiliary) space is defined as that space required to accommodate machine services, e.g. Tool Crib, Cutter Grinders, Tool Salvage etc.

4.2.1.5 SERVICES SPACE

Services Space comprises ducts, enclosures, cable trays,

etc., and/or maintenance steelwork accomodating supply lines of gasses, power, technological water, coolant, oils etc. for manufacturing purposes.

4.2.1.6 SHOP FLOOR "BREATHING SPACE"

Shop floor "Breathing Space" is the space where NONE of the above spaces are included. (It could be empty). In practice a space like this is usually kept as reserve to accommodate small changes in layout, and expansion. It is usually utilized as additional intermediate store.

It should be noted that all the 'technological' spaces are considered above as well as below zero floor level according to specific situation and needs.

Foundations of work stations, equipment, etc., are considered as being part of the spaces (sub-systems) to which the work stations, equipment, etc., belong (e.g. foundation for a production milling machine is considered in the sub-system Manufacturing Space).

4.2.1.7 BUILDING - CIVIL ENGINEERING SPACE

Building - Civil Engineering Space is defined as the space physically accomodating all 'technological' spaces (Manufacturing Space, Product Space, Man . Space,

Manufacturing Services Space, Services Space, and Breathing Space), and is providing a suitable environment.

The space includes:

Foundations of buildings (columns etc.)

Floors, Staircases, Platforms, Pits, Ramps etc.

Columns

Storm and sewerage water ducts

Drinking water piping

Walls, Barriers, Doors, Windows

Roof structure

Any unspecified structural supports, stiffeners, etc.

Heating and Ventilation, and

Lighting.

4.2.2 PRODUCTION PROGRAMME

The reasons for wishing to change the layout of a factory such as market forces, orders and production capacity requirements were considered, but are not part of this study. It is assumed only that the Production Programme has been determined that and a new layout has been requested.

The Production Programme basically conditions the type of production (technology, operations, types of machines, and equipment), and this directly influences the type of layout (as quoted in Introduction, Chapter 1.).

4.2.2.1 INFLUENCES OF PRODUCTION PROGRAMME ON DESIGN OF MANUFACTURING SPACE

In Chapter 3. were discussed some computer aided systems which also consider Production Programmes. They sometimes use very sophisticated methods to arrive at a very simple, and usually the only possible, solution: i.e., positioning work stations 'technologically' in an order/line, which is at the same time an economic optimum.

It is also the practical layout strategy (see 4.3) of positioning work stations in a real industrial bay that dictates [13] the order of work stations. This could be, in an overwhelming number of cases, only a physical line of interrelated work stations.

Once a 'technological' position of work stations is computed (by any of the suitable systems mentioned in Chapter 3.), or intelligently established, the actual layout may be designed with CAFLAP system in a straightforward manner. CAFLAP system operations start from the very moment when a 'technological' order of work stations is established, and this data is fed into the system. It can be said that the type of Production Programme, or even type of layout, has no bearing on the design of manufacturing space by CAFLAP system. Neither can it influence the performance of CAFLAP itself.

4.2.2.2 INFLUENCES OF PRODUCTION PROGRAMME ON DESIGN OF PRODUCT SPACE

The Production Programme cannot be considered in isolation and the influences of Production Management techniques (state of organisation) must also be considered. Together they create needs for size of aisles, stores, intermediate stores and Product Space next to work stations.

When designing the size of aisles, the basic unit to be considered is the Unit Load (expressed in dimensions, widthxlengthxheight, and in volume/hr or weight/hr). Unit Load is defined as an optimum load in Material Handling (M.H.) to satisfy all principles of standardization; or simply as " a unit to be moved or handled at one time" as suggested by Tompkins and White [39].

For the purposes of deriving the computer graphics expression, the basic equations from Hydrodynamics was considered:

$$\omega = Q / F$$

where ω = speed of movements
of Unit Loads (m/hr)

Q = Volume of Unit Loads
manufactured per unit
of time (cu.m/hr)

F = sectional area available
for transport (sq.m)

$$F = w \cdot f$$

and

$$f = Q / w \cdot w$$

w = Aisle width (m)

f = "filling" of the Bay (m)

is height of the Aisle

utilised for M.H.,

(indicates the density

of M.H.).

It has to be said that the above considerations only serve as an auxiliary guide because the real movement of material in batch production is in paces. However, such equations help to define the optimum dimensions of transport aisles when translated into computer graphic histograms.

Further the value 'f' (filling) can:

- a) Indicate any slowdown in M.H. area, or production area and, once the optimum value is established, any deviation could be monitored, i.e. it could be used as a tool for the Production Control Department;
- b) Show what speed of movements in Product Space is required; how many M.H. vehicles, fork-lift trucks, or what sort of M.H. means of transport are needed.

Computer Program 'M100.FOR' was contemplated to provide

basic data for the above.

In order to design the size of Product Space at work stations, the following basic systems have to be considered: Two Bin system, Just-in-Time system (KANBAN) and Base Stock control [77,78,79,80]. For any of these systems presentation of Product Space creates special problems, and these are dealt with in section 4.3 Layout Strategy.

The product mix and size of batches can influence Product Space (see 4.2.1.2) considerably, but only if the batches are very small. This has, of course, to be considered in conjunction with M.H. cycle and unit loads.

A unit load (U1) has requirement for space (Us); the total time required for machining of a batch is Tb, and the duration time of a regular M.H. cycle is Tmh.

If a unit load is equal to one batch, and time Tb is N times smaller than M.H. cycle (Tmh),

$$T_{mh} = T_b \times N \quad (\text{or } T_{mh} = \sum_1^n T_b)$$

then Product Space (Ps) -space next to work station available for unit loads waiting for machining or transport- must be increased N times.

$$P_s = N \times U_s \quad (\text{or } P_s = \sum_1^n U_s)$$

Or, vice versa, material handling cycle must be shortened (which would increase M.H. costs).

The above consideration is of general validity, including the increasingly popular Just-in-Time system (JIT).

If the JIT (KANBAN) system in production control is used, each Kanban (Shop sign, card) represents a unit load -or container load, according to Burbidge [77]. Apart from identifying the contents of a material container, Kanban is used to order a replacement supply when a container is issued. Kanban practically defines the size of a batch. The number of Kanbans issued indicates the number of batches (unit loads) in the process, and determines the size of the base stock. In other words: the more Kanbans, the larger the base stock. This leads to demands for increased Production Space generally.

It must be concluded that, apart from style of production management, the Product Space is influenced mainly by the type of M.H. equipment.

Other product spaces, Stores and Intermediate Stores should be designed intelligently, but could be incorporated into automatic layout system as individual modules.

Overall Conclusion:

Insufficient Product Space generally results in difficulties, especially in the following areas:

- shop floor management/production management
- material handling (clumsy and slow M.H., bad access)
- safety

Excessive Product Space results in an overall increase of shop floor/ space and this creates waste in the following spheres:

- material handling costs (bigger distances),
- ventilation and heating costs,
- lighting costs,
- maintenance costs, and
- larger capital investment costs.

The above indicates that the design of an optimum Product Space is quite a difficult task considering the variability of factors involved. It is made even more complicated by the requirements of computer graphic presentation and this leads to the development of a novelty idea: the concept of a PRODUCT SPACE ZONE (see the following section 4.3).

4.3 LAYOUT STRATEGY

One of the objectives of CAFLAP project is to shorten the time of the traditional layout approximation process (as described in Chapter 2.), while maintaining the principles of a good factory layout. This can only be done by preparing the detail layout first, skipping the two initial project stages: Feasibility Study and Investment Project (see Fig. 6.).




Fig. 6. PROJECT STAGES - DESIGN PHASES - CAFLAP APPROACH

4.3.1 CAPACITY CALCULATION

It is assumed that the number and types of work stations needed will be extracted from Route Sheets (or Job Cards), and the 'technological' positions of work stations will be established (as mentioned in Chapter 3.). The number of machine tools (M/C) can also be calculated via program 'M100.FOR'.

4.3.2 DETAIL LAYOUT

Experience has shown that the actual layout can be prepared effectively only when it is started in the direction of the Flow of Material, and in the 'technological' order of a line of work stations involved.

In Fig. 7., Layouts a) to g) are presented as typical detail layouts of regularly arranged work stations in Industrial Bays.




Fig. 7.

TYPICAL DETAIL LAYOUTS OF REGULARLY ARRANGED WORK STATIONS
(Plan views)

Types a) and b) are considered ideal:

- to satisfy the criteria of a good layout,
and
- to provide maximum comfort for the operator (create
a set of environmental configurations in order
to optimise his performance - all ergonomic
principles are maintained).

For the above reasons these two types have been selected to be used for automatic positioning in CAFLAP system developed here. The main steps in detailed layout are shown in a system chart {Fig. 8.}.

STEP 1.

The list of work stations is determined and individual Work Station Modules are drawn and filed. The basic width of the industrial bay and the width of the Product Space Zone are determined intelligently according to the width of an average size Work Station Module and the width of Unit Load {see Fig.9}.




Fig. 8. CAFLAP SYSTEM
SIMPLIFIED SYSTEM CHART




Fig. 9.

DESIGN OF AN INDUSTRIAL BAY
(3 - D representation, viewed from above)

The PRODUCT SPACE ZONE is defined as a 'hard shoulder' type area; a continuous strip of space running alongside aisles, which is designed:

- a) to serve for storage of material, W.I.P. and products (Unit Loads, pallets etc. [39,83]) next to work station, and
- b) as a 'boarder' for automatic positioning mode in CAFLAP.

The width is determined by the width of Unit Load. The Product Space Zone can accommodate all the different demands (i.e., Two-bin, Just-in-time, and Base-Stock Control) on Product Space resulting from the above mentioned systems. The only space loss is limited to the width of the Man-Space, allowing a safe passage for the operator.

If the automatic positioning mode was considered in isolation from the rest of the CAFLAP system, it could be classified according to Moore [30] as an improvement type procedure because it starts with a predetermined industrial bay.

STEP 2.

The first work station is positioned manually in a requested place/section of the industrial hall either at a right angle to the aisle or obliquely to it (see Fig.6. a) and b)).

STEP 3.

The rest of the layout development follows according to the mode selected (see section 4.5.4). If a collision course is indicated, a facility for manual positioning (manual override) is used in order to reposition one or more work stations as necessary to avoid the collision. If then requested, the automatic positioning mode can be resumed.

This method can also be used to find the optimum width of an industrial bay [see Fig.10.], i.e. if the work station is found to be colliding with the 'border' (Product Space Zone, aisle, walls etc.) it is repositioned into an oblique position. This, intelligently assessed, could lead to an even narrower bay design, especially if work stations are long and 'slim' (e.g. a turret lathe).




Fig. 10.

FINDING THE OPTIMUM WIDTH OF INDUSTRIAL BAY

The value of this procedure for a 'green field' layout design is obvious.

A narrow industrial bay is much more cost effective than a wide span industrial bay, which is not only expensive to build (initial high capital investment), but also to maintain. The larger span bay requires a higher roof structure which also increases the volume of air to be ventilated and heated: a further consideration for costs. The construction height of the building cannot be fully utilised technologically. If cranes are used, it is again the larger span of the bay that dictates higher cost of cranes and may influence their performance.

In a practical layout, there are two types of work station formations: regular and irregular (see Fig.4). CAFLAP system has been developed to accommodate both: for the irregular formation case the manual positioning mode of CAFLAP may be used, while the automatic mode serves in the case of regular positioning.

4.3.3. OVERALL LAYOUT OF INDUSTRIAL HALL

CAFLAP can be used as a tool for design of an industrial hall of any shape. The following describes a typical case. A flow chart in Fig. 11. shows the methodical steps in layout design of an industrial hall. For typical production

line flow patterns see Fig. 13.




Fig. 11. MAIN STEPS IN THE DESIGN
OF INDUSTRIAL HALL-OVERALL LAYOUT

1. 1. 7

A detail layout of 'technologically' self-contained sections (i.e. an interdependent line or group of work stations), is continued in a straight 'continuous' line. This also satisfies Muther's [4] layout fundamentals {see Fig. 12}. A 'continuous longitudinal bay' is thus designed {corresponding to Fig. 13. a)}.

The principle of a 'continuous industrial bay' is an aid for layout planning using automatic positioning mode (see section 4.5.4). It provides for fluent positioning of work stations in the bay.

The continuous bay is designed in its total length regardless the length of the industrial hall. The hall usually accommodates more than one bay {see Fig. 13.d)}. The work stations may be positioned on both sides of the aisle.

When the length of the industrial hall 'H1' is shorter than the length of the continuous industrial bay 'L' and a U-shape or S-shape Flow Pattern is used {see Fig.13. b)}, the total length of longitudinal bay has to be cut (while 'technologically' self-contained sections are maintained), into lengths which can be accommodated in the industrial hall.

When a Parallel Lines Flow Pattern {see Fig.13. c)} is used, individual lengths have to be cut accordingly.

RELATIONSHIP

degree of closeness


desired
among M/Cs

OP01 → OP02 → OP03 → OP04 →

operations

SPACE


configuration



ideal position of work stations

ADJUSTMENT


realistic best fit




realistic position of work stations

Fig. 12. 'CONTINUOUS' LINE SATISFIES LAYOUT FUNDAMENTALS


a) STRAIGHT LINE



b)



c)



d)

TYPICAL LAYOUT OF AN INDUSTRIAL BAY




Fig. 13.

FLOW PATTERN FOR PRODUCTION LINES

4.4 LAYOUT USING INTERACTIVE COMPUTER GRAPHICS

In the preparatory stage of this project it was essential to select an existing commercial software system suitable for the purposes of CAFLAP methodology. The selection was influenced by CAFLAP demands for a computer graphics system and also by several other factors, which are summarised as follows:

The system should have a facility for a simple design of all objects/spaces in 3-D. This refers especially to the design of Work Station Modules and to the Civil Engineering Space with all its elements.

The system should have a facility for marking the designed objects with identification or tag numbers.

The system should have a suitable potential for the development of facilities for manual and automatic positioning of 3-D objects and collision course finding. Kinetic function ability is essential for the positioning of Work Station Modules in the Civil Engineering Space and for Collision Course Finding. It is also important for the observation of the developed scene.

The obvious choice available was a CAD drafting system, for example MEDUSA (in possession of Middlesex Polytechnic).

The system was tested and part of the Project was investigated with the participation of some engineering undergraduates.

In spite of the fact that MEDUSA offers an excellent drafting facility, it was realised that modification of the system for the purposes of CAFLAP would be far too complicated (if not impossible). Therefore the development using this system had to be dropped.

Another system in operation at Middlesex Polytechnic is PICASO (PIcture Computer Algorithm Subroutine Orientated) developed by Dr. John Vince [93, 94].

It is a FORTRAN-based computer graphics system, designed to ease the interface between programmer and graphical problem areas. PICASO subroutines may be incorporated into any FORTRAN or PASCAL based programs. It offers a comprehensive library of 2-D shapes and 3-D objects which may be manipulated through a wealth of manipulating algorithms. The system's conceptual space allows the user, through the 'observer', projection mode and projection space (using system commands), to observe and manipulate any designed scene. For shapes and object analysis the system is equipped with some thirty six analysis commands. For shapes and objects presentation there are over thirty drawing commands. Drawings generated by PICASO are normally drawn on high resolution VDU and could also be plotted upon any suitable plotter. Since PICASO was apparently developed for

visual arts, it has a variety of built-in features to suit that purpose. Because of its versatility, it offers considerable potential for creative use even to engineers. It also has a capacity for modification and for further development. These are the reasons why PICASO was adopted for use in CAFLAP work.

The hardware used was originally Prime 550 computer which was replaced by VAX/VMS VERSION V4.5 computer system. Terminals used were Applied Digital Data System, Model ADDS-Regent 25; Insight Terminals Ltd., Model vdt-1; and printer EPSON FX-80.

4.5 PROGRAMS AND THEIR SOLUTIONS

The CAFLAP programs developed here were compiled in FORTRAN 77. The major reason for using FORTRAN was because the research project exploited the PICASO computer graphics library, which was implemented in FORTRAN 77. Although PICASO can be treated as a library of subroutines and functions, and therefore is accessible to other languages such as: PASCAL and C, it was decided to implement all programs in FORTRAN as the CAFLAP system needed to modify some of the original code of PICASO. Maintaining this language consistency only involved the Writer in learning one language. Furthermore, Middlesex Polytechnic - where the research was undertaken - had used FORTRAN as its primary scientific/mathematical language and was able to

provide a reliable software support service.

Although FORTRAN has played a very important part in the development of scientific/mathematical software, and is still used to implement original code for some companies, the language in favour at the moment is C. It offers a more rigorous programming environment with strengths in: data structures, structured programming, interaction with UNIX and reduced program development times.

CAFLAP could be implemented in C, and also in other languages such as PASCAL, or BASIC, but would require modification to exploit the benefits offered by PICASO. If CAFLAP was to be made independent of PICASO, it would require substantial support in the area of computer graphics.

Developing any program requiring computer graphics facilities presents problem to the programmer, mainly because of the variety of graphic specification available for workstations. To help overcome these implementation problems some computer graphics standards have now been developed, e.g. GKS, GKS-3D and PHIGS. None of these systems were available to the Writer during his work; nor was it possible to have access to sophisticated colour graphics workstations that would have had an impact upon CAFLAP's interface.

CAFLAP was developed as a vehicle to explore the Writer's ideas in developing strategies for automatic factory layout, and in this respect it was successful. To be considered now as the basis for a commercial system, it has in future to be rewritten specifically to meet the demands of any particular commercial environment.

The development of layouts, using computer graphics, generally followed the steps outlined in the Layout Strategy (Chapter 4.3).

In order to maintain an efficient programming technique [96] the main programs have been kept short (i.e. not more than 100 lines), and the subroutines have been mostly built-in, in a tree-like hierarchy. The input data are manipulated via COMMON areas, subroutine arguments, external files and an interactive terminal, for the convenience of the user, in some cases in conjunction with a printer. Each program is internally documented by comments in natural language, for the benefit of the user or another programmer. The comments are divided into two categories: Macro Introductory Comments and Micro Continuous Comments.

The Macro Introductory Comments describe the general qualities of the program:

- name of the program;
- the purpose for which the program was built;
- if the program is long and complicated, there is a

- short description of previously written sub-programs of which it consists or with which it co-operates;
- size of the program, i.e. for which number of work stations it is designed;
- program output.

The Micro Continuous Comments are those relating to the main operations, and these help to clarify and expand the significance of the FORTRAN written code.

The layouts of programs produced here have purposely been kept simple for easy reading and understanding. Great care has also been given to Statement Numbering so as to keep them in an ascending numerical order sequence, which is easy to follow. The resultant layout, and especially the included comments, thus make the programs largely self-explanatory.

The programs were developed as an integral and major part of this work but, because of their large physical volume, it was not considered appropriate to include them here. They are instead described in the following sections and included, in their entirety, as Appendix II.

4.5.1 WORK STATION MODULE BUILDER

Work Station Modules are built by the program 'WSBUILDER.FOR'. A 3-D template is built-up from a

hand-drawn sketch of the Work Station Module. The sketch includes Maintenance Space, Operational Space, Man Space, and work station (i.e. the machine tool itself including accessories), maintaining recommendations from manufacturers and all ergonomic principles. The steps in Work Station Modules design via the interactive program are following:

- requested objects (boxes, cylindrical parts, anchoring bolts, operator(s), Tag Number etc.) are selected according to a pre-printed code;
- instructions are given in the program regarding size and position requirements;
- the engineer feeds in requested dimensions and positions of the objects, starting from the origin (x=0,y=0,z=0);
- this process continues, object after object, until a complete Work Station Module is built;
- the work station is then filed under a unique Tag No. for future reference/recall, and the procedure is ended.

'Drawing' of the next work station can follow.

Any Work Station Module picture may be recalled by program 'WSRECALL.FOR'.

NOTE:

Information for the hand-made sketches of Work Station Modules is usually taken from the machine tool

manufacturer's drawings, foundation plans and manuals (including installation and maintenance recommendations and instructions).

Some well established manufacturers of machine tools helpfully supply, with their installation manuals, pre-printed simplified 2-D templates of their machine, on the basis of which the sketch of the Work Station Module could be prepared. The original intention was to identify Man-Space, Maintenance Space and Operational Space in the drawing by hatching. But this was found impossible in a 3-D representation because hatching would obscure the picture. Therefore the Spaces are drawn inside the 'largest volume' of Work Station Module {Fig. 5.}, without any further identification (hatching or tinting).

4.5.2 BUILDING (CIVIL ENG. SPACE) DESIGN PROGRAM

For the purpose of designing an Industrial Bay interior, Program 'CIVES3.FOR' has been compiled. A fully-detailed 3-D image of an industrial bay may be built from PICASO objects (presently only Boxes are used).

The method is following:

Individual civil engineering elements and 'borders' (i.e. Product Space Zones, aisles, etc.), are input.

The 3-D image is shown on a VDU and individual elements can be changed, replaced, or added until the simulation of the bay interior is completed.

NOTE:

In case the layout is being planned in an existing building, the Civil Engineering Space will be built exactly according to the civil engineering drawings available.

The writer's experience is that even well established old factories often possess unreliable civil engineering information, so that, an industrial hall survey may have to be taken and new reliable drawings produced.

4.5.3 MANUAL POSITIONING PROGRAMS

For the manual positioning of Work Station Modules (largest volumes only) in the bay, or for the positioning of departments, bays in the hall and halls in a plot, a program 'IYTVAXOO.FOR', using a joystick, has been compiled. Examples of drawings prepared by this program are shown in Appendix III, Drwgs Nos. 02. and 03.

Any objects, represented here by boxes, can be entered into a list and marked individually by Tag Nos. or any other identification (e.g. name of a department). They are then positioned against the background of a grid representing the requested area.

For manual positioning of work stations only, program 'IYTWSFILE.FOR' has been compiled. This program has a facility to retrieve detailed Work Station Modules and incorporate them into a required layout in a similar way as

in the program 'IYTVAX00.FOR'.

4.5.4 AUTOMATIC POSITIONING PROGRAM

WITH COLLISION COURSE FINDING PROVISION

For automatic positioning of Work Station Modules inside the industrial bay, program 'POSCLASH5.FOR' has been compiled.

The functions, satisfying the layout strategy of section 4.3.2, shown on a VDU or printer, are as follows:

- list of work stations available with facility for any required changes {Fig. 14.};
- present situation of development {Fig. 15.};
- new development of the layout in manual and automatic mode, and in any combination of modes {Fig. 16. and 17.};
- facility for collision course finding of Work Station Modules with building elements, 'borders' and other 'obstacles';
- automatic stop at any work station colliding, with identification of work station Tag.No.;
- facility to show {Fig.18.} the situation at a clash;
- manual override allowing to find intelligently the best new position for the colliding work station in the bay;
- continuation of the development of layout in manual or automatic mode {Fig. 19. and 20.}, with a facility to

stop or to continue the development of new alternatives of the layout.

The system is controlled (positioning, repositioning etc.) by unique identification numbers or Tag Numbers.

NOTE:

The rotation axis for Work Station Modules manipulation is the Y-axis running through the far corner of the module on the left of the operator, as shown in Fig.5.

The Tag Number is a part of the Work Station Module and has to be treated as such.

The display area on a 12 inch VDU, which could be used for layout development, measures 18x33 meters in scale, with 77 maximum Work Station Modules.

Fig. 14.


File of existing Work Station Module volumes

1	300.00	200.00	270.00	WS001
2	280.00	200.00	220.00	WS002
3	250.00	150.00	150.00	WS003
4	350.00	190.00	210.00	WS004

Do you wish to extend/update the existing file...YE or NO

Fig. 15.

LAYOUT...The existing situation of development



Do you want to continue/change the layout...YE or NO ?

Fig. 16.

You are now in POSITIONING MODE

Are you starting a NEW layout, from the first W.St. in technological order?
..YES or NO

Do you wish to POSITION the considered WorkStation manually ... YE or NO

Please POSITION the W.S. by cross-hairs...




Fig. 18.

DO YOU WISH TO RE-POSIT THE CLASHING W.S. ONLY
 ..YES,NO...If NO you can reposition any No.of W.S.





Fig. 19.

You are now in the Manual ..to..Auto Mode

Do you wish to re-POSITION the Work Station...YE or NO



Please POSITION the W.S. by cross-hairs...

Is the POSITION of W.S. according to your wish...YE or NO

Fig. 20. a)

Do you wish to continue developing the layout...

in automatic mode ... YE or NO

TOTAL VALUE OF -Z- DIMENSION IS

1187.31

YOU ARE NOW IN AUTOMATIC MODE to activate press return/new line once!

LAYOUT ACCEPTABLE

Fig. 20. b)

LAYOUT...The existing situation of development
Do you wish to redraw the layout?...YES,NO..
If NO is typed, the session is over

4.5.5 DISPLAY PROGRAM

Program 'DISPLAY.FOR' has been compiled for displaying the layout and manipulation of the whole scene. It also allows the user to study developed alternatives, and provides a better 3-D presentation on VDU and/or printing.

The user feeds in a requested distance, rotation, and elevation, and the layout is shown on VDU {see Fig.21.}.


ENLARGEMENT OF THE SCENE

Fig. 21.

RESULT OF 'DISLAYO' PROGRAM

4.5.6 AUXILIARY PROGRAMS

To simulate real situations in Factory Layout Planning some Auxiliary Programs have been compiled:

4.5.6.1 MANUAL FEEDING OF WORK STATIONS

Frequently, in practice, the plant layout engineer has a list of work stations available for the manufacturing programme. From the list, suitable machine tools and equipment must be selected and a 'technological' order of their relative positions in the layout has to be established. Interrelations of these operations is illustrated by Fig.22. Programs for 'technological' positioning developed at Strathclyde University (Dr.Carrie [13,14]), were originally intended to be used here. However, because of some technical difficulties experienced in the transfer of the Strathclyde programs, the program 'MFEED.FOR' was compiled instead. The program is substituting the results of Dr.Carrie's programs and feeds in a ready designed 'technological' line of work stations needed for the job. The program allows the user to change the 'technological' order, with changing requirements.

To accompany 'MFEED.FOR', program 'WSVTOTO.FOR' was written, which allows the reorganisation of Work Station Modules (in 'largest volume' presentation, see Fig. 5.), according to 'technological' order. This step was found necessary

because the 'largest volumes' of Work Station Modules are only used in some parts of programs, while in other parts the detailed Work Station Modules are used. The 'largest volumes' give a clearer presentation and understanding of layout development {see Fig. 20.b}}, while layouts using detailed Work Station Modules may be used for detailed study or final placement of machines (anchoring bolts, etc.) on shop floor.




Fig. 22. TOTAL CAFLAP SYSTEM

4.5.6.2 CAPACITY CALCULATIONS

The layout engineer must of course be in possession of some basic figures about the new layout (see Chapter 2. Project stages 1. and 2.). The capacity calculation program 'M100.FOR' is intended for basic capacity calculations for the case where no detailed information about production is available.

The program provides calculation of:

- Volume of Material Handling;
- Number of work stations needed;
- Manufacturing area needed;
- Total length of industrial bay.

This program is an example of others which may be developed in the future to estimate and plan, e.g. manning levels, production capacity in relation to shift coefficient, general effectiveness of layout, etc..

5. THE TESTING OF PROGRAMS

All programs were running and were tested for required functions.

5.1 'WSBUILDR.FOR' Program

To produce a 3-D template of an average Work Station Module takes 10-15 minutes. The template gives a reasonable image of the work station and, even if positioned on a one meter grid, it was found that it could be used for the placement of machines within the usual shop floor tolerances of 10 cm.

The 'WSRECALL.FOR' program retrieves the filed 3-D template.

5.2 BUILDING 'CIVES3.FOR' Design Program

To place any civil engineering element via this program takes about 30 to 60 seconds, and any change could be introduced equally fast. The 3-D model of the interior of the bay produced gives a good image of the space available for the layout. The capacity of maximum 200 building elements is more than sufficient.

5.3 MANUAL POSITIONING PROGRAMS

These programs were most thoroughly tested and no special

problems were encountered by users. The positioning of objects was found to be very fast and easy procedure. The only disadvantage is the inaccuracy that arise in connection with the use of joystick. Due to that, incompatible pictures on VDU and printouts are produced, if an adjacent position of work stations is intended. The printout from the CALCOMP 960 plotter shows a double line where work stations touch, while the optical reading of crosshair/work station on VDU gives a single image. This is evidently caused by a combination of both hardware deficiency and the human factor error.

5.4 AUTOMATIC POSITIONING PROGRAM

The composite program 'POSCLASH5.FOR' was found to be easy to use and produced very fast automatic positioning of Work Station Modules according to the design specification.

When ever a clash with building elements occurs, the collision course finding is immediate and the manual override can start without any delay.

Similar problems to those mentioned in the last section have been found with the joystick position accuracy.

IDENTIFICATION BY TAG NOS:

The Tag Number of the 'largest volume' of work station is placed horizontally at the base plate level; while the tag

number of the detailed Work Station Module is written vertically in an upright position. This design is a result of the findings during the testing of 'DISPLAY.FOR' Programs, and makes the reading of Tag No. easier in any display position.

5.5 DISPLAY PROGRAM

'DISPLAY.FOR' program ran without any problems, and the device for observation of the scene from any angle and distance proved useful.

6. DISCUSSION OF RESULTS

The use of PICASO for 3-D design and simulation has proved to be very useful. PICASO is a unique 2-D and 3-D computer graphics system developed at Middlesex Polytechnic to symplify the human interface when manipulating shapes and objects. As with any software environment there are limitations imposed upon the user when using the available commands. CAFLAP's interface would have been greatly improved if the user had had control over line types when objects were subject to hidden-line removal. Objects would have looked tidier if their surfaces could have been shaded or even transparent; there was a need to move elements around the screen in real-time. These problems are not identified as specific criticisms of PICASO but rather to identify the type of graphics facilities CAFLAP could benefit from in future with access to a sophisticated real-time full-colour graphics workstation.

It is felt that the drawing of work stations or buildings by use of a joystick should be attempted in future development of CAFLAP, despite the knowledge of possible inaccuracies inherent in the joystick-VDU-printer combination.

Experience has shown that accuracy, using a scale of 1:50 and a layout grid of 250x250 mm, is satisfactory for the needs of any type of layout for any type of mechanical

engineering production; so inaccuracies resulting from use of joystick are within usual plant layout design tolerance (10cm).

The interactive program 'IYTVAX00.FOR' for manual positioning has all positive functions specified, and it is believed that it could be used for any plant layout almost universally. Small adaptations, for example the listing of Work Stations or, vice versa, printing Work Station lists not only in chronological but also in the 'technological' order, could easily be made on request. The same is true for the 'IYTWSFILE.FOR' program.

Although the 'POSCLASH5.FOR' Program is the most developed program of all, it has scope for further development as a more versatile tool. For example, collision course finding could be extended (on the principles already developed) for clashes of work station foundations with underground piping or power ducts network, etc.. Similarly, principles for positioning according to Fig.7. a) and b), could be applied to layouts such as Fig.7. c) etc.. This could spare present users possible errors with a negative reading of joystick. However, selfguarding mechanism, protecting user against the error during manipulation (negative angles), would be useful to add.

During the automatic positioning, with the hardware used here and system of identification of spaces (no hatching,

no tinting), the Maintenance Space cannot be placed in the Man-Space of the previous work station to increase the shop floor utilisation. This has to be considered as a calculated loss at this stage of development.

BENEFITS OF CAFLAP TO THE PLANT LAYOUT ENGINEER.

CAFLAP programs testing showed there are two main areas of benefits for the user:

Firstly, it makes plant layout work easier, and the task is accomplished faster.

Secondly, CAFLAP functions as a methodological tool, guiding the user to perform the plant layout tasks systematically and with a holistic approach. This improves the quality of the work and expands user's potential, leading towards a deeper understanding of the nature of plant layout problems. CAFLAP stimulates the user's creativity, giving an opportunity actually to override the computer when necessary. The user is thus the master of the computer, not just its follower. This is illustrated in Fig.23, which shows how CAFLAP benefits the plant layout engineer.




Fig. 23. THE MAIN BENEFITS OF CAFLAP
TO THE PLANT LAYOUT ENGINEER

7. INDUSTRIAL APPLICATION OF CAFLAP

The interactive program for manual positioning was used during 1986-87 Factory Layout Planning projects for Eltron (London) Ltd. Eltron (London) Ltd., established in 1927, has three factories employing over 200 people and is one of the world's leading manufacturers of industrial electrical heating systems and equipment.

Eltron required new layouts for a two-fold increase of production capacity on 'green field' site, and cooperated with Middlesex Polytechnic on development of necessary layouts. For examples see Appendix III., Drawings No. 2. and 3.

Although it was not possible to do any detailed and exact quantitative control-study evaluation, work on the layout using CAFLAP proved much faster than had been possible hitherto by traditional methods.

Final results, with drawings printed on the CALCOMP 960 plotter, were also of a superior quality to those previously obtained. The results produced were more than satisfactory in fulfilling the practical needs of the production management team. Certainly if detail Work Stations Modules had also been incorporated at that time, the result would have been even more remarkable and well received by

Industry.

The automatic positioning program was also not then fully developed so that it was not possible to test its impact in a real industrial environment. However, test runs have shown that the method of automatic positioning of individual work station 3-D templates in construction or improvement situations, with the use of collision course finding and clash indication, is viable and very fast. Originally, as stated in chapter 4.2, the development of CAFLAP was aimed at layout and relayout of a medium size engineering company with batch production and with a maximum product weight of 60kN. These limits were set because the development of CAFLAP was targeted on companies with limited resources, premises, and manufacturing facilities. It was originally wrongly contemplated that the span of an industrial bay, or the type of M.H. equipment (e.g. cranes, fork lift trucks, conveyors) and shape of aisles, could limit the use of CAFLAP automated layout system. These factors could be restrictive and could cause problems for the use of computerised methods designing block plan plant layout (Chapter 3.2). But the CAFLAP method of positioning individual work stations in a 'technological' line is not restricted in this way. Hence the advanced development of the automated positioning method has actually disproved the existence of such a restriction, and CAFLAP may be used for any general application.

EVALUATION OF PROJECT ALTERNATIVES

Projects and alternatives, in a classical plant layout approach, are usually evaluated by means of comparison of the following main parameters:

- production programme per time unit
(expressed in terms of quantity of products,
weight, etc.)
- areas
- number of production machines
- number of operators

and indicators derived from the above e.g:

Ratio of Manufacturing Area to Total Area;
Area per one work station (in m sq./ l);
Production output per 1 m sq. of Manufacturing Area
(kN /m sq.) etc.

The Space Management concept offers a completely new approach to the economic evaluation of projects and their alternatives, giving more accurate results. This is achieved by considering new facts, established in the course of this research work, with following examples of resulting indicators e.g.:

Ratio of :

Manufacturing Space to total space of the hall;

Manufacturing Space to Product Space;

Manufacturing Space to Maintenance Space;

Manufacturing Space + Product Space to Manufacturing Services Space;

Manufacturing + Product + Manufacturing Services Spaces to 'Breathing Space'... etc.

The highest ratio of Manufacturing Space to the 'other' spaces is sought. A set of indicators may be tailored according to individual needs.

They could also provide a very instructive feedback for designers and machine manufacturers.

8. PRESENT LIMITATIONS OF THE SYSTEM

AND

RECOMMENDATIONS FOR FURTHER DEVELOPMENT

At this stage of development the system has the following limitations:

There is no independent facility for collision course finding for travelling overhead cranes or installed robots. If they are to be avoided, the 'obstacles' have to be entered at present via 'CIVES3.FOR' program. In the same way that power and pipeline networks are considered.

A facility for an automatic design for an width of industrial bay and optimum industrial hall is not yet available.

There is as yet no facility to move the picture of the bay to keep pace with automatic development of the layout, and to produce the 'continuous bay' in graphical presentation. At present the area of layout shown is limited to individual sections, determined by the size of VDU.

Other programs (e.g. Strathclyde) desirable for 'technological' positioning of work stations are not incorporated in the overall system.

With respect to the above limitations, the following are areas for further development:

- to extend the already developed programs into all the remaining areas of plant layout;
- to use colours (colour VDU) for further improvement of identification of spaces (man, maintenance) and for space saving during collision course finding;
- to add a facility for complete automatic design of industrial bays and halls;
- to incorporate the 'technological' positioning programs and facility for automatic retrieving of information from Work Station Cards;
- to build a library of Work Station Modules of all British made machine tools;
- to incorporate/develop the system into a Computer Integrated Engineering System.

9. CONCLUSIONS

A Computer Aided Factory Layout Planning system has been developed to the stage where it is industrially useful: further refinements are suggested.

The SPACE MANAGEMENT principles used are abstracted from the complex reality of the Factory Layout Planning field. These principles, translated into CAFLAP system, enable layout tasks to be greatly simplified.

All the main ideas and principles of CAFLAP developed here have been confirmed by computer programs compiled and their results.

The Computer Aided Factory Layout Planning system should not be considered as a new drafting system, nor as an algorithm for finding the most suitable relative placement of work stations.

CAFLAP should be judged as a tool for:

- speeding up layout work through the application of CAFLAP ideas e.g. Work Station Modules, Space Management concepts and positioning systems;
- increasing the quality of layout work by means of design of Work Station Modules and

collision course finding·positioning programs;

- diminishing manual repetitiveness of layout work;
- introducing facility for a more detailed layout in the early stages of a project, which will increase the quality and the quantity of information available for strategic decision making.

CAFLAP is therefore a device to:

- free engineers for more creative work;
- eliminate the number of project stages;
- ease finding optimum alternatives of layout;
- introduce new models into production in the shortest possible time;
- lower the cost of capital investment.

The developed SPACE MANAGEMENT concept also offers a new approach to the economic evaluation of projects and their alternatives, by means of comparison of ratios of spaces (Chapter 7. -Economic Evaluation of Project Alternatives). Assessment of the essential Manufacturing Spaces, together with all the auxiliary, service, and 'breathing' spaces, helps to find the areas of potential retrench. This then leads to an expedient relay layout and even to a rational redesign of Work Station Modules. If an improvement of the existing factory is undertaken, the assessment, with the

help of the spaces ratios, pinpoints the areas with the most abundant use of the auxiliary spaces which should be tackled first.

Computer graphics methodology, principles, and kinetic functions, have all been used in an innovative way to assist the creative design work of plant layout engineer.

An early decision was made to use simple hardware in this work, e.g. a small monochrome VDU and a basic printer. The aim was to make CAFLAP system accessible to a widest possible spectrum of users. Certainly this decision imposed some limitations on the extent of development of the Space Management ideas. Further development is therefore a matter of some compromise, but the main objectives of the current work have been achieved.

CAFLAP system is an important step forward in the direction of total computer integrated engineering system design.

BOB KOBLIHA

22nd July 1988.

10. REFERENCES

10.1 LITERATURE SEARCH

A computer literature search (Dialog), from NTIS data base, was carried out at Middlesex Polytechnic in March 1985.

The key words were: Plant Layout, Factory Layout, Computer Aided and CAD.

Following sources were searched manually:

The International Software Directory (IBM - 1985),
Engineering and Scientific Application - Programs available
from non-IBM sources (IBM-1983),

Research in British Universities, Polytechnics and Colleges
(1984), superseded by Current Research in Britain (J.W.
Arrowsmith Ltd. 1985),

Location and Layout Planning, An International Bibliography,
(Spring-Verlag 1985),

Buyers Guide to CAD Systems (Draughting and Design 1987,
Vol.7, No.7., 9.June, 12-17),

Factors to consider in choosing a graphically animated
simulation system (Industrial Engineering, August 1986,
36-68).

Applied Science and Technology Index (The H.W. Wilson

- (pp. 3,34)
- 2 Cullinane T.P. and Facility Layout in The 80s
Tompkins J.A. The Changing consideration
(PERA 85045 6)
(p.36)
 - 3 Bestwick P.F. and Quantitative Production Management
Lockyer K. (Pitman - 1982)
 - 4 Muther Richard Systematic Layout Planning
(CBI Publishing Company, Inc.
1973)
(pp. 2-1,2-2)
 - 5 Armour G.C. and A Heuristic Algorithm and Simulation
Buffa E.S. Approach to Relative Location of
Facilities
(Management Science, Vol.9,
No.2, 1963)
 - 6 Armour G.C.,Buffa E.S. Allocation Facilities with Craft
and Vollmann T.E. (Harvard Business Review,
March-1964)
 - 7 Hicks Philip E. Introduction to Industrial Eng.
and Management Science
(McGraw-Hill Book Comp., 1977)
 - 8 Lee R.C. and CORELAP-computerised Relationship
Moor J.M. Layout Planning

(J.Ind.Eng.,Vol.18,No.3,195-200,
1967)

- 9 Apple J.M. and
 Deisenroth M.P. A computerised Plant Layout
 Analysis and Evaluation Technique
 (PLANET)
 (Proceedings of the 23rd Annual
 Conf. and Conv., American Insitute
 of Industr. Engineers,Anaheim,
 California, pp.121-127, 1972)
- 10 Apple James M. Plant Layout and Material Handling
 (The Ronald Press Company,N.Y.,
 1963)
- 11 Kuhle H.,
 Dangelmeir W. and
 Warnecke H.J. Computer-Aided Layout Planning
 (PERA -87036 14)
- 12 Krejcirik M. RUGU Algorithm
 (Computer Aided Design, 1969)
- 13 Choudhury Shyamal Numerical Taxonomy Applied to
 Plant Layout
 (University of Strathclyde, 1970)
 (pp.34-44)
- 14 Carrie Allan S. The Layout of multi-product lines
 (INT.J.PROD.RES., 1975, VOL.13,
 NO.6, 541-557)

- 15 Parnaby J. Concept of Manufacturing System
System Behaviour
(Open University System Group-
Open University , 1980)
- 16 Francis R.L. Facility Layout and Location
and
an analytical approach
White J.A. (Prentice-Hall, 1974)
- 17 Immer John.R. Material Handling
(McGraw-Hill, 1953)
- 18 Elmaghraby S.E. The Design of Production Systems
(Chapman & Hall Ltd., 1966)
- 19 Wilde D.J. Foundation of Optimization
and
(Prentice-Hall, 1967)
Beichtler C.S.
- 20 Lockett M. Organisation as Systems
and
(The Open University Press, 1980)
Spear R.
- 21 Lockyer K.G. Factory and Production
Management
(Piman, 1981)
- 22 Hiscox W.J. Factory Layout Planning and
Progress
(Pitman, London, 1948)
- 23 Gough P.J.C. Swarf and machine tool

- (Hutchinson of London, 1970)
- 24 Zorzi A. Venice,
 City-Republic-Empire
 (Sidgwick and Jackson Ltd, 1983)
- 25 Hollocks B.W. Cost effective engineering
 through simulation
 (Proc Instn Mech Engrs
 Vol 198A No5, I Mech E 1984)
- 26 Schriber J.J. Simulation Using GPSS
 (Wiley, New York 1974)
- 27 Haken H. Synergetics - cooperative
 phenomena in multicomponent
 systems
 (Proc., Conference on
 Synergetics, 1973)
- 28 Fuller Burkminster R. Synergetics: Exploration in
 the Geometry of Thinking
 (Macmillan Publishing Comp.,
 New York, 1982)
- 29 Byg Systems Ltd. GRASP
 (Company catalogues and
 a manual;
 Nottingham, 1986)
- 30 Moore J.M. Computer aided facilities design:

- An international survey.
(INT.J.PROD.RES.,1974,
Vol. 13, No.1, 21-44)
- 31 Evans G.W., Layout design heuristic employing
 Wilhelm M.R. and the theory of fuzzy sets.
 Karwowski W. (INT.J.PROD.RES., 1987,
 VOL. 25, NO.10, 1431-1450)
- 32 Lewis W.P. and On the application of computer
 Block aids to plant layout.
 (INT.J.PROD.RES., 1980,
 Vol. 18, No.1, 11-20)
- 33 Farish Mike CAD keeps factory planning in trim
 for project present.
 (The Engineer, 21 May 1987, p.48)
- 34 O'Brian C. and An interactive approach to computer
 Abdel Barp S.E.Z. aided facility layout.
 (INT.J.PROD.RES., 1980,
 Vol. 18, No.2, 201-211)
- 35 Apple J.M. Material Handling Design.
 (New York, Ronald Press, 1973)
- 36 Ridley J. Safety at Work.
 (Butterworths, 1983)
- 37 Broadhurst A. The Health and Safety at Work
 Act in Practice.

- Sept., Vol.14, No.5, 583-595)
- 44 Johnson R.V. SPACECRAFT for Multi-floor Layout Planning.
(Management Science, 1982, Vol. 28, No.4, April, 407-417)
- 45 Jacobs R.F. A note on SPACECRAFT for multi-floor layout planning.
(Management Science, 1984, Vol. 30, May, No.5, 648-649)
- 46 Cinar Unver Facilities Planning: A system and space allocation approach in spatial synthesis in computer aided building design.
(Charles M.Eastman (Ed.), New York Wiley, 1975)
- 47 Hassan M.D.Mohsen, Hogg G.L. and Smith D.R. SHAPE: A construction algorithm for area placement evaluation.
(INT.J.PROD.RES., 1986, Vol.24, No.5, 1283-1295)
- 48 Domschke Wolfgang and Drexl Andreas Location and Layout Planning An International Bibliography.
(Springer-Verlag, Berlin Heidelberg, 1985)
- 49 Muther R. and Wheeler J.D. Simplified Systematic Layout Planning.

- (Factory, Vol.120, n 8,9,10,
August p.68-77, Sept. p.111-119,
Oct. p. 101-110)
- 50 Carrie A.S.,
Moore J.M.,
Roczniak M., and
Seppanen J.J. Graph Theory and Computer Aided
Facilities Design.
(OMEGA. The Int.Journal of Mgmt.
Sci., 1978, Vol.6, No.4, 353-361)
- 51 Carrie A.S. Numerical taxonomy applied to
group technology and plant layout.
(INT.J.PROD.RES., 1973,
Vol.11, No.4, 399-416)
- 52 Carrie A.S. and
Mannion J. Layout design and simulation
of group cells.
(16th International Machine Tool
Design and Research Conference-
Proceedings- The Macmillan
Press Ltd. 1976)
- 53 Seppänen J.J. and
Moore J.M. String processing algorithms
for plant layout problems.
(INT.J.PROD.RES., 1975,
Vol. 13, No.3, 239-254)
- 54 Carrie A.S. PLANTAP: A package for group
technology and plant layout.
(Advances in Computer Aided
Manufacture, D.McPherson, ed.

- North-Holland Publishing Comp.
1977)
- 55 Carrie A.S. Computer-aided layout planning-
the way ahead.
(INT.J.PROD.RES., 1980,
Vol. 18, No.3, 283-294)
- 56 Ross G.C. PLANTEC,
Internal Memo MI/331.
(East Kilbride:Computer Aided
Manufacturing Division,
National Engineering Laboratory)
- 57 Tompkins J.A. and Computer Aided Layout: A User's
Moore J.M. Guide.
(Facilities Planning and Design
Division, American Insitute of
Industrial Engineers, Inc. 1978)
- 58 Konz Stephan Facilities design.
(John Wiley and Sons, Inc., 1985)
- 59 Muther R. and Four approaches to
McPherson K. computerised layout planning.
(Industrial Engineering,
Feb. 1970)
- 60 Rosenblatt Meir.J. The facilities layout problem:
a multi-goal approach.

(INT.J.PROD.RES., 1979,
Vol. 17, No.4, 323-332)

- 61 Liggett R.S. A partitioning approach to large
 floor plan layout problems.
 (CAD 80:Int.Conf. and Exhibition
 on Computers in Design Eng.
 4th Brighton, Mar. 31-Apr.3 1980,
 Proceedings Published by IPC Sci.
 and Technol.Press, Guilford
 Surrey, 1980)
- 62 Kaltnekar Z. Some algorithms for decision-
 making about layout of
 production systems.
 (INT.J.PROD.RES., 1980,
 Vol.18, No.4, 467-478,
 PERA abstract No.1 85047 12)
- 63 Foulds L.R. and Some graph theoretic approaches
 Giffin J.W. to certain facilities layout
 models.
 (Research Report No.84-10,
 Dept.of Industrial and Systems
 Eng.,University of Florida,
 Mar. 1984)
- 64 Giffin J.W., Drawing a block plan from
 Foulds L.R. and a REL chart with graph theory
 Cameron D.C. and a microcomputer.

- (Research Report No. 84-9,
Dept. of Industrial and Systems
Eng., Univerisity of Florida,
Mar. 1984)
- 65 Foulds L.R. and
Giffin J.W. A graph theoretic heuristic
for minimizing total transportation
cost in facilities layout.
(Research Report No.84-20,
Dept. of Industrial and System
Eng., University of Florida,
April 1984)
- 66 Foulds L.R.
Giffin J.W. and
Evans J.D. Towards a new decision support
system for facilities layout
planners.
(Research Report No.85-1,
Dept. of Industrial and System
Eng., University of Florida,
Sept.1985)
- 67 Herroelen W. and
Van Gils A. On the use of flow dominance
in complexity measures for
facility layout problems.
(INT.J.PROD.RES., 1985,
Vol.23, No.1, 97-108)
- 68 Driscoll J. and
Sawyer J.H.R. A computer model for investi-
gating the relayout of batch
production areas.

- (INT.J.PROD.RES., 1985,
Vol.23, No.4, 783-794)
- 69 Baer T. MAPping the factory.
(Mechanical Engineering,
Jan. 1986)
- 70 Tice S.E. Interactive Computer Graphics
Model and Simulat On-orbit
Operatios.
(Mechanical Engineering,
Feb. 1986)
- 71 Grant J.W. and Factors To Consider In Choosing
Weiner S.A. A Graphically Animated
Simulation System.
(Industrial Engineering,
Aug. 1986, 36-40,65-68)
- 72 Buyers guide to CAD Systems.
(Draughting and Design, 1987,
Vol.7, No.7, 9.June, 12-17)
- 73 Ministry of Planned Maintenance.
Technology (London, A.H.S. Lucas, 1966)
- 74 Clifton R.H. Principles of Planned
Maintenance.
(London, Edward Arnold, 1974)
- 75 Heintzelman J.E. The complete handbook

- of maintenance management.
(Prentice-Hall, 1978)
- 76 Patton J.D., Jr. Preventive Maintenance.
(Research Triangle Park, NC:
Instrument Society of
America, 1983)
- 77 Burbridge J.L. The Japanese Kanban
System.
(Institute of Production
Control- January/February
1982; PERA I 86552 5)
- 78 Voss C.A. Two sides of the JIT coin-
Japan and UK.
(CME, April 1988)
- 79 Battersby A. A guide to Stock Control.
(Pitman, 1970)
- 80 Marsden A. Just in Time - the People
implication.
(Ingersol Engineers, 1986)
- 81 Kvålseth Tarald Ergonomics of workstation
design.
(London, Butterworths, 1983)
- 82 Woodson W.E. and Human engineering guide
Conover D.E. for equipment designer.

(University of California
Press, 1964)

83 Kulwiec R.A.

Material Handling Handbook.

-Sponsored by ASME and

International Material

Management Society-

(New York, John Wiley

and Sons, 1985)

BRITISH STANDARDS

- | | | |
|----|------------------|--|
| 84 | British Standard | BS 5191:1975
Glossary of Production Planning
and Control terms
(Items: 12001,13006,13005,23004) |
| 85 | British Standard | BS 3138:1979
Glossary of terms used
in Work Study and Organisation
and Methods. |
| 86 | British Standard | BS 3811:1974
Maintenance Terms in
Terotechnology. |
| 87 | British Standard | BS 308:Part1:1984
Engineering drawings practice.
Recommendation for general
principles. |
| 88 | Act | Health and Safety at
Work Act 1974.
(Her Majesty's Stationary
Office, 1974) |

COMPUTING AND COMPUTER GRAPHICS

- 89 Haag James N. Comprehensive Standard Fortran Programming.
(Hayden Book Company, Inc.,
New York, 1970)
- 90 Hill Louis A., Jr. Stuctured Programming in Fortran.
(Prentice-Hall, Inc., 1981)
- 91 Nanney Ray.T. Computing.
A Problem-Solving Approach
with FORTRAN 77.
(Prentice-Hall,Inc., 1981)
- 92 Brainerd Walter S., FORTRAN 77 Programming.
Goldberg Charles H. (Harper & Row, Publishers, 1978)
and
Gross Jonathan L.
- 93 Vince John The Picaso System.
(Campus, 1983)
- 94 Vince John Picaso Programs.
(Campus, 1983)
- 95 Vince John An Intoroduction to Computer Graphics.
(Campus, Handout)

- 96 Vince John Fortran Coding Techniques.
(Campus, Handout)
- 97 Vince J.A. Dictionary of Computer
Graphics.
(Frances Pinter, 1984)
- 98 Gardan Y. and Interactive Graphs.
Lucas M. (Kogan Page Ltd., 1985)
- 99 Rooney J. and Principles of Computer-aided
Steadman P. Design.
(The Open University, 1987)

APPENDIX I

Appendix I

TERMINOLOGY

Standard terminology, given by British Standards, still fails to cover some areas in Production and Industrial Engineering. In these areas terminology varies from factory to factory and also internationally among English speaking countries. This is true especially in the field of Factory Layout Planning which is often accented by American English. Some terminology and expressions which, are frequently used in parallel, follow:

Item	Term	Parallel Expression(s)	Remarks
1	Plant Layout	Factory Layout Planning Facility Layout Facility Allocation Economic Activity Location	
2	Project Stage	Project Phase	e.g. Muther[4]
3	Feasibility Study	Programme Study Investment Study	
4	Investment Project	Programme Tender	e.g. Ford Motor Company
5	Project	Final Stage Project	

6	Working Drawings	Detail Drawings Shop Drawings "as made" drawings	
7	Introductory Project		intermediate stage
8	'technological' positioning	theoretical pos.	positioning to suit best technol. demands and economy of production
9	Preventive Maintenance	Regular Maintenance	
10	Manufacturing Services	Auxiliary Services Subsidiary Services	
11	Services	Energy supply	
12	Templates on 'Skins'	Templates and Tapes Templates and Paste	Tompkins and White[39] Farish[33]

APPENDIX II

C O M P U T E R P R O G R A M S

1. 'WSBUILDR.FOR'
2. 'WSRECALL.FOR'
3. 'CIVES.FOR'
4. 'IYTVAX00.FOR'
5. 'IYTWSFILE.FOR'
6. 'POSCLASH5.FOR'
7. 'DISPLAY.FOR'
8. 'MFEEED.FOR'
9. 'WSVTOTO.FOR'
10. 'M100.FOR'


```

1  C  *WSBUILDER.FOR* PROGRAM
2  C  FOR DESIGN/DRAWING OF WORK STATIONS AND EQUIP...
3  C  IMPROVED ON 1-6.10.86.
4  C  FURTHER IMPROVEMENT INTRODUCED ON 10.2.87.
5  C  FURTHER IMPROVEMENT ON 31.7.87 (*OPERATOR* ADDED)
6  C
7
8  REAL A(3000),B(5000),C(5000),R(2000)
9  INTEGER SIDES
10 LOGICAL FIRST
11 CHARACTER*12 FILNAM
12 CHARACTER*12 W$NAME
13 CHARACTER*12 TAGNO
14
15
16 FIRST = .TRUE.
17 C
18 C
19 WRITE (6,50)
20 50  FORMAT (' WORK STATION DESIGN PROGRAM. ')
21 C  Please start
22 C  &design from the origin using only positive figures ...
23 C  &including Work Station Module Volume...turning point is
24 C  &left bottom corner. This is important for Jo stick and
25 C  &automatic positioning as well!
26 CALL BELL
27 CALL REAPAG
28
29 WRITE (6,60)
30 60  FORMAT (' SHAPES and CODES'/' Select wanted')
31 CALL UPDISC (FILNAM,10)
32
33 30  CONTINUE
34 WRITE (6,5001)
35 5001 FORMAT (' BX  BOX-shaped PARTS,start with foundat.plate')
36 WRITE (6,5020)
37 5020 FORMAT (' AB  ANCHORING BOLTS or FOUNDATION BOLTS')
38 WRITE (6,5030)
39 5030 FORMAT (' CY  CYLINDRICAL PARTS')
40 WRITE (6,5040)
41 5040 FORMAT (' CO  CONICAL PARTS')
42 WRITE (6,5050)
43 5050 FORMAT (' PY  PYRAMIDAL PARTS')
44 WRITE (6,5060)
45 5060 FORMAT (' SP  SPHERICAL PARTS')
46 WRITE (6,5090)
47 5090 FORMAT (' OP  OPERATOR')
48 WRITE (6,5070)
49 5070 FORMAT (' TN  TAG NUMBER a unique identification no')
50 WRITE (6,5080)
51 5080 FORMAT (' XX  NO MORE SHAPES REQUESTED-END OF SESSION',/)
52 WRITE (6,35)
53 35  FORMAT (' Please write the selected CODE')
54 CALL BELL
55
56 READ(6,40)CODE
57 40  FORMAT(A2/)
58 IF (CODE.EQ.'BX') GOTO 200
59 IF (CODE.EQ.'AB') GOTO 300
60 IF (CODE.EQ.'CY') GOTO 400

```

3.

```

61      IF (CODE.EQ."CG") GOTO 500
62      IF (CODE.EQ."PY") GOTO 600
63      IF (CODE.EQ."SP") GOTO 700
64      IF (CODE.EQ."OP") GOTO 900
65      IF (CODE.EQ."IN") GOTO 800
66      IF (CODE.EQ."XX") GOTO 100
67      C
68      C      IF THE ENTRY DOES NOT CORRESPOND WITH THE CODE
69      C      THE ERROR MESSAGE IS WRITTEN
70      C
71      CALL BELL
72
73      WRITE (6,70)
74      70      FORMAT (' Please enter your response again - using CAPITALS')
75      GOTO 30
76
77      200      CONTINUE
78      C
79      C      BOX SHAPES ARE INTRODUCED
80      C
81      CALL BELL
82      WRITE (6,210)
83      210      FORMAT (' Please enter dim. for X,Y,Z,ROT,XS,YS,ZS in cm!"/)
84      C
85      C      NOTE DIMENSIONS MUST BE PUT IN CENTIMETERS
86      C      NUMBERS MUST BE ENTERED IN 5 FIG.,DEC.POIN AND 2 FIG.FORM
87      C      ROTATION IN DEGREE (EXAMPLE 30.0)
88      C
89      READ (5,220,END=230) X,Y,Z,ROT,XS,YS,ZS
90      WRITE (10,220) X,Y,Z,ROT,XS,YS,ZS
91      220      FORMAT (7F8.2/)
92      CALL BOX (A,X,Y,Z)
93      CALL TURN3D (A,ROT,0.0,0.0,2,b)
94      CALL SHIFT3 (P,XS,YS,ZS)
95      230      CONTINUE
96      GOTO 1000
97
98      300      CONTINUE
99      CALL BELL
100     C
101     C      SHAPES OF ENCHORING BOLTS ARE INTRODUCED
102     C
103
104     WRITE(6,310)
105     310     FORMAT (' Please enter data for ROTation and Shift XS,YS,ZS"/)
106     READ(5,320,END=330)ROT,XS,YS,ZS
107     WRITE(10,320)ROT,XS,YS,ZS
108     320     FORMAT(4F8.2/)
109     CALL FBOLT (A)
110     CALL TURN3D(A,ROT,0.0,0.0,2,b)
111     CALL SHIFT3(b,XS,YS,ZS)
112     330     CONTINUE
113     GOTO 1000
114
115     400     CONTINUE
116     CALL BELL
117     C
118     C      CYLINDRICAL PARTS ARE INTRODUCED
119     C
120     WRITE(6,405)

```

4.

```

121 405 FORMAT(' Please write dim. DIA,HEIGHT,SIDES,ROT,XS,YS,ZS'/)
122
123 READ (5,410,END=420)DIA,HEIG,SIDES,ROT,XS,YS,ZS
124 *WRITE(10,410)DIA,HEIG,SIDES,ROT,XS,YS,ZS
125 410 FORMAT(2F8.2,18,4F8.2)
126 CALL CYLIND(A,DIA,HEIG,SIDES)
127 CALL TURN3D(A,ROT,0.0,0.0,2,B)
128 CALL SHIFT3(B,XS,YS,ZS)
129 420 CONTINUE
130 GOTO 1000
131
132
133 500 CONTINUE
134 CALL BELL
135 C
136 C CONICAL PARTS ARE INTRODUCED HERE
137 C
138 *WRITE (6,510)
139 510 FORMAT (' Please enter dim. of cone DIAM,HEIGHT and No of
140 &sides,rotation ROT and shift XS,YS,ZS'//)
141 READ (5,520,END=530)DIAM,HEIGHT,NO,ROT,XS,YS,ZS
142 *WRITE (10,520) DIAM,HEIGHT,NO,ROT,XS,YS,ZS
143 520 FORMAT (2F8.2,114,4F8.2)
144 CALL CONE (A,DIAM,HEIGHT,NO)
145 CALL TURN3D (A,ROT,0.0,0.0,2,B)
146 CALL SHIFT3 (B,XS,YS,ZS)
147 530 CONTINUE
148 GOTO 1000
149 C
150 600 CONTINUE
151 CALL BELL
152 C
153 C PYRAMIDAL PARTS ARE INTRODUCED HERE
154 C
155 *WRITE(6,610)
156 610 FORMAT (' Please enter dimensions for Pyramidal parts WIDTH,
157 &DEPTH,HEIGHT and ROTATION and Shift XS,YS,ZS'//)
158 READ (5,620,END=630) WIDTH,DEPTH,HEIGHT,ROT,XS,YS,ZS
159 *WRITE (10,620) WIDTH,DEPTH,HEIGHT,ROT,XS,YS,ZS
160 620 FORMAT (7F8.2)
161 CALL PYRAM (A,WIDTH,DEPTH,HEIGHT)
162 CALL TURN3D (A,ROT,0.0,0.0,2,B)
163 CALL SHIFT3 (B,XS,YS,ZS)
164 630 CONTINUE
165 GOTO 1000
166
167
168 700 CONTINUE
169 CALL BELL
170
171 C
172 C HERE ARE INTRODUCED ALL SPHERICAL PARTS
173 C
174 *WRITE (6,710)
175 710 FORMAT (' Please enter dimension for spherical parts DIAM,
176 &NH_no of horizontal tiles and NV_no of vertical tiles
177 &and ROTATION and Shift XS,YS,ZS'//)
178
179
180 READ (5,720,END=730)DIAM,NH,NV,ROT,XS,YS,ZS

```

```

181      WRITE (10,720)DIAM,HH,NV,ROT,XS,YS,ZS
182 720   FORMAT (1F8.2,2I8,4F8.2)
183      CALL SPHERE (A,DIAM,HH,NV)
184      CALL TURN3D(A,ROT,0.0,0.0,2,B)
185      CALL SHIFT3(B,XS,YS,ZS)
186 730   CONTINUE
187      GOTO 1000
188
189 900   CONTINUE
190      CALL BELL
191  C
192  C      3-D TEMPLATE/MODEL OF 'OPERATOR' IS INTRODUCED
193  C
194      *WRITE (6,910)
195 910   FORMAT (' Please enter data for ROTATION and SHIFT...
196      &XS,YS,ZS' /)
197      READ (5,920,END=930)ROT,XS,YS,ZS
198      *WRITE (10,920)ROT,XS,YS,ZS
199 920   FORMAT (4F8.2)
200      CALL OPERATOR (A)
201      CALL TURN3D (A,ROT,0.0,0.0,2,B)
202      CALL SHIFT3 (B,XS,YS,ZS)
203 930   CONTINUE
204      GOTO 1000
205
206 800   CONTINUE
207      CALL BELL
208  C
209  C      HERE IS INTRODUCED A TAG NUMBER
210  C
211      *WRITE (6,810)
212 810   FORMAT (' Please enter TAG NO, ROTation and shift XS,YS,ZS'/)
213      READ (5,820,END=830)TAGNO,ROT,XS,YS,ZS
214      *WRITE (10,820)TAGNO,ROT,XS,YS,ZS
215 820   FORMAT(A6,1F8.2)
216      CALL BERSH(TAGNO,6,2,60.0,E)
217      CALL TRANSP(R,A)
218      CALL TURN3D (A,ROT,0.0,0.0,2,B)
219      CALL SHIFT3 (B,XS,YS,ZS)
220 830   CONTINUE
221      GOTO 1000
222
223 1000  CONTINUE
224      IF (FIRST) GOTO 1010
225      CALL JOIN (B,C)
226
227      GOTO 30
228
229 1010  CONTINUE
230      CALL COPY (B,C)
231      FIRST = .FALSE.
232      GOTO 30
233
234 100   CONTINUE
235      CALL CLDISC (FILNAM,10)
236
237      CALL UPDISC('ASFDIM',10)
238      FAC  =DIN('FAC  ')
239      FORA =DIN('FORX ')
240      FORY =DIN('FORY ')

```

```

241 FRAX1 =DIN("FRAX1 ")
242 FRAX2 =DIN("FRAX2 ")
243 FRAY1 =DIN("FRAY1 ")
244 FRAY2 =DIN("FRAY2 ")
245 PICPLA=DIN("PICPLA")
246 DISTNC=DIN("DISTNC")
247 ROTATN=DIN("ROTATN")
248 ELEVTN=DIN("ELEVTN")
249 CALL CLDISC("WSPDIA",10)
250 CALL NEWPAG
251 CALL START
252 C CALL FACTOR(FAC)
253 CALL FORMAT(FGRX,FGRY)
254 CALL FRAME(FRAX1,FRAX2,FRAY1,FRAY2)
255 CALL PLANE(PICPLA)
256 CALL PEYE(0.0,0.0,0.0,DISTNC,ROTATN,ELEVTN)
257 CALL DRAWIT(C)
258 CALL HCLOSE
259 CALL FINISH
260 C
261 C IF THE SHAPE IS ACCORDING TO OUR REQUIREMENT SAY YES
262 C
263 WRITE(6,2100)
264 2100 FORMAT(" Is the work Station of a required likeness YE/NO?")
265
266 READ (5,2110)ANS
267 2110 FORMAT(A2/)
268 IF (ANS.EQ."NO".OR.ANS.EQ."N") GOTO 30
269 IF (ANS.EQ."YE".OR.ANS.EQ."Y") GOTO 2200
270
271 2200 CONTINUE
272 C
273 C WORK STATION DETAILED DRAWN BY HELP OF THE ABOVE PROGRAM
274 C IS FILED UNDER A UNIQUE TAG NUMBER
275 C EACH WORK STATION HAS GOT ITS OWN FILE
276 C
277 WRITE(6,2300)
278 2300 FORMAT(" ENTER FILENAME/VSNAME=a tag No. of work station drawn")
279 READ(5,2310)VSNAME
280 2310 FORMAT(A12)
281 CALL OUT30(C,VSNAME)
282 STOP
283 END
284 C
285 C
286 C "FBOLT" - FOUNDATION BOLT
287 C THIS IS A SUBROUTINE DRAWING AN ANCHORING BOLT
288 C
288 C...
290
291 SUBROUTINE FBOLT (F)
292
293 READ D(39), E(88), F(127)
294 CALL LINE3D(D,0.0,0.0,2.0,0.0,0.0,-2.0,10)
295 CALL LINE3D(E,2.0,0.0,0.0,-2.0,0.0,0.0,10)
296 CALL JOIN(D,E)
297 CALL LINE3D(F,0.0,2.0,0.0,0.0,-8.0,0.0,10)
298 CALL JOIN(E,F)
299 RETURN
300 END

```


7.

```

301 C
302 C      *OPERATOR* -3-D TEMPLATE
303 C
304 C      SUBROUTINE OPERATOR (T)
305 C
306 C      TRUNK, ARMS, LEGS
307 C
308 C      REAL A(100), B(150), C(900)
309 C      READ
310 C      REAL F(1000), D(1200), T(2000)
311
312
313 CALL BOX (A, 55.0, 60.0, 35.0)
314 CALL SHIFTS (A, 0.0, 90.0, 0.0)
315 CALL BOX (B, 10.0, 90.0, 20.0)
316 CALL JOIN (A, B)
317 CALL BOX (C, 10.0, 90.0, 20.0)
318 CALL SHIFTS (C, 35.0, 0.0, 0.0)
319 CALL JOIN (B, C)
320 CALL BOX (F, 20.0, 25.0, 20.0)
321 CALL SHIFTS (F, 27.0, 150.0, 0.0)
322 CALL JOIN (C, F)
323 CALL CODE (D, 20.0, 15.0, 6)
324 CALL TURNED (E, 270.0, 0.0, 0.0, 1, T)
325 CALL SHIFTS (T, 27.0, 155.0, -20.0)
326 CALL JOIN (F, T)
327 CALL DRAWIT(T)
328
329 RETURN
330 END
331 C
332 C...
333 C
334 C... EDITOR UNDER THE NAME *%FILE.FOR*
335 C

```

[illegible]

W	W	SSSS	RRRR	EEEE	CCCC	AAA	L	L			
W	W	S	R	R	E	C	A	A	L	L	
W	W	S	R	R	R	E	C	A	A	L	L
W	W	SSS	RRRR	EEEE	C	A	A	A	L	L	
W	W	W	S	R	R	E	C	AAAAA	L	L	
W	W	W	S	R	R	E	C	A	A	L	L
W	W	SSSS	R	R	EEEE	CCCC	A	A	LLLLL	LLLLL	

160) queued to SYS\$PRINT on 9-NOV-1987 12:13 by user BDB1, UIC (RESM0012,60B1), under account RE
printer _LPA0: on 9-NOV-1987 12:14 from queue LPA0.

```

*****  

Digital Equipment Corporation - VAX/VMS Version V4.5 *****  

*****

```

9.

```

1  C   PROGRAM "RECALLWS.FOR"
2  C   THIS PROGRAM IS RECALLING/PRESENTING THE WORK STATIONS DRAWN
3  C   BY MEPL OF PROGRAM WSFILE.FOR
4  C
5      REAL V(5000)
6      CHARACTER*12 ASNAME
7      CHARACTER*12 TAGNO
8      CALL OPDISC("NSFDIR",10)
9      FAC  =DIN("FAC  ")
10     FORX =DIN("FORX ")
11     FORY =DIN("FORX ")
12     FRAX1=DIN("FRAX1 ")
13     FRAX2=DIN("FRAX2 ")
14     FRAY1=DIN("FRAY1 ")
15     FRAY2=DIN("FRAY2 ")
16     PICPLA=DIN("PICPLA")
17     DISTNC=DIN("DISTNC")
18     ROTATN=DIN("ROTATN")
19     ELEVTN=DIN("ELEVTN",10)
20     CALL CLDISC("SEFDIR",10)
21     CALL START
22     CALL FACTOR(FAC)
23     CALL FORMAT(FORX,FOXY)
24     CALL FRAME(FRAX1,FRAX2,FRAY1,FRAY2)
25     CALL PLANE(PICPLA)
26     CALL PEYE(0.0,0.0,0.0,DISTNC,ROTATN,ELEVTN)
27
28     WRITE (6,50)
29 50    FORMAT (' Please write in the work Station tag No. ')
30     READ(5,60) TAGNO
31 60    FORMAT(A12)
32     CALL IN3D(V,TAGNO)
33     CALL DRAWIT (V)
34     CALL PCLOSE
35     CALL FINISH
36     STOP
37     END
38
39  C
40  C... FILE UNDER THE NAME "RECALLWS.FOR"
41  C

```


II.

```

1  C "CIVES.FOR" PROGRAM IS WRITTEN FOR DESIGN OF CIVIL
2  C ENGINEERING SPACE (SECTION OF A BAY) - CONSISTING
3  C OF CIVIL ENGINEERING ELEMENTS (HERE PRESENTED AS
4  C BOXES ONLY!)
5  C
6  C DATA ARE FEED IN MANUALLY ONLY
7  C (EXCEPT "DIN" FEEDING)
8  C
9  C PRINTER AND VDU IS USED
10 C
11 C
12 REAL A(98),B(98), CESPAC (10000)
13 REAL XWID(100),YWID(100),ZWID(100),XDIS(100),YDIS(100),ZDIS(100)
14 REAL DGR(100),ZT(100),XT(100)
15
16 INTEGER NCEE
17 INTEGER SELECT,DESEL, ALPHA,GRAPHI
18 DATA SELECT/"40033/"
19 DATA DESEL/"40433/"
20 DATA ALPHA/"30/"
21 DATA GRAPHI/"35/"
22
23
24 C WRITE(6,10)ALPHA
25 C10 FORMAT("+",A2,S)
26 C WRITE(6,10)SELECT
27 C WRITE(6,20)
28 20 FORMAT(" Program for design of a Civil Eng. Space(bay) in 3-D")
29 C WRITE(6,10)DESEL
30 C WRITE(6,10)GRAPHI
31 C
32 C THE CIVIL ENGINEERING ELEMENTS AND
33 C OTHER SPACES - ALL DIMENSIONS SHOULD BE ENTERED IN DECIMETERS (DM)
34 CALL START
35 CALL GPODISC("CIVDIS",10)
36 DISTNC=DIN("DISTNC")
37 ROTATN=DIN("ROTATN")
38 ELEVTN=DIN("ELEVTN")
39 ZOOM =DIN("ZOOM ")
40 NLX =DIN("NLX ")
41 NLY =DIN("NLY ")
42 NLZ =DIN("NLZ ")
43 SPACE =DIN("SPACE ")
44 CALL CLDISC("CIVDIS",10)
45 CALL FORMAT (80,0,80,0)
46 CALL FRAME(-55.0,25.0,-35.0,25.0)
47 CALL POTE (0.0,0.0,0.0,DISTNC,ROTATN,ELEVTN)
48 CALL PLANE (ZOOM)
49 CALL RESH(NLX,NLY,NLZ,SPACE)
50
51 C PRESENT SITUATION IS DRAWN
52
53 CALL PRESENT
54 C
55 C NEW DEVELOPMENT STARTS IF REQUESTED
56 C
57 CALL DEVELOP
58 CALL GCLOSE
59 CALL FINISH
60 STOP

```

12.

```

61      END
62      C...
63
64      SUBROUTINE DEVELOP
65      REAL A(98),B(98), CESPAC (10000)
66      REAL XWID(100),YWID(100),ZWID(100),XDIS(100),YDIS(100),ZDIS(100)
67      REAL DGR(100),ZT(100),XT(100)
68
69      INTEGER NCEE
70      INTEGER SELECT,DESEL, ALPHA,GRAPH1
71      DATA SELECT/"40033/
72      DATA DESEL/"40433/
73      DATA ALPHA/"30/
74      DATA GRAPH1/"35/
75
76
77      C      WRITE(6,10)ALPHA
78      C10    FORMAT(" ",A2,S)
79      C      WRITE(6,10)SELECT
80
81      C      IF REQUESTED A NEW DEVELOPMENT FOLLOWS
82
83      C50    CONTINUE
84      C      WRITE (6,60)
85      C60    FORMAT (' Do you wish to change/develop the Layout...YES/NO')
86      C      READ (5,70)ANS
87      C70    FORMAT (A2)
88      C      IF (ANS.EQ.'NO'.OR.ANS.EQ.'N') GOTO 500
89      C      IF (ANS.EQ.'YE'.OR.ANS.EQ.'N') GOTO 125
90      C      WRITE (6,120)
91      C120   FORMAT (' Please enter your response again')
92      C      GOTO 50
93      C125   CONTINUE
94      C      CALL NEWPAC
95      C130   CONTINUE
96      C      CALL OPENISC ('CELDIM',10)
97      C      READ(10,190,END=135)1,XWID(1),YWID(1),ZWID(1),XDIS(1),YDIS(1),
98      C      &ZDIS(1),DGR(1),ZT(1),XT(1)
99
100     C      WRITE(6,190)1,XWID(1),YWID(1),ZWID(1),XDIS(1),YDIS(1),
101     C      &ZDIS(1),DGR(1),ZT(1),XT(1)
102     C      GOTO 130
103     C135    CONTINUE
104     C      CALL CLDISC ('CELDIM',10)
105
106     C      WRITE(6,10)ALPHA
107     C      WRITE(6,10)SELECT
108     C      WRITE(6,140)
109     C140    FORMAT(' PLEASE ENTER NO. OF CIV,E. ELEMENTS(NCEE) REQUIRED')
110     C      WRITE(6,10)DESEL
111     C      WRITE(6,10)GRAPH1
112     C      READ(5,*)NCEE
113     C      WRITE(6,150)NCEE
114     C150    FORMAT(I3)
115     C      WRITE(6,10)ALPHA
116     C      WRITE(6,10)SELECT
117     C      WRITE(6,160)NCEE
118     C160    FORMAT(I3)
119     C      WRITE(6,10)DESEL
120     C      WRITE(6,10)GRAPH1

```

13.

```

121 C WRITE(6,10)ALPHA
122 C WRITE(6,10)SELECT
123 WRITE(6,260)
124 260 FORMAT (' Please enter Item No., dim. & posn. of objects in dm
125 & to end development/extending type 99 ')
126 WRITE (6,270)
127 270 FORMAT (' I',2A,'XWID',4X,'YWID',4X,'ZWID',4X,'XDIS',4X,'YDIS',4X,
128 &'ZDIS',5X,'DGR',5X,'ZT',5X,'XT')
129 C WRITE(6,10)DESEL
130 C WRITE(6,10)GRAPH1
131 280 CONTINUE
132 READ(5,190)I,XWID(I),YWID(I),ZWID(I),XDIS(I),YDIS(I),ZDIS(I),
133 &DGR(I),ZT(I),XT(I)
134 IF (I.NE.99) GOTO 280
135 C WRITE(6,10)ALPHA
136 C WRITE(6,10)SELECT
137 CALL OPDISC ('CELDIM',10)
138 DO 200 I=1,99
139 IF (XWID(I).EQ.0.0.AND.YWID(I).EQ.0.0) GOTO 200
140 WRITE(6,190)I,XWID(I),YWID(I),ZWID(I),XDIS(I),YDIS(I),ZDIS(I),
141 &DGR(I),ZT(I),XT(I)
142 190 FORMAT(13,9F8.2)
143 C WRITE(6,10)DESEL
144 C WRITE(6,10)GRAPH1
145 WRITE(10,190)I,XWID(I),YWID(I),ZWID(I),XDIS(I),YDIS(I),ZDIS(I),
146 &DGR(I),ZT(I),XT(I)
147 200 CONTINUE
148 CALL CLDISC ('CELDIM',10)
149 C
150 C A PAUSE IS INTRODUCED FOR CHECKING
151 C TO CONTINUE TYPE "G"
152 C
153 CALL CESPAC
154 DO 300 I = 1,99
155 IF (XWID(I).EQ.0.0.AND.YWID(I).EQ.0.0) GOTO 300
156 CALL BOX (A,XWID(I),YWID(I),ZWID(I))
157 CALL SHIFT3(A,XDIS(I),YDIS(I),ZDIS(I))
158 CALL TURN3D (A,DGR(I),ZT(I),XT(I),2,B)
159 IF (I.EQ.1) CALL COPY (B,CESPAC)
160 IF (I.NE.1) CALL JOIN (B,CESPAC)
161 300 CONTINUE
162 CALL DRAWIT (CESPAC)
163 CALL GOT3D (CESPAC,'CIVILD')
164 GOTO 50
165 500 CONTINUE
166 RETURN
167 END
168
169 C
170 C...
171 SUBROUTINE MESH(NLX,NLY,NLZ,SPACE)
172 REAL A(1000)
173 CALL GRIL3D(A,NLX,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,SPACE,.0,.0)
174 CALL DRAWIT(A)
175 CALL GRIL3D(A,NLY,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE,.0)
176 CALL DRAWIT(A)
177 CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,.0,.0,SPACE)
178 CALL DRAWIT(A)
179 CALL GRIL3D(A,NLY,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,.0,SPACE,.0)
180 CALL DRAWIT(A)

```

14.

```

181      CALL GRIL3D(A,NLX,.0,.0,.0,.0,FLUAT(NLZ-1)*SPACE,SPACE,.0,.0)
182      CALL DRAWIT(A)
183      CALL GRIL3D(A,NLZ,.0,.0,.0,FLUAT(NLX-1)*SPACE,.0,.0,.0,SPACE)
184      CALL DRAWIT(A)
185      RETURN
186      END
187  C...
188      SUBROUTINE PRESENT
189      REAL A(98),B(98),CESPAC(10000)
190      REAL XWID(100),YWID(100),ZWID(100),XDIS(100),YDIS(100),ZDIS(100)
191      REAL DGR(100),ZT(100),XT(100)
192
193      INTEGER NCEE
194      INTEGER SELECT,DESEL,ALPHA,GRAPH1
195      DATA SELECT/'40033'/
196      DATA DESEL/'40433'/
197      DATA ALPHA/'30'/
198      DATA GRAPH1/'35'/
199
200
201  C      WRITE(6,10)ALPHA
202  C10    FORMAT(' ',A2,S)
203  C      WRITE(6,10)SELECT
204
205      WRITE (6,20)
206  20    FORMAT(' LAYOUT...The present situation of development')
207      CALL SELL
208      CALL OPDISC('CIVDIM',10)
209      DISINC=DIN('DISTHC')
210      ROTATH=DIN('ROTATH')
211      ELEVTH=DIN('ELEVTH')
212      ZOOM=DIN('ZOOM ')
213      NLX=DIN('NLX ')
214      NLY=DIN('NLY ')
215      NLZ=DIN('NLZ ')
216      SPACE=DIN('SPACE ')
217      CALL CLDISC('CIVDIM',10)
218      CALL RESO(NLX,NLY,NLZ,SPACE)
219      CALL OPDISC ('CELDIM',10)
220
221  60    CONTINUE
222      READ(10,90,END=110)1,XWID(1),YWID(1),ZWID(1),XDIS(1),YDIS(1),
223      &ZDIS(1),DGR(1),ZT(1),XT(1)
224  90    FORMAT(13,9F8.2)
225  C      WRITE(6,90)1,XWID(1),YWID(1),ZWID(1),XDIS(1),YDIS(1),
226  C      &ZDIS(1),DGR(1),ZT(1),XT(1)
227      GOTO 60
228  110   CONTINUE
229      CALL CLDISC ('CELDIM',10)
230      DO 150 I=1,99
231      CALL BGA (A,XWID(I),YWID(I),ZWID(I))
232      CALL SHIFB(A,XDIS(I),YDIS(I),ZDIS(I))
233      CALL TURN3D (A,DGR(I),ZT(I),XT(I),2,B)
234      IF (1.EQ.1) CALL COPY (B,CESPAC)
235      IF (1.NE.1) CALL JOIN (B,CESPAC)
236  150   CONTINUE
237      CALL DRAWIT (CESPAC)
238      RETURN
239      END
240

```


15.

241 C....
241 C THIS IS *CIVES3.FOR PROGRAM
241 C USING PRINTER (COMMANDS) AND *DIR* FUNCTIONS
241 C


```

1  C      'IYTVAA00.FOR'
2  C      INTERACTIVE LAYOUT PROGRAM
3  C      FOR MANUAL POSITIONING OF ANY 'OBJECTS'
4  C      (WORK STATION, DEPARTMENTS, BAYS, HALLS IN PLOT ETC.)
5  C      USING 'LARGEST VOLUMES' ONLY
6  C
7  C
8      REAL X,Y,Z,P,XPOS,ZPOS,ANGLE
9      INTEGER NWS
10     COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
11     $FNAME
12     CHARACTER*12 FNAME(77)
13     DATA X,Y,Z/231*999.0/
14     DATA XPOS,ZPOS/154*999.0/
15     DATA ANGLE/77*0.0/
16     CALL START
17     CALL WSVOL
18     CALL OPDISC('MESDIM',10)
19     FAC =DIN('FAC  ')
20     FORX =DIN('FORX  ')
21     FORY =DIN('FORY  ')
22     FRAX1 =DIN('FRAX1 ')
23     FRAX2 =DIN('FRAX2 ')
24     FRAY1 =DIN('FRAY1 ')
25     FRAY2 =DIN('FRAY2 ')
26     PICPLA=DIN('PICPLA')
27     DISTNC=DIN('DISTNC')
28     ROTATN=DIN('ROTATN')
29     ELEVTN=DIN('ELEVTN')
30     ZOOM =DIN('ZOOM  ')
31     NLX =DIN('NLX  ')
32     NLY =DIN('NLY  ')
33     NLZ =DIN('NLZ  ')
34     SPACE =DIN('SPACE ')
35     CALL CLDISC('MESDIM',10)
36     C      CALL FACTOR(FAC)
37     CALL FORMAT(FORX,FORY)
38     CALL FRAME(FRAX1,FRAX2,FRAY1,FRAY2)
39     CALL PLANE(PICPLA)
40     CALL PEYE(0.0,0.0,0.0,DISTNC,ROTATN,ELEVTN)
41     CALL MESH(NLX,NLY,NLZ,SPACE)
42     CALL NCLOSE
43     CALL OPDISC('WSVOLD',10)
44     NAS=1
45     5    READ(10,10,END=20)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
46     10    FORMAT(15,3F6.2,A12)
47     NWS=NWS+1
48     GOTO 5
49     20    CALL CLDISC('WSVOLD',10)
50     NWS=NAS-1
51     CALL PRESIT(NWS)
52     CALL JOYST(NWS,PICPLA,DISTNC)
53     CALL FINISH
54     STOP
55     END
56     C...
57     SUBROUTINE WSVOL
58     INTEGER ANS,NWS
59     COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
60     $FNAME

```

18.

```

61      INTEGER SELECT,DESEL, ALPHA,GRAPH1
62      CHARACTER*12 FNAME(77)
63      DATA SELECT/'40033'/
64      DATA DESEL/'40433'/
65      DATA ALPHA/'30'/
66      DATA GRAPH1/'35'/
67      C
68      C      OUTPUT OF CURRENT DATA FILE
69      C
70      WRITE(6,10)ALPHA
71      10  FORMAT('+',A2,S)
72      *WRITE(6,10)SELECT
73      WRITE(6,20)
74      20  FORMAT(' File of existing Work Station Module volumes')
75      CALL OPDISC('WSVOLD',10)
76      30  CONTINUE
77      READ(10,40,END=60)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
78      40  FORMAT(15,3F8.2,A12)
79      *WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
80      50  FORMAT(15,3F8.2,1X,A12)
81      C      PLEASE NOTE ABOVE WAS THE EXTRA SPACE '1X'DELETED
82      GOTO 30
83      60  CONTINUE
84      CALL CLDISC('WSVOLD',10)
85      C
86      C      EXTEND FILE?
87      C
88      WRITE(6,70)
89      70  FORMAT(' Do you wish to extend/update the existing file-YE or NO')
90      *WRITE(6,10)DESEL
91      *WRITE(6,10)GRAPH1
92      80  READ(5,85)ANS
93      85  FORMAT(A2)
94      IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 150
95      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 100
96      WRITE(6,90)
97      90  FORMAT(' Please enter your response again')
98      GOTO 80
99      100  CONTINUE
100     *WRITE(6,110)
101     110  FORMAT(' PLEASE ENTER WS No.,X,Y,Z,DIM OF *S AND TAG No OF WS...
102     &TO END EXTENDING TYPE 77')
103     120  CONTINUE
104     READ(5,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
105     IF(J.NE.77)GOTO 100
106     C
107     C      OUTPUT LATEST DATA TO DISC AND TERMINAL
108     C
109     WRITE(6,10)ALPHA
110     *WRITE(6,10)SELECT
111     WRITE(6,20)
112     CALL OPDISC('WSVOLD',10)
113     130  CONTINUE
114     DO 140 J=1,76
115     IF (X(J).EQ.999.0.AND.Y(J).EQ.999.0)GOTO 140
116     *WRITE(10,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
117     *WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
118     140  CONTINUE
119     CALL CLDISC('WSVOLD',10)
120     *WRITE(6,10)DESEL

```

C 19.

```

121 WRITE(6,10)GRAPHI
122 150 CONTINUE
123 RETURN
124 END
125 C...
126 C...
127 SUBROUTINE MESH(NLX,NLY,NLZ,SPACE)
128 REAL A(1000)
129 CALL GRILL3D(A,NLX,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,SPACE,.0,.0)
130 CALL DRAWIT(A)
131 CALL GRILL3D(A,NLY,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE,.0)
132 CALL DRAWIT(A)
133 CALL GRILL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,.0,.0,SPACE)
134 CALL DRAWIT(A)
135 CALL GRILL3D(A,NLY,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,.0,SPACE,.0)
136 CALL DRAWIT(A)
137 CALL GRILL3D(A,NLX,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,SPACE,.0,.0)
138 CALL DRAWIT(A)
139 CALL GRILL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,.0,SPACE)
140 CALL DRAWIT(A)
141 RETURN
142 END
143 C...
144 C THIS IS A SUBROUTINE FOR SHOWING THE PRESENT SITUATION
145
146 SUBROUTINE PRESIT(NWS)
147 READ P(500),F(2000),G(2000),I(2000),U(2000)
148 INTEGER NWS
149 COMMON/DCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
150 &FNAME
151 INTEGER SELECT,DESEL, ALPHA,GRAPHI
152 CHARACTER*12 FNAME(77)
153 DATA SELECT/'40033'/
154 DATA DESEL/'40433'/
155 DATA ALPHA/'30'/
156 DATA GRAPHI/'35'/
157 C PRINTING THE PRESENT SITUATION OF LAYOUT DEVELOPMENT
158 WRITE(6,10)
159 10 FORMAT(' LAYOUT-the existing situation of development')
160 CALL BELL
161 CALL OPDISC('MESHIM',10)
162 NLX =DIN('NLX ')
163 NLY =DIN('NLY ')
164 NLZ =DIN('NLZ ')
165 SPACE =DIN('SPACE ')
166 CALL CLDISC('MESDIM',10)
167 CALL MESH(NLX,NLY,NLZ,SPACE)
168 CALL OPDISC('WSPOS0',11)
169 DO 80 K=1,76
170 50 READ(11,60,END=70)J,XPOS(J),ZPOS(J),ANGLE(J),FNAME(J)(1:12)
171 60 FORMAT(15,3F10.2,A12)
172 CALL BOX(P,X(J),Y(J),Z(J))
173 XWORK = XPOS(J)
174 ZWORK = ZPOS(J)
175 CALL TURN3D(P,ANGLE(J),0.0,0.0,2,R)
176 CALL HERSH(FNAME(J)(1:12),6,2,60.0,0)
177 CALL TRANSP(0,T)
178 CALL TURN3D(1,270.0,0.0,0.0,1,B)
179 CALL JOIN(R,B)
180 CALL DRAW3D(0,1.0,XWORK,0.0,ZWORK,1)

```

20.

```

181 80 CONTINUE
182 70 CALL CLDISC('ASPOSD',11)
183 RETURN
184 END
185 C
186 C 'JOYST' SUBROUTINE IS FOR MANIPULATION OF ANY
187 C 'OBJECT' USING ORDER 'N' (NOT VIA TAG NOS.!)
188 C
189
190 C...
191 SUBROUTINE JOYST(NWS,PICPLA,DISTNC)
192 REAL P(500),X(2000),Y(2000),Z(2000),U(2000)
193 INTEGER NWS
194 COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
195 6FRAME
196 INTEGER SELECT,DESEL, ALPHA,GRAPH1
197 CHARACTER*12 FRAME(77)
198 DATA SELECT/'40033'/
199 DATA DESEL/'40433'/
200 DATA ALPHA/'30'/
201 DATA GRAPH1/'35'/
202
203 C CHANGE OF LAYOUT IS CONSIDERED
204 WRITE(6,85)ALPHA
205 85 FORMAT('+',A2,S)
206 WRITE(6,85)SELECT
207 WRITE(6,90)
208 90 FORMAT(' DO you wish to develop the layout-YE or NO')
209 WRITE(6,85)DESEL
210 WRITE(6,85)GRAPH1
211 100 READ(5,110)ANS
212 110 FORMAT(A2)
213 IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 250
214 IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 150
215 120 FORMAT(' Please enter your response again')
216 150 CONTINUE
217 160 CALL BELL
218 CALL PL11(3,0,-5.0,3)
219 WRITE(6,170)
220 170 FORMAT(' Which workstation?')
221 READ(5,*)I
222 IF(I.EQ.0)GOTO 190
223 CALL BOX(P,X(N),Y(N),Z(N))
224 CALL SCREEN(1CHAR,X1,Y1)
225 CALL SCREEN(1CHAR,X2,Y2)
226 CALL NEWFAG
227 CALL BELL
228 CALL OPDISC('MESDIM',10)
229 NLX =DIN('NLX ')
230 NLY =DIN('NLY ')
231 NLZ =DIN('NLZ ')
232 SPACE =DIN('SPACE ')
233 CALL CLDISC('MESDIM',10)
234 CALL MESH(NLX,NLY,NLZ,SPACE)
235 ANGLE(N) = ATAN2(Y2-Y1,X2-X1)*180.0/3.14159265
236 XPOS(N) = Y1*DISTNC/PICPLA
237 ZPOS(N) = X1*DISTNC/PICPLA
238 DO 180 K = 1,76
239 CALL BOX(P,X(K),Y(K),Z(K))
240 XWRK = XPOS(K)

```

21.

```

241      ZWORK = ZPOS(K)
242      IF(XWORK.EQ.999.0.AND.ZWORK.EQ.999.0)GOTO 180
243      CALL TURN3D(P,ANGLE(K),0.0,0.0,2,R)
244      CALL MERSH(FNAME(K)(1:12),0,2,60.0,0)
245      CALL TRANSP(U,T)
246      CALL TURN3D(T,270.0,0.0,0.0,1,U)
247      CALL JOIN(R,U)
248      CALL DRAW3D(U,1.0,XWORK,0.0,ZWORK,1)
249      180  CONTINUE
250      GOTO 160
251      190  CONTINUE
252      CALL OPDISC('WSPUSD',11)
253      DO 200 K = 1,76
254      IF(XPOS(K).EQ.999.0.AND.ZPOS(K).EQ.999.0)GOTO 200
255      WRITE(10,210)K,XPOS(K),ZPOS(K),ANGLE(K),FNAME(K)(1:12)
256      210  FORMAT(15,3F10.2,A12)
257      200  CONTINUE
258      CALL CLDISC('WSPUSD',11)
259      250  RETURN
260      END
261      C...
262      C....
263      C   FILE UNDER 'ITTVAX00.FOR'
264      C

```

111	Y	Y	T T T T	W	W	S S S S	F F F F	111	L	E E E E
I	Y	Y	T	W	W	S	F	I	L	E
I			T	W	W	S	F	I	L	E
I	Y	Y	T	W	W	S S S	F F F F	I	L	E E E E
I	Y		T	W	W	S	F	I	L	E
I	Y		T	W	W	S	F	I	L	E
111	Y		T	W	W	S S S S	F	111	L L L L L	E E E E E

[illegible]

23.

```

1 C PROGRAM INTERACTIVE LAYOUT (IYTWSFILE)
2 C INCORPORATING WORK STATION DETAILS (WSFILE)
3 C READING FROM FILES 'WSNAME'
3 C DETAILED WORK STATIONS ARE RECALLED VIA
3 C ORDER NOS 'N' ONLY ! (NOT VIA TAG NOS. !)
3 C
4 REAL X,Y,Z,P,XPOS,ZPOS,ANGLE
5 INTEGER NWS
6 COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
7 *FNAME
8 CHARACTER*12 *SNAME
9 CHARACTER*12 FNAME(77)
10 DATA X,Y,Z/231*999.0/
11 DATA XPOS,ZPOS/154*999.0/
12 DATA ANGLE/77*0.0/
13 CALL START
14 CALL WSVOL
15 CALL UPDISC('MESDIM',10)
16 FAC =DIN('FAC ')
17 FORX =DIN('FORX ')
18 FURY =DIN('FURY ')
19 FRAX1 =DIN('FRAX1 ')
20 FRAX2 =DIN('FRAX2 ')
21 FRAY1 =DIN('FRAY1 ')
22 FRAY2 =DIN('FRAY2 ')
23 PICPLA=DIN('PICPLA')
24 DISTNC=DIN('DISTNC')
25 ROTATN=DIN('ROTATN')
26 ELEVTN=DIN('ELEVTN')
27 ZOOM =DIN('ZOOM ')
28 NLX =DIN('NLX ')
29 NLY =DIN('NLY ')
30 NLZ =DIN('NLZ ')
31 SPACE =DIN('SPACE ')
32 CALL CLDISC('MESDIM',10)
33 CALL FACTOR(FAC)
34 CALL FORMAT(FORX,FURY)
35 CALL FRAME(FRAX1,FRAX2,FRAY1,FRAY2)
36 CALL PLANE(PICPLA)
37 CALL PEYE(0.0,0.0,0.0,0.0,DISTNC,ROTATN,ELEVTN)
38 CALL MESH(NLX,NLY,NLZ,SPACE)
39 CALL NCLOSE
40 CALL UPDISC('ASVOLD',10)
41 NWS=1
42 5 READ(10,10,END=20)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
43 10 FORMAT(15,3F8.2,A12)
44 NWS=NWS+1
45 GOTO 5
46 20 CALL CLDISC('WSVOLD',10)
47 NWS=NWS-1
48 CALL PRESIT(NWS)
49 CALL JOYST(NWS,PICPLA,DISTNC)
50 CALL FINISH
51 STOP
52 END
53 C...
54 SUBROUTINE WSVOL
55 INTEGER ANS,NWS
56 COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),

```

```

57      &FNAME
58      INTEGER SELECT,DESEL, ALPHA,GRAPH1
59      CHARACTER*12 FNAME(77)
60      DATA SELECT/'40033'/
61      DATA DESEL/'40433'/
62      DATA ALPHA/'30'/
63      DATA GRAPH1/'35'/
64      C
65      C      OUTPUT OF CURRENT DATA FILE
66      C
67      WRITE(6,10)ALPHA
68      10  FORMAT('+',A2,S)
69      WRITE(6,10)SELECT
70      WRITE(6,20)
71      20  FORMAT(/// ' File of existing work Station Module volumes'//)
72      WRITE (6,35) ' Item','Dim X','Dim Y','Dim Y','Tag No'
73      35  FORMAT (A5,3A8,A7/)
74      CALL UPDISC('WSVOLD',10)
75      30  CONTINUE
76      READ(10,40,END=60)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
77      40  FORMAT(15,3F8.2,A12)
78      WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
79      50  FORMAT(15,3F8.2,1X,A12)
80      C      PLEASE NOTE ABOVE WAS THE EXTRA SPACE '1X'DELETED
81      GOTO 30
82      60  CONTINUE
83      CALL CDISCS('WSVOLD',10)
84      C
85      C      EXTEND FILE?
86      C
87      WRITE(6,70)
88      70  FORMAT( / ' Do you wish to extend/update the file-YE or NO'//)
89      WRITE(6,10)DESEL
90      WRITE(6,10)GRAPH1
91      80  READ(5,85)ANS
92      85  FORMAT(A2)
93      IF(ANS.EQ.'NO').OR.ANS.EQ.'N')GOTO 150
94      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 100
95      C
96      C      ERROR MESSAGE
97      C
98      WRITE(6,90)
99      90  FORMAT(' Please enter your response again ! use CAPITALS !')
100     GOTO 80
101     100  CONTINUE
102     C
103     C      NEW ENTRY IS WRITTEN
104     C
105     WRITE(6,110)
106     110  FORMAT(' Please enter Item No. Dim of W.S. X,Y,Z, and TAG No
107           &...TO END EXTENDING TYPE 77')
108     120  CONTINUE
109     READ(5,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
110     IF(J.EQ.77)GOTO 100
111     C
112     C      OUTPUT LATEST DATA TO DISC AND TERMINAL
113     C
114     WRITE(6,10)ALPHA
115     WRITE(6,10)SELECT
116     WRITE(6,20)

```

C 25.

```

117      CALL UPDISC('WSVOLD',10)
118      CONTINUE
119      DO 140 J=1,76
120      IF (X(J).EQ.999.0.AND.Y(J).EQ.999.0)GOTO 140
121      WRITE(10,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
122      WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
123      140 CONTINUE
124      CALL CLDISC('WSVOLD',10)
125      WRITE(6,10)DESEL
126      WRITE(6,10)GRAPH1
127      150 CONTINUE
128      RETURN
129      END
130      C...
131      C...
132      SUBROUTINE MESH(NLX,NLY,NLZ,SPACE)
133      REAL A(1000)
134      CALL GRIL3D(A,NLX,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,SPACE,.0,.0)
135      CALL DRAWIT(A)
136      CALL GRIL3D(A,NLY,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,SPACE,.0)
137      CALL DRAWIT(A)
138      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,.0,SPACE)
139      CALL DRAWIT(A)
140      CALL GRIL3D(A,NLY,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,.0,SPACE,.0)
141      CALL DRAWIT(A)
142      CALL GRIL3D(A,NLX,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,SPACE,.0,.0)
143      CALL DRAWIT(A)
144      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE)
145      CALL DRAWIT(A)
146      RETURN
147      END
148      C...
149      C      THIS IS A SUBROUTINE FOR SHOWING THE PRESENT SITUATION
150
151      SUBROUTINE PRESIT(NWS)
152      REAL P(500),R(2000),Q(2000),T(2000),U(2000),V(7000)
153      INTEGER N*8
154      COMMON/LC*8/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
155      &FNAME
156      INTEGER SELECT,DESEL, ALPHA,GRAPH1
157      CHARACTER*12 FNAME(77)
158      CHARACTER*12 WNAME
159      DATA SELECT/'40033'/
160      DATA DESEL/'40433'/
161      DATA ALPHA/'30'/
162      DATA GRAPH1/'35'/
163      C
164      C      PRINTING THE PRESENT SITUATION OF LAYOUT DEVELOPMENT
165      C
166      WRITE (6,5)ALPHA
167      5      FORMAT('+',A2,S)
168      WRITE (6,5)SELECT
169      WRITE(6,10)
170      10      FORMAT(' LAYOUT-the existing situation of developrent'////)
171      WRITE (6,5)DESEL
172      WRITE (6,5)GRAPH1
173      CALL BELL
174      CALL UPDISC('MESDIN',10)
175      NLX   =DIN('NLX   ')
176      NLY   =DIN('NLY   ')

```

C 26

```

177      NLZ =DIN('NLZ ')
178      SPACE =DIN('SPACE ')
179      CALL CLDISC('MESDIM',10)
180      CALL MESH(NLX,NLY,NLZ,SPACE)
181      CALL OPDISC('WSPUSD',11)
182      DO 80 K=1,76
183      READ(11,60,END=70)J,XPOS(J),ZPOS(J),ANGLE(J),FNAME(J)(1:12)
184  60    FORMAT(15,3F10.2,A12)
185      CALL BOX(P,X(J),Y(J),Z(J))
186      XWORK = XPOS(J)
187      ZWORK = ZPOS(J)
188      IF(XWORK.EQ.999.0.AND.ZWORK.EQ.999.0)GOTO 80
189      CALL TURN3D(P,ANGLE(J),0.0,0.0,2,R)
190      WNAME=FNAME(J)
191      CALL HERSH(FNAME(J)(1:12),6,2,60.0,0)
192      CALL TRANSP(0,1)
193      CALL TURN3D(1,270.0,0.0,0.0,1,U)
194      CALL JOIN(F,U)
195      C
196      C    DETAIL SHAPE OF THE WORK STATION IS RETRIEVED
197      C    FROM A DISK
198      C
199      CALL IN3D(V,WNAME)
200      CALL JOIN(U,V)
201      CALL DRAW3D(V,1.0,XWORK,0.0,ZWORK,1)
202  80    CONTINUE
203  70    CALL CLDISC('WSPUSD',11)
204      RETURN
205      END
206      C...
207
208      C...
209      SUBROUTINE JOYST(NWS,FICPLA,DISINC)
210      REAL P(500),R(2000),C(2000),T(2000),U(2000),V(7000)
211      INTEGER ANS, NWS
212      COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
213      &FNAME
214      INTEGER SELECT,DESEL, ALPHA,GRAPH1
215      CHARACTER*12 FNAME(77)
216      CHARACTER*12 WNAME
217      DATA SELECT/'40033'/
218      DATA DESEL/'40433'/
219      DATA ALPHA/'30'/
220      DATA GRAPH1/'35'/
221
222      C    CHANGE OF LAYOUT IS CONSIDERED
223      WRITE(6,85)ALPHA
224  85    FORMAT('+',A2,S)
225      WRITE(6,85)SELECT
226      WRITE(6,90)
227  90    FORMAT(' Do you wish to develop the layout-YE or NO')
228      WRITE(6,85)DESEL
229      WRITE(6,85)GRAPH1
230  100   READ(5,110)ANS
231  110   FORMAT(A2)
232      IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 250
233      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 150
234  120   FORMAT(' Please enter your response again')
235  150   CONTINUE
236  160   CALL BELL

```

27.

```

237      CALL PLIT(3,0,-5,0,3)
238      WRITE(6,170)
239 170    FORMAT(' Which workstation?')
240      READ(5,*)R
241      IF(R.EQ.0)GOTO 190
242      CALL BOX(P,X(N),Y(N),Z(N))
243      CALL SCREEN(1CHAR,X1,Y1)
244      CALL SCREEN(1CHAR,X2,Y2)
245      CALL NEWPAG
246      CALL BELD
247      CALL OPDISC('MESDIM',10)
248      NLX =DIN('NLX  ')
249      NLY =DIN('NLY  ')
250      NLZ =DIN('NLZ  ')
251      SPACE =DIN('SPACE ')
252      CALL CLDISC('MESDIM',10)
253      CALL MESH(NLX,NLY,NLZ,SPACE)
254      ANGLE(K) = ATAN2(Y2-Y1,X2-X1)*180.0/3.14159265
255      XPOS(K) = Y1*DISTNC/PICPLA
256      ZPOS(K) = X1*DISTNC/PICPLA
257      DO 180 K = 1,76
258      CALL BOX(P,X(K),Y(K),Z(K))
259      XWORK = XPOS(K)
260      ZWORK = ZPOS(K)
261      IF(XWORK.EQ.999.0.AND.ZWORK.EQ.999.0)GOTO 180
262      CALL TURN3D(P,ANGLE(K),0,0,0,0,2,R)
263      WSHAME=FNAME(K)
264      CALL HERSH(FNAME(K)(1:12),6,2,60,0,0)
265      CALL TRANSP(0,T)
266      CALL TURN3D(T,270,0,0,0,0,0,1,U)
267      CALL JOIN(R,U)
268  C
269  C   DETAILED SHAPE OF THE WORK STATION IS RETRIEVED
270  C   FROM A DISK
271  C
272      CALL IN3D(V,WSHAME)
273      CALL JOIN(U,V)
274      CALL DRAW3D(V,1.0,XWORK,0.0,ZWORK,1)
275 180    CONTINUE
276      GOTO 160
277 190    CONTINUE
278      CALL OPDISC('SPOSD',10)
279      DO 200 K = 1,76
280      IF(XPOS(K).EQ.999.0.AND.ZPOS(K).EQ.999.0)GOTO 200
281      WRITE(10,210)K,XPOS(K),ZPOS(K),ANGLE(K),FNAME(K)(1:12)
282 210    FORMAT(15,3F10.2,A12)
283 200    CONTINUE
284      CALL CLDISC('SPOSD',10)
285 250    RETURN
286      END
287  C...
288  C....
289  C   FILE UNDER 'LYTNSFILE'

```

[illegible]

PPP	UUU	SSSS	CCCC	L	AAA	SSSS	H	H	5555			
P	P	U	U	S	C	L	A	A	S	H	H	5
P	P	U	U	S	C	L	A	A	S	H	H	555
PPPF	U	U	SSS	C	L	A	A	SSS	HHHHH			5
P	U	U	S	C	L	AAAAA	S	H	H			5
P	U	U	S	C	L	A	A	S	H	H	5	5
P	UUU	SSSS	CCCC	LLLLL	A	A	SSSS	H	H			555

(1165) queued to SYS\$PRINT on 9-NOV-1987 12:15 by user BOB1, BIC (HESM0012,BOB1), under account
 printer _LPAU: on 9-NOV-1987 12:20 from queue LPAU.

[illegible]

29.

```

1 C "POSCLASH5.FOR" PROGRAM IS AN INTRACTIVE PROGRAM
2 C FOR AUTOMATIC POSITIONING OF A LINE OR A GROUP OF
3 C WORK STATION WITHIN BUILDING (CIVIL ENG.SPACE)
4 C INCLUDING COLLISION COURSE FINDING WITH
5 C OBJECTS (WALLS,COLUMNS ETC) WITHIN BUILDING
6 C AND FACILITY TO ENTER READY BUILT LAYOUT AT ANY WORK STATION
7 C FOR RE-LAYOUT VIA JOYSTICK AND AUTOMATIC
8 C
9 C
10 C
11 C
12 C THE "MFEED" PROGRAM RESULTS (OR DR.C. SYSTEM) ARE INTRODUCED
13 C AND W.S. IN AN PRODUCTION LINE ORDER VIA "WSVTGIC"
14 C DISC WSVTUR.DAT ARE ENTERED
15 C
16 C
17 C
18 C GENERALLY: I AM SOLVING A TASK OF AUTOMATIC POSITIONING
19 C OF GROUP OF WORK STATION (MAX. NUMBER OF W.S. IS 77!).
20 C
21 C
22 C...
23 C PROGRAM INTERACTIVE LAYOUT (IDLAY)
24 C INTEGER NXS
25 C COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
26 C &FNAME(77)
27 C CHARACTER*12 FRAME
28 C CHARACTER*12 ASNAME
29 C
30 C INTEGER SELECT,DESEL, ALPHA,GRAPH1
31 C DATA X,Y,Z/231*999.0/
32 C DATA XPOS,ZPOS/154*999.0/
33 C DATA ANGLE/77*0.0/
34 C DATA SELECT/"40033/
35 C DATA DESEL/"40433/
36 C DATA ALPHA/"30/
37 C DATA GRAPH1/"35/
38 C CALL START
39 C CALL WSVOL
40 C CALL OPDISC("MESDIM",10)
41 C FAC =DIN("FAC ")
42 C FORX =DIN("FORX ")
43 C FURY =DIN("FURY ")
44 C FRAX1 =DIN("FRAX1 ")
45 C FRAX2 =DIN("FRAX2 ")
46 C FRAY1 =DIN("FRAY1 ")
47 C FRAY2 =DIN("FRAY2 ")
48 C PICPLA=DIN("PICPLA")
49 C DISTNC=DIN("DISTNC")
50 C ROTATN=DIN("ROTATN")
51 C ELEVTH=DIN("ELEVTH")
52 C ZOOM =DIN("ZOOM ")
53 C NLX =DIN("NLX ")
54 C NLY =DIN("NLY ")
55 C NLZ =DIN("NLZ ")
56 C SPACE =DIN("SPACE ")
57 C CALL CLDISC("MESDIM",10)
58 C CALL FACTOR(FAC)
59 C CALL FORMAT(FORX,FURY)
60 C CALL FRAME(FRAX1,FRAX2,FRAY1,FRAY2)

```

```

61      CALL PLANE(PICPLA)
62      CALL PEYE(0.0,0.0,0.0,DISTNC,ROTATN,ELEVTR)
63      CALL MESH(NLX,NLY,NLZ,SPACE)
64      CALL OPDISC('WSVOLD',10)
65      NWS=1
66      5  READ(10,10,END=20)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
67      10  FORMAT(15,3F8.2,A12)
68      NWS=NWS+1
69      GOTO 5
70      20  CALL CLDISC('WSVOLD',10)
71      NWS=NWS-1
72      CALL PFESIT (NWS)
73      40  CONTINUE
74      WRITE(6,50)ALPHA
75      50  FORMAT('+',A2,S)
76      WRITE(6,50)SELECT
77      WRITE(6,70)
78      70  FORMAT (' Do you want to continue/change the layout...
79      &YE or NO ? ')
80      WRITE(6,50)DESEL
81      WRITE(6,50)GRAPH1
82      READ(5,85)ANS
83      85  FORMAT(A2)
84      IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 2900
85      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 100
86      WRITE(6,50)ALPHA
87      WRITE(6,50)SELECT
88      WRITE(6,90)
89      90  FORMAT(' Please enter your response again - use CAPITALS')
90      WRITE(6,50)DESEL
91      WRITE(6,50)GRAPH1
92      GOTO 40
93      100  CONTINUE
94      C
95      CALL POSIT(PICPLA,DISTNC)
96      2900  CONTINUE
97      CALL RCLOSE
98      CALL FINISH
99      STOP
100     END
101     C
102     C   THIS IS THE END OF MAIN POSCOL2.FOR PROGRAM
103     C
104
105     C...
106     SUBROUTINE WSVOL
107     INTEGER ANS,NWS
108     COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
109     &FNAME(77)
110     INTEGER SELECT,DESEL, ALPHA,GRAPH1
111     CHARACTER*12 FNAME
112     DATA SELECT/'40033'/
113     DATA DESEL/'40433'/
114     DATA ALPHA/'30'/
115     DATA GRAPH1/'3S'/
116     C
117     C   OUTPUT OF CURRENT DATA FILE
118     C
119     WRITE(6,10)ALPHA
120     10  FORMAT('+',A2,S)

```


31.

```

121      WRITE(6,10)SELECT
122      WRITE(6,20)
123      20      FORMAT(' File of existing work Station Module volumes')
124      CALL UPDISC('*SVOLD',10)
125      30      CONTINUE
126      READ(10,40,END=60)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
127      40      FORMAT(15,3F6.2,A12)
128      C      WRITE(6,10)ALPHA
129      C      WRITE(6,10)SELECT
130      WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
131      50      FORMAT(15,3F6.2,1X,A12)
132      C      WRITE(6,10)DESEL
133      C      WRITE(6,10)GRAPHI
134      C      PLEASE NOTE ABOVE WAS THE EXTRA SPACE 'IX'DELETED
135      GOTO 30
136      60      CONTINUE
137      CALL CLDISC('*SVOLD',10)
138      C
139      C      EXTEND FILE?
140      C
141      C      CALL BELL
142      C      WRITE(6,10)ALPHA
143      C      WRITE(6,10)SELECT
144      WRITE(6,70)
145      70      FORMAT(' Do you wish to extend/update the existing file...
146      &YE or NO')
147      WRITE(6,10)DESEL
148      WRITE(6,10)GRAPHI
149      80      READ(5,85)ANS
150      85      FORMAT(A2)
151      IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 150
152      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 100
153      C      WRITE(6,10)ALPHA
154      C      WRITE(6,10)SELECT
155      WRITE(6,90)
156      90      FORMAT(' Please enter your response again')
157      C      WRITE(6,10)DESEL
158      C      WRITE(6,10)GRAPHI
159      GOTO 80
160      100     CONTINUE
161      WRITE(6,110)
162      110     FORMAT(' PLEASE ENTER WS No.,X,Y,Z,DIM OF WS AND TAG No OF WS...
163      &TO END EXTENDING TYPE 77')
164      120     CONTINUE
165      READ(5,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
166      IF(J.NE.77)GOTO 100
167      C
168      C      OUTPUT LATEST DATA TO DISC AND TERNINAL
169      C
170      WRITE(6,10)ALPHA
171      WRITE(6,10)SELECT
172      WRITE(6,20)
173      CALL UPDISC('*SVOLD',10)
174      130     CONTINUE
175      DO 140 J=1,76
176      IF (X(J).EQ.999.0.AND.Y(J).EQ.999.0)GOTO 140
177      WRITE(10,40)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
178      WRITE(6,50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
179      140     CONTINUE
180      CALL CLDISC('*SVOLD',10)

```

32.

```

181      WRITE(6,10)DESEL
182      WRITE(6,10)GRAPH1
183 150    CONTINUE
184      RETURN
185      END
186  C...
187      SUBROUTINE MESH(NLX,NLY,NLZ,SPACE)
188      REAL A(1000)
189      CALL GRIL3D(A,NLX,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,SPACE,.0,.0)
190      CALL DRAWIT(A)
191      CALL GRIL3D(A,NLY,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE,.0)
192      CALL DRAWIT(A)
193      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,.0,.0,SPACE)
194      CALL DRAWIT(A)
195      CALL GRIL3D(A,NLY,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,.0,SPACE,.0)
196      CALL DRAWIT(A)
197      CALL GRIL3D(A,NLX,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,SPACE,.0,.0)
198      CALL DRAWIT(A)
199      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE)
200      CALL DRAWIT(A)
201      RETURN
202      END
203
204  C...
205      SUBROUTINE PRESIT (NWS)
206  C
207  C      THIS IS A SUBROUTINE FOR SHOWING THE PRESENT SITUATION
208  C
209      REAL P(500),R(2000),Q(2000),T(2000),U(2000)
210      REAL CESPAC(10000)
211      INTEGER NWS
212      COMMON/UCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
213      &FRAME(77)
214      INTEGER SELECT,DESEL, ALPHA,GRAPH1
215      CHARACTER*12 FRAME
216      DATA SELECT/'40033'/
217      DATA DESEL/'40433'/
218      DATA ALPHA/'30'/
219      DATA GRAPH1/'35'/
220  C      PRINTING THE PRESENT SITUATION OF LAYOUT DEVELOPMENT
221      WRITE(6,10)ALPHA
222 10      FORMAT('+',A2,S)
223      WRITE(6,10)SELECT
224      WRITE(6,20)
225 20      FORMAT(' LAYOUT...The existing situation of development')
226      WRITE(6,10)DESEL
227      WRITE(6,10)GRAPH1
228      CALL BELL
229      CALL OPDISC('RESDIM',10)
230      NLX =DIN('NLX  ')
231      NLY =DIN('NLY  ')
232      NLZ =DIN('NLZ  ')
233      SPACE =DIN('SPACE ')
234      CALL CLDISC('RESDIM',10)
235      CALL MESH(NLX,NLY,NLZ,SPACE)
236  C
237  C      BUILDING IS CALLED IN
238  C
239      CALL IN3D (CESPAC,'CIVILD')
240      CALL DRAWIT (CESPAC)

```

33.

```

241      CALL UPDISC('WSVTOR',12)
242  40    READ(12,60,END=50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
243      CALL UPDISC('WSPOSA',11)
244  50    READ(11,60,END=90)J,XPOS(J),ZPOS(J),ANGLE(J),FNAME(J)(1:12)
245  60    FORMAT(15,3F8.2,A12)
246      CALL DOA(P,X(J),Y(J),Z(J))
247      XWORK = XPOS(J)
248      ZWORK = ZPOS(J)
249      CALL BERSH(FNAME(J)(1:12),6,2,60.0,G)
250      CALL TRANSP(0,1)
251      CALL TURN3D(T,270.0,0.0,0.0,1,U)
252      CALL JOIN(P,U)
253      CALL TURN3D(0,ANGLE(J),0.0,0.0,2,R)
254      CALL SHIFT3 (R,XWORK,0.0,ZWORK)
255      CALL DRAWIT (R)
256  C     CALL DRAW3D(0,1.0,XWORK,0.0,ZWORK,1)
257      GO TO 40
258  90    CONTINUE
259      CALL CLDISC('WSPOSA',11)
260      CALL CLDISC('WSVTOR',12)
261
262
263      RETURN
264      END
265  C...
266  C...
267      SUBROUTINE POSIT(PICPLA,DISTWC)
268  C
269  C     THIS IS A SUBROUTINE FOR ENTIRE POSITIONING OF W.S.
270  C     INCLUDING SUBROUTINE JOY2 (FOR MANUAL POSITION OF ONE W.S.)
271  C     SUBROUTINE JOUST (FOR ERIK AT ANY SITUATION AND FOR
272  C     GROUP TECHNOLOGY LAYOUT
273  C     AND SUBROUTINE PLACE (FOR AUTOMATIC PLACING OF SELECTED
274  C     GROUP/LINE OF WORK STATIONS INTO AN OPTIMAL PLACE)
275  C
276
277      REAL X,Y,Z,XPOS,ZPOS,ANGLE,XSUM,ZSUM
278      REAL AS,ZS,AS
279      REAL JR
280      REAL P(500),R(2000),O(2000),T(7300),U(2000),G(2000),V(2000)
281      REAL W(7000),CESPAC(10000)
282      LOGICAL FOUND
283      INTEGER N*5,ANS,SUMJ,RESULT
284      COMMON/LC*5/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
285      &FNAME(77)
286      INTEGER SELECT,DESEL, ALPHA,GRAPH1
287      CHARACTER*12 FNAME
288      CHARACTER*12 WNAME
289      DATA X,Y,Z/231*999.0/
290      DATA XPOS,ZPOS/154*999.0/
291      DATA ANGLE/77*0.0/
292      DATA SELECT/'40033/
293      DATA DESEL/'40433/
294      DATA ALPHA/'30/
295      DATA GRAPH1/'35/
296  C
297  C
298  15    CONTINUE
299      WRITE(6,10)ALPHA
300  10    FORMAT('+',A2,S)

```

```

301      WRITE(6,10)SELECT
302
303      WRITE (6,20)
304 20    FORMAT (' You are now in POSITIONING MODE ')
305      WRITE (6,22)
306 22    FORMAT (' Are you starting a NEW layout,from the first W.St.
307 6in technological order?'/...'YES or NO')
308      WRITE(6,10)DESEL
309      WRITE(6,10)GRAPH1
310
311 42    CONTINUE
312
313      READ (5,43)ANS
314 43    FORMAT (A2)
315      IF (ANS.EQ.'NO'.OR.ANS.EQ.'N') GOTO 7000
316      IF (ANS.EQ.'YE'.OR.ANS.EQ.'Y') GOTO 25
317      WRITE (6,44)
318 44    FORMAT (' Please enter your response again - use capitals')
319      GOTO 42
320 7000   CONTINUE
321      CALL JOYST (K43,PICPLA,DIS10C,L)
322      GOTO 7100
323
324
325 25    CONTINUE
326 C
327 C      WORK STATION (VOLUMES) IN A REORGANISED TECHNOLOGICAL
328 C      ORDER ARE INTRODUCED VIA DISC 'WSVTOR'.
329 C      DISC 'WSVTOR' IS FED VIA PROGRAM WSVTOTO, FOR WHICH
330 C      IS NOT AN INTEGRAL PART OF THIS PROGRAM 'POSCOL'
331 C      (COMPUTER TIME SAVING ! DURING RUN OF 'POSCOL')
332 C
333      CALL OPDISC ('WSVTOR',12)
334 C
335 C      READING IN THE 'first' WORK STATION ONLY
336 C
337      READ (12,30)J,X(J),Y(J),Z(J),FRAME(J)(1:12)
338 30    FORMAT (15,3F8.2,A12)
339      WRITE(6,10)ALPHA
340      WRITE(6,10)SELECT
341      WRITE (6,50)
342 50    FORMAT (' Do you wish to POSITION the considered work
343 6Station manually ... YE or NO'/)
344      WRITE(6,10)DESEL
345      WRITE(6,10)GRAPH1
346 100   READ(5,110)ANS
347 110   FORMAT(A2)
348      IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 405
349      IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 150
350      WRITE(6,10)ALPHA
351      WRITE(6,10)SELECT
352      WRITE (6,120)
353 120   FORMAT(' Please enter your response again')
354      WRITE(6,10)DESEL
355      WRITE(6,10)GRAPH1
356      GOTO 100
357 C
358 C      IF YOU SELECT 'NO' YOU ARE GOING DIRECTLY INTO
359 C      THE AUTOMATIC POSITIONING PROGRAM -SUBROUTINE "PLACE"
360 C

```

```

361 150 CONTINUE
362 160 CALL BELL
363 WRITE (6,200)
364 200 FORMAT (' Use Joystick for corrective action')
365 C
366 C BUILDING IS CALLED IN
367 C
368 CALL IN3D (CESPAC,'CIVIL')
369 CALL GRANIT (CESPAC)
370 CALL JOY2 (J,PICPLA,DISTRC,G,XS,ZS,AS)
371
372
373 405 CONTINUE
374 WRITE(6,10)ALPHA
375 WRITE(6,10)SELECT
376 WRITE (6,410)
377 410 FORMAT (' Do you wish to continue developing the layout...
378 in automatic mode ... YE or NO?')
379 WRITE(6,10)DESEL
380 WRITE(6,10)GRAPH1
381 420 READ(5,430)ANS
382 430 FORMAT(A2)
383 IF(ANS.EQ.'NO'.OR.ANS.EQ.'N')GOTO 700
384 IF(ANS.EQ.'YE'.OR.ANS.EQ.'Y')GOTO 450
385 WRITE(6,10)ALPHA
386 WRITE(6,10)SELECT
387 WRITE (6,410)
388 440 FORMAT(' Please enter your response again')
389 WRITE(6,10)DESEL
390 WRITE(6,10)GRAPH1
391 GOTO 405
392 450 CONTINUE
393
394 C
395 C CONTINUES IN AUTOMATIC MODE
396 C
397 C
398 C PROGRAM IS GOING TO SUMUP DIRECTLY
399 C
400 XPOS(J) = XS
401 ZPOS(J) = ZS
402 ANGLE(J) = AS
403 GOTO 500
404 7100 CONTINUE
405 CALL UPDISC ('*SVTOR',12)
406
407 C CALL NEWPAG
408 C
409 C THE NEXT (CORRECT) W.S., AFTER THE SELECTED W.S.
410 C (OR WORK STATIONS) ARE POSITIONED
411 C TO START WITHIN AUTOMATIC POSITIONING SYSTEM,
412 C IS RETRIEVED
413 C
414 7110 CONTINUE
415 READ (12,30)J,X(J),I(J),Z(J),FRAME(J)(1:12)
416 IF (J.NE.L) GOTO 7110
417 IF (J.EQ.L) GOTO 7120
418 7120 CONTINUE
419 XS = XPOS(J)
420 ZS = ZPOS(J)

```

```

421      AS = ANGLE(J)
422      480  CONTINUE
423
424      CALL 103D (CESPAC,'CIVILD')
425      CALL DRAWIT (CESPAC)
426      C
427      C      BECAUSE THE NEXT ROUND IS ADDING TO 'K'  ZS=SUMZ
428      C
429
430
431      500  CALL SUMUPZ (J,XSUM,ZSUM,XS,ZS,AS)
432      WRITE(6,10)ALPHA
433      *RITE(6,10)SELECT
434      *RITE (6,520)
435      520  FORMAT (' TITAL VALUE OF -2- DIMENSION IS')
436      WRITE (6,540) ZSUM
437      540  FORMAT (F10.2)
438      *RITE(6,10)DESEL
439      *RITE(6,10)GRAPH1
440
441      C
442      C      A NEW (NEXT) W.S. IS CONSIDERED
443      C
444
445
446      READ (12,30,END=700)K,X(K),Y(K),Z(K),FRAME(K)(1:12)
447
448      CALL PLACE(K,XSUM,ZSUM,AS,1)
449      C
450      C      'T' IS THE VERY LAST WORK STATION WHICH IS CLASHING
451      C      WITH BUILDING (CIVIL ENG. SPACE/ELEMENT/BOX)
452      C      OR IN COLLISION WITH ANOTHER WORK STATION
453      C
454
455      CALL COLLOWS (T,CESPAC,RESULT)
456      C
457      C      ACTIONS WHEN CLASH OR COLLISION OCCURS
458      C
459      WRITE (6,800)
460      800  FORMAT (' RESULT')
461      WRITE (6,1000)RESULT
462      1000 FORMAT (18)
463      IF (RESULT.EQ.2) GOTO 5000
464      IF (RESULT.EQ.3) THEN
465      GOTO 5500
466      ELSE
467      GOTO 4000
468      END IF
469
470      4000 CALL BELL
471      WRITE (6,10)ALPHA
472      WRITE (6,10)SELECT
473      *RITE (6,4100)
474      4100 FORMAT (' CLASH !!!')
475      *RITE (6,4110)FRAME(K)(1:12)
476      4110 FORMAT (2X,A12)
477
478
479      *RITE (6,10)DESEL
480      *RITE (6,10)GRAPH1

```

37.

```

481      WRITE(6,4200)
482      4200  FORMAT (' Do you wish to see the scene of the clash')
483      4250  READ (5,4300)ANS
484      4300  FORMAT (A2)
485      IF (ANS.EQ.'NO'.OR.ANS.EQ.'N') GOTO 6100
486      IF (ANS.EQ.'YE'.OR.ANS.EQ.'Y') GOTO 6000
487      WRITE (6,4400)
488      4400  FORMAT (' Please enter your response again - use capitals')
489      GOTO 4250
490
491
492      5000  CONTINUE
493      WRITE (6,5200)
494      5200  FORMAT (' TOUCH ! ')
495      5500  CONTINUE
496      C      CALL DRAWIT (1)
497      CALL DRAWIT (CESPAC)
498      WRITE (6,10)ALPHA
499      WRITE (6,10)SELECT
500      WRITE (6,3100)
501      3100  FORMAT(' LAYOUT ACCEPTABLE')
502      WRITE (6,10)DESEL
503      WRITE (6,10)GRAPH1
504      C
505      C      'J' IS REPLACED BY 'K'
506      C
507      J = K
508      XPOS(K) = XSUM
509      ZPOS(K) = ZSUM
510      ANGLE(K) = AS
511      ZS = ZSUM
512      5800  CONTINUE
513      GOTO 480
514      6000  CONTINUE
515      CALL NEWPAG
516      CALL DRAWIT(1)
517      CALL DRAWIT (CESPAC)
518
519      6100  CONTINUE
520      WRITE (6,10)ALPHA
521      WRITE (6,10)SELECT
522      WRITE (6,6120)
523      6120  FORMAT (' DO YOU WISH TO RE-POSIT THE CLASHING W.S. ONLY'/
524      '...YES,NO...If NO you can reposition any No.of W.S.')
525      WRITE (6,10)DESEL
526      WRITE (6,10)GRAPH1
527      6130  READ (5,6140)ANS
528      6140  FORMAT (A2)
529      IF (ANS.EQ.'NO'.OR.ANS.EQ.'N') GOTO 7000
530      IF (ANS.EQ.'YE'.OR.ANS.EQ.'Y') GOTO 6200
531      WRITE (6,6150)
532      6150  FORMAT (' Please enter your response again - use capitals')
533      GOTO 6130
534      6200  CONTINUE
535      C
536      C      THE CLASHING WORK STATION WILL BE REPOSITIONED
537      C
538
539      J = K
540

```

38.

```
541
542 6500 GOTO 150
543 700  CONTINUE
544 C
545 C    POSITION OF THE LAST WORK STATION IS RECORDED
546 C
547
548 CALL UPDISC ('WSPUSA',11)
549 DO 3300 L = 1,76
550 IF (XPOS(L).EQ.999.0.AND.ZPOS(L).EQ.999.0) GOTO 3300
551 WRITE (11,3200) L,XPOS(L),ZPOS(L),ANGLE(L),FNAME(L)(1:12)
552 3200 FORMAT (15,3F8.2,A12)
553
554 3300 CONTINUE
555 CALL CLDISC ('WSPUSA',11)
556 CALL CLDISC ('WSVTOR',12)
557 C
558 C    FOR A BETT FINAL PRENTATION THE LAYOUT IS REDRAWN
559 C    WITH DETAILS OF WORK STATIONS RETRIEVED
560 C
561 CALL NEWPAG
562 CALL PRESIT (NWS)
563 C    CALL PRESITDET (NWS)
564
565 C
566 C    FINAL DECISION IS MADE REGARDING CONTINUATION
567 C    OR STOPING THE PROGRAM
568 C
569 WRITE (6,10)ALPHA
570 WRITE (6,10)SELECT
571 WRITE(6,3320)
572 3320 FORMAT (' Do you wish to reora* the layout?...YES,ND..'/
573 & ' If NO is typed, the session is over')
574 WRITE (6,10)DESEL
575 WRITE (6,10)GRAPHI
576 3360 READ (5,3330)ANS
577 3330 FORMAT (A2)
578 IF (ANS.EQ.'NO'.OR.ANS.EQ.'N') GOTO 3400
579 IF (ANS.EQ.'YE'.OR.ANS.EQ.'Y') GOTO 15
580 WRITE (6,3340)
581 WRITE (6,10)ALPHA
582 WRITE (6,10)SELECT
583 3340 FORMAT (' Please enter your response again - use capitals')
584 WRITE (6,10)DESEL
585 WRITE (6,10)GRAPHI
586 GOTO 3360
587
588 3400 CONTINUE
589 RETURN
590 END
591
592
593 C...
594 SUBROUTINE JOY2 (J,PICPLA,DISTNC,R,XS,ZS,AS)
595 C
596 C    SUBROUTINE "JOY2" IS A MODIFIED SUBROUTINE JOYS1
597 C    WHICH WILL ALLOWE TO POSITION ONLY ONE WORK STATION
598 C    IN TIME.
599 C    THIS IS BECAUSE OF THE 'ZPCS' DIMENSION WHICH HAS
600 C    TO BE SUMMED.
```


39.

```

601 C
602 C
603 REAL X,Y,Z,XPOS,ZPOS,ANGLE
604 REAL P(500),R(2000),G(2000),T(2000),G(2000),V(2000)
605 REAL CESPAC(10000)
606 INTEGER NWS,ANS
607 COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
608 &FNAME(77)
609 INTEGER SELECT,DESEL, ALPHA,GRAPHI
610 CHARACTER*12 FNAME
611 CHARACTER*12 ASNAME
612 DATA X,Y,Z/231*999.0/
613 DATA XPOS,ZPOS/154*999.0/
614 DATA ANGLE/77*0.0/
615 DATA SELECT/"40033/
616 DATA DESEL/"40433/
617 DATA ALPHA/"30/
618 DATA GRAPHI/"35/
619 C
620 WRITE(6,10)ALPHA
621 10 FORMAT(' ',A2,S)
622 WRITE(6,10)SELECT
623 WRITE (6,50)
624 50 FORMAT (' You are now in the Manual ..to..Auto Mode'/)
625
626 70 CONTINUE
627 C CHANGE OF LAYOUT IS CONSIDERED
628 WRITE(6,90)
629 90 FORMAT(' Do you wish to re-POSITION the work Station...YE or NO')
630 WRITE(6,10)DESEL
631 WRITE(6,10)GRAPHI
632 100 READ(5,110)ANS
633 110 FORMAT(A2)
634 IF(ANS.EQ."NO".OR.ANS.EQ."N")GOTO 250
635 IF(ANS.EQ."YE".OR.ANS.EQ."Y")GOTO 150
636 WRITE(6,10)ALPHA
637 WRITE(6,10)SELECT
638 WRITE (6,120)
639 120 FORMAT(' Please enter your response again')
640 WRITE(6,10)DESEL
641 WRITE(6,10)GRAPHI
642 GOTO 70
643 150 CONTINUE
644 153 CONTINUE
645 CONTINUE
646 WRITE(6,10)ALPHA
647 WRITE(6,10)SELECT
648 WRITE (6,155)
649 155 FORMAT (' Please POSITION the w.S. by cross-hairs...')
650 WRITE(6,10)DESEL
651 WRITE(6,10)GRAPHI
652 C
653 C 1st movement POSIT the right bottom corner..press spacer..
654 C 2nd movement POSIT/turns the w.s. around this corner..
655 C
656 C press spacer.
657 C
658 160 CALL BELL
659 C CALL PLIT(3.0,-5.0,3)
660 C

```

```

661 C FIRST WORK STATION VOLUME IS FEAD AUTOMATICALLY
662 C VIA SUBROUTINE "POSIT" (AREA LABEL 25-30)...J...N !
663 C REANGLE(J)ON IS TO HAVE FIRST W.S. OF A GROUP OF MACHINES
664 C READY FOR AUTOMATIC READING.
665 C
666 CALL BOX(P,X(J),Y(J),Z(J))
667 CALL SCREEN(ICHAR,X1,Y1)
668 CALL SCREEN(ICHAR,X2,Y2)
669 CALL NEWPAG
670 C CALL BELL
671 CALL UFDISC("MESD1M",10)
672 NLX =DIN("NLX ")
673 NLY =DIN("NLY ")
674 NLZ =DIN("NLZ ")
675 SPACE =DIN("SPACE ")
676 CALL CLDISC("MESD1M",10)
677 CALL MESH(NLX,NLY,NLZ,SPACE)
678 CALL IN3D (CESPAC,"CIVILU")
679 CALL DRAWIT (CESPAC)
680 AS = ATAN2(Y2-Y1,X2-X1)*180.0/3.14159265
681 XS = Y1*DISTRN/PICPLA
682 ZS = X1*DISTRN/PICPLA
683 CALL BOX(P,X(J),Y(J),Z(J))
684
685 CALL HERSH(FNAME(J)(1:12),6,2,60.0,0)
686 CALL TRANSP(0,1)
687 CALL TURN3D(T,270.0,0.0,0.0,1,6)
688 CALL JOIN(P,G)
689 WNAME = FNAME(J)
690 CALL IN3D (V,WNAME)
691 CALL JOIN (G,V)
692 CALL TURN3D(V,AS,0.0,0.0,2,R)
693 CALL SHIFT3(R,XS,0.0,ZS)
694 CALL DRAWIT (R)
695 C CALL DRAW3D(V,1.0,XS,0.0,ZS,1)
696 180 CONTINUE
697 WRITE(6,10)ALPHA
698 WRITE(6,10)SELECT
699
700 WRITE (6,200)
701 200 FORMAT (' Is the POSITION of W.S. according to your wish...
702 &YE or NO?')
703 WRITE(6,10)DESEL
704 WRITE(6,10)GRAPH1
705 210 READ(5,220)ANS
706 220 FORMAT(A2)
707 IF(ANS.EQ."NO".OR.ANS.EQ."N")GOTO 153
708 IF(ANS.EQ."YE".OR.ANS.EQ."Y")GOTO 250
709 WRITE(6,10)ALPHA
710 WRITE(6,10)SELECT
711 WRITE (6,230)
712 230 FORMAT(" Please enter your response again")
713 WRITE(6,10)DESEL
714 WRITE(6,10)GRAPH1
715 GOTO 210
716 250 CONTINUE
717 XPOS(N) = XS
718 ZPOS(N) = ZS
719 ANGLE(N) = AS
720 C

```

```

721 C      POSITION OF THE WORK STATION POSITIONED VIA JOYSTICK
722 C      IS RECORDED/FILED IN 'WSPOSA',11
723 C
724      CALL OPDISC('WSPOSA',11)
725      GO 290 IF N = 1,76
726      IF (XPOS(N).EQ.999.0.AND.ZPOS(N).EQ.999.0) GOTO 291
727      WRITE(10,270)N,XPOS(N),ZPOS(N),ANGLE(N),FRAME(N)(1:12)
728 270      FORMAT(15,3F10.2,A12)
729 290      CONTINUE
730      CALL CLDISC('WSPOSA',11)
731
732      RETURN
733      END
734
735 C
736 C
737 C...
738      SUBROUTINE SUMUPZ (J,SUMX,SUMZ,XS,ZS,AS)
739 C
740 C      THIS SUBROUTINE IS CALCULATING THE TOTAL "Z" DIMENSION
741 C
742
743      REAL X,Y,Z,XPOS,ZPOS,ANGLE
744      REAL XS,ZS,AS
745      REAL P(S00), W(7000), SUMX, SUMZ
746      INTEGER J
747      COMMON/LCHS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
748      &FNAME(77)
749      INTEGER SELECT,DESEL, ALPHA,GRAPH1
750      CHARACTER*12 FNAME
751      CHARACTER*12 WNAME
752      DATA SELECT/'40033'/
753      DATA DESEL/'40433'/
754      DATA ALPHA/'30'/
755      DATA GRAPH1/'35'/
756
757      WRITE(6,10)ALPHA
758 10      FORMAT('4',A2,5)
759      WRITE(6,10)SELECT
760      WRITE (6,20)
761 20      FORMAT (' YOU ARE NOW IN SUMUPZ SUBROUTINE
762      &to activate press return/new line once! '/')
763      WRITE(6,10)DESEL
764      WRITE(6,10)GRAPH1
765 C
766 C      "ZPOS(J)" SUM UP
767 C      SUM UP THE "Z" DIMENSIONS OF ALL PREVIOUS WORK STATIONS
768 C      BECAUSE THE WORK STATION MODULE VOLUME AND WORK STATION
769 C      DETAILED SHOULD BE CONSIDERED BOTH ARE TAKEN INTO
770 C      AN ACCOUNT.
771 C
772 C
773      CALL BOX (P,X(J),Y(J),Z(J))
774      WNAME=FNAME(J)
775      CALL IN3D(X,WNAME)
776 C      write(*,*) ' w',w(4),w(5),w(6)
777 C      write(*,*) ' ',w(7),w(8),w(9)
778      CALL JOIN (P,w)
779      U = DEPTH(W)
780 C      write(*,*) ' p',p(4),p(5),p(6)

```

C 42.

```

781 C      write(+,+) ' ',p(7),p(8),p(9)
782 C
783 C      BECAUSE OF TURNING DURING THE POSITIONING
784 C      THE ANGLE IS CHANGING AND THIS IS CHANGING
785 C      THE ACTUAL DISTANCE OF THE NEXT WORK STATION
786 C      POSITION
787 C      D = D/cosh of the angle
788 C
789 C
790 C      F = D/COS(AS)
791 C
792 C
793 C      INSTEAD OF THE ORIGINAL ZPOS(J) XPOS(J) IS TAKEN
794 C      SUMM OF "Z" DIMENSION
795 C
796 C      write(+,+) ' zs',zs,' d' ,d
797 C      SUMZ = ZS + F
798 C      SUMX=XS
799 C      ZS = SUMZ
800 C      RETURN
801 C      END
802 C
803 C...
804 C
805 C      SUBROUTINE PLACE (K,XSUM,ZSUM,AS,T)
806 C
807 C      (PLACING A REAL W.S. IN THE DIRECTION "Z")
808 C
809 C
810 C      THIS SUBROUTINE IS ACTUALLY PLACING A WORK STATION INTO
811 C      AN OPTIMUM POSITION RELATED TO OTHER SPACES (W.S. VOLUMES
812 C      CIVIL ENG SPACE AND M.H. SPACE). NO INTERVENTION OF
813 C      THE USER IS NEEDED.
814 C
815 C      REAL X,Y,Z,XPOS,ZPOS,ANGLE
816 C      REAL XSUM,ZSUM,AS
817 C      REAL P(500), A(7000), T(7300)
818 C      INTEGER N=5,K
819 C      COMMON/LCHS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
820 C      &FNAME(77)
821 C      INTEGER SELECT,DESEL, ALPHA,GRAPH1
822 C      CHARACTER*12 FNAME
823 C      CHARACTER*12 ASNAME
824 C      DATA X,Y,Z/231*999.0/
825 C      DATA XPOS,ZPOS/154*999.0/
826 C      DATA ANGLE/77*0.0/
827 C      DATA SELECT/"40033/
828 C      DATA DESEL/"40433/
829 C      DATA ALPHA/"30/
830 C      DATA GRAPH1/"35/
831 C
832 C      CALL BELL
833 C      WRITE(6,10)ALPHA
834 C      10  FORMAT("+",A2,S)
835 C      WRITE(6,10)SELECT
836 C      WRITE (6,20)
837 C      20  FORMAT (' YOU ARE NOW IN AUTOMATIC MODE
838 C      &to activate press return/new line once! "')
839 C      WRITE(6,10)DESEL
840 C      WRITE(6,10)GRAPH1

```

43.

```

841
842 C      AFTER THE SUM UP THE NEXT PLACES THE WORK STATION
843 C      VOLUME IN AN OPTIMUM POSITION WITH A NEW 'Z' DIMENSION
844 C      BUT THERE ARE NO CHANGES IN 'X' DIMENSION YET
845 C
846 C      CALL BELL
847 CALL OPDISC('MESDIM',10)
848 NLX =DIN('NLX  ')
849 NLY =DIN('NLY  ')
850 NLZ =DIN('NLZ  ')
851 SPACE =DIN('SPACE ')
852 CALL CLDISC('MESDIM',10)
853 CALL MESH(NLX,NLY,NLZ,SPACE)
854
855 CALL BOX(P,X(K),Y(K),Z(K))
856
857 XNAME = FNAME(K)
858 C
859 C      DETAILED WORK STATION IS RETRIEVED FROM THE DISC "XNAME"
860 C
861 CALL IN3D(X,XNAME)
862 CALL JOIN (P,X)
863 CALL TURN3D(X,AS,0.0,0.0,2,T)
864 CALL SHIF3 (T,XSUM,0.0,ZSUM)
865 CALL DRAWIT (T)
866 RETURN
867 END
868 C...
869 SUBROUTINE SIGNAL
870 300 CONTINUE
871 WRITE (6,40)
872 40  FORMAT (' DIAGNOSTIC !'//)
873
874 400 CALL BELL
875 WRITE (6,410)
876 410 FORMAT (' CLASH!!! CORRECTIVE ACTION KINDLY REQUESTED!')
877
878 500 CONTINUE
879 RETURN
880 END
881 C
882 C      FOLLOWS SUBROUTINE FOR COLLISION OF THE LAST WORK
883 C      STATION AND THE BUILDING (CIVIL ENG. SPACE)
884 C
885 C...
886
887 SUBROUTINE COLLOWS (WS1,CESPAK,RESULT)
888 REAL WS1(7300)
889
890 REAL CESPAK(10000)
891 INTEGER RESULT,AREA
892 C      COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
893 C      &FNAME(77)
894
895 CHARACTER*12 FNAME
896 CHARACTER*12 XNAME
897
898 INTEGER SELECT,DESEL, ALPHA,GRAPHI
899 DATA SELECT/'40033'/
900 DATA DESEL/'40433'/

```

44.

```

901      DATA ALPHA/'30/
902      DATA GRAPHI/'35/
903      C
904      C      FIRST CALL IN CIVIL ENG. SPACE
905      C
906      C      CALL IN3D (CESPAC,'CIVILD')
907
908
909      C      FOLLOWS SUBROUTINE FOR CHECKING RESULT
910      C      OF COLLISION
911
912      WRITE (6,10) ALPHA
913      FORMAT ('+',A2,S)
914      WRITE (6,10) SELECT
915      WRITE (6,30)
916      30      FORMAT (' 1 = INSIDE'/' 2 = TOUCH (O.K.)'/' 3 = OUTSIDE')
917      WRITE (6,10) DESEL
918      WRITE (6,10) GRAPHI
919      CALL INSPAC (WS1,CESPAC,RESULT)
920      WRITE (6,100) RESULT
921      100      FORMAT (18)
922
923
924      RETURN
925      END
926      C
927      C      "INSPAC" IS CONTROLLING THE PROCESS IN
928      C      THE COLLISION FINDING
929      C
930      C...
931      SUBROUTINE INSPAC (WS1,CESPAC,RESULT)
932      REAL WS(1), CESPAC(1), OBJECT(100)
933      C
934      C      WS1      = WORK STATION WHICH IS (AS A LAST ONE) POSITIONED
935      C      IN THE BAY (CIVIL ENG. SPACE)
936      C      CESPAC = BUILDING (CIVIL ENG. SPACE)
937      C      OBJECT = IS ANY CIVIL ENG. ELEMENT OF WHICH THE BUILDING
938      C      CONSIST
939      C
940      C      INTEGER RESULT, AREA
941      C      COMMON/LCAS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
942      C      &FRAME(77)
943      C
944      C      NBLOCK IS GIVEN BY A NUMBER OF PICASSO CONTOURS
945      C      AND IS ACTUALLY GIVING (BY ANALYSIS) A NUMBER
946      C      OF OBJECTS OF WHICH THE BUILDING CONSISTS
947      C      AND IS LIMITING THE NUMBER OF LOOPS
948      C
949      C      NBLOCK = CESPAC(2)/6.0
950      C      DO 100 N = 1, NBLOCK
951      C      CALL ABOX (CESPAC, N, OBJECT)
952      C      CALL COLISN (WS1, OBJECT, RESULT, AREA)
953      C      WRITE (6,80) RESULT
954      C      80      FORMAT (18)
955      C      IF (RESULT.EQ.1) RETURN
956      C      100      CONTINUE
957
958      RETURN
959      END
960      C

```

45.

```

961 C "ABOX" IS RETRIEVING FROM CIVIL ENGINEERING
962 C DRAWING INDIVIDUAL CIVIL ENGINEERING SPACES(ELEMENTS)
963 C ONE SPACE(ELEMENT - ACTUALLY THE "NTH",NEN) IN TIME
964 C...
965 SUBROUTINE ABOX (CESPAC, NTH, OBJECT)
966 REAL CESPAC(1), OBJECT(1), SHAPE(100)
967 INTEGER FROM, TO
968 C COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
969 C &FNAME(77)
970
971 IF (NTH.LT.1) THEN
972 GOTO 200
973 ELSE IF (NTH.GT.100) THEN
974 GOTO 250
975 ELSE
976 GOTO 270
977 END IF
978 200 CONTINUE
979 C
980 WRITE (6,310)
981 310 FORMAT('DIAGNOSTIC - WRONG READING 1')
982 250 WRITE (6,320)
983 320 FORMAT('DIAGNOSTIC - TOO BIG -ERROR 2')
984 C
985 C READING OF CONTOURS OF INDIVIDUAL OBJECTS
986 C
987 270 CONTINUE
988
989 FROM = (NTH - 1) * 6 + 1
990 TO = FROM + 5
991
992 DO 10 N = FROM, TO
993 C
994 C THE INDIVIDUAL SHAPE IS EXTRACTED
995 C
996 CALL EXTGH (CESPAC, N, SHAPE)
997 IF (N.EQ.FROM) CALL COPY (SHAPE,OBJECT)
998 IF (N.NE.FROM) CALL JOIN (SHAPE,OBJECT)
999 10 CONTINUE
1000 RETURN
1001 END
1002 C...
1003 C...
1004
1005 SUBROUTINE COLISH (WS1,OBJECT,RESULT,AREA)
1006 REAL WS1(1),OBJECT(100)
1007 INTEGER RESULT,AREA
1008 C COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
1009 C &FNAME(77)
1010 INTEGER SELECT,DESEL, ALPHA,GRAPH1
1011 DATA SELECT/'40033'/
1012 DATA DESEL/'40433'/
1013 DATA ALPHA/'30'/
1014 DATA GRAPH1/'35'/
1015
1016 WRITE (6,10) ALPHA
1017 10 FORMAT ('+',A2,5)
1018 WRITE (6,10) SELECT
1019 CALL HULL3D (WS1,XMIN1,XMAX1,YMIN1,YMAX1,ZMIN1,ZMAX1)
1020 CALL HULL3D (OBJECT,XMIN2,XMAX2,YMIN2,YMAX2,ZMIN2,ZMAX2)

```

46.

```

1021
1022      RESULT = 3
1023      WRITE (6,30) RESULT
1024      FORMAT (18)
1025      C      AREA = 1
1026      C
1027      C      HORIZONTAL PLANE IN AREA "X" IS TESTED (AREA=1)
1028      C
1029      IF (XMIN2.EQ.XMAX1.OR.XMAX2.EQ.XMIN1) GOTO 100
1030      C      CONDITION OF OUTSIDE ... 3 IS CONSIDERED
1031      IF (XMAX2.LT.XMIN1.OR.XMIN2.GT.XMAX1) RETURN
1032      GOTO 150
1033      100      IF ((YMIN2.LE.YMAX1.AND.YMAX2.GT.YMIN1).OR.
1034      &(YMAX2.GE.YMIN1.AND.YMIN2.GT.YMIN1)) GOTO 200
1035      C      CONDITION OUTSIDE ... 3 IS CONSIDERED
1036      150      IF (YMAX2.LT.YMIN1.OR.YMIN2.GT.YMAX1) RETURN
1037      GOTO 250
1038      C
1039      C      CONDITION IN Z-DIMENSION
1040      C      CONDITION "TOUCH...2" IS CONSIDERED
1041      C
1042      200      IF ((ZMIN2.LE.ZMAX1.AND.ZMAX2.GT.ZMIN1).OR.
1043      &(ZMAX2.GE.ZMIN1.AND.ZMIN2.GT.ZMIN1)) GOTO 300
1044      250      IF (ZMAX2.LT.ZMIN1.OR.ZMIN2.GT.ZMAX1) RETURN
1045      RESULT = 1
1046      WRITE (6,260) RESULT
1047      260      FORMAT (18)
1048      RETURN
1049      300      RESULT = 2
1050      WRITE (6,320) RESULT
1051      320      FORMAT (18)
1052
1053      WRITE (6,10)DESEL
1054      WRITE (6,10)GRAPH1
1055      RETURN
1056      END
1057      C....
1058      C      END OF PROGRAM "COLLCS1.FOR"
1059      C
1060      C....
1061      C....
1062      SUBROUTINE JOYST(NWS,PICPLA,DISTNC,J)
1063      REAL P(500),R(2000),U(2000),I(2000),U(2000)
1064      REAL V(2000),CESPAC(10000)
1065      INTEGER NWS
1066      COMMON/LCHS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
1067      &FNAME(77)
1068      INTEGER SELECT,DESEL,ALPHA,GRAPH1
1069      CHARACTER*12 FNAME
1070      CHARACTER*12 WNAME
1071
1072      DATA SELECT/"40033"/
1073      DATA DESEL/"40433"/
1074      DATA ALPHA/"30"/
1075      DATA GRAPH1/"35"/
1076
1077      60      CALL BELL
1078      CALL PLIT(3.0,-5.0,3)
1079      WRITE(6,70)ALPHA
1080      70      FORMAT('+',A2,S)

```


47.

```

1081      WRITE(6,70)SELECT
1082      WRITE(6,80)
1083      80  FORMAT(' Which work Station..to start from? Type Tag No...')
1084      & ' To end ...type "END"'
1085      WRITE(6,70)DESEL
1086      WRITE(6,70)GRAPHI
1087
1088      90  CONTINUE
1089      READ (5,100) W$NAME
1090      100  FORMAT (A12)
1091      WRITE (6,110) W$NAME
1092      110  FORMAT (1A,A12)
1093      IF (W$NAME(1:3).EQ."END") GOTO 190
1094
1095      DO 120 J = 1,76
1096      IF (W$NAME.EQ.FNAME(J)(1:12)) GOTO 140
1097      120  CONTINUE
1098
1099      WRITE (6,130)
1100      130  FORMAT (' Please enter your TAG NO exactly again')
1101      GOTO 90
1102
1103      C
1104      C
1105      140  CALL BOX(P,X(J),Y(J),Z(J))
1106      CALL SCREEN(1CHAR,X1,Y1)
1107      CALL SCREEN(1CHAR,X2,Y2)
1108      CALL NEWPAG
1109      CALL BELL
1110      CALL OPDISC("MESDIM",10)
1111      NLX  =DIN("NLX  ")
1112      NLY  =DIN("NLY  ")
1113      NLZ  =DIN("NLZ  ")
1114      SPACE =DIN("SPACE ")
1115      CALL CLDISC("MESDIM",10)
1116      CALL HESH(NLX,NLY,NLZ,SPACE)
1117      CALL IN3D (CESPAC,"CIVILD")
1118      CALL DRAWIT (CESPAC)
1119      ANGLE(J) = ATAN2(Y2-Y1,X2-X1)*180.0/3.14159265
1120      XPOS(J) = Y1*DISTNC/PICPLA
1121      ZPOS(J) = X1*DISINC/PICPLA
1122      DO 180 M = 1,76
1123      CALL BOX(P,X(M),Y(M),Z(M))
1124      XWORK = XPOS(M)
1125      ZWORK = ZPOS(M)
1126      IF(XWORK.EQ.999.0.AND.ZWORK.EQ.999.0)GOTO 180
1127      CALL HERSH(FNAME(M)(1:12),6,2,60.0,0)
1128      CALL TRANSP(G,T)
1129      CALL TURN3D(T,270.0,0.0,0.0,1,U)
1130      CALL JOIN(P,U)
1131      CALL IN3D (V,FNAME(M))
1132      CALL JOIN (U,V)
1133
1134      CALL TURN3D(V,ANGLE(M),0.0,0.0,2,H)
1135      CALL SHIFT3 (H,XWORK,0.0,ZWORK)
1136      CALL DRAWIT (H)
1137      C  CALL DRAW3D(U,1.0,XWORK,0.0,ZWORK,1)
1138      180  CONTINUE
1139      GOTO 60
1140      190  CONTINUE

```

48.

```

1141 CALL OPDISC('SPOSA',11)
1142 DO 200 M = 1,76
1143 IF(XPOS(M).EQ.999.0.AND.ZPOS(M).EQ.999.0)GOTO 200
1144 WRITE(10,210)M,XPOS(M),ZPOS(M),ANGLE(M),FNAME(M)(1:12)
1145 210 FORMAT(15,3F10.2,A12)
1146 200 CONTINUE
1147 CALL CLDISC('SPOSA',11)
1148 250 RETURN
1149 END
1150 C...
1151 SUBROUTINE PRESITDET (NWS)
1152 C
1153 C THIS IS A SUBROUTINE FOR SHOWING THE PRESENT SITUATION
1154 C WITH DETAILED WORK STATIONS DRAWN
1155
1156 C
1157 REAL P(500),R(2000),G(2000),T(2000),U(2000)
1158 REAL CESPAC(10000),V(2000)
1159 INTEGER NWS
1160 COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
1161 &FNAME(77)
1162 INTEGER SELECT,DESEL, ALPHA,GRAPH1
1163 CHARACTER*12 FNAME
1164 CHARACTER*12 ASNAME
1165 DATA SELECT/'40033'/
1166 DATA DESEL/'40433'/
1167 DATA ALPHA/'30'/
1168 DATA GRAPH1/'35'/
1169 C PRINTING THE PRESENT SITUATION OF LAYOUT DEVELOPMENT
1170 WRITE(6,10)ALPHA
1171 10 FORMAT(' ',A2,S)
1172 WRITE(6,10)SELECT
1173 WRITE(6,20)
1174 20 FORMAT(' LAYOUT...The existing situation of development')
1175 WRITE(6,10)DESEL
1176 WRITE(6,10)GRAPH1
1177 CALL BELL
1178 CALL OPDISC('MESDIN',10)
1179 NLX =DIN('NLX ')
1180 NLY =DIN('NLY ')
1181 NLZ =DIN('NLZ ')
1182 SPACE =DIN('SPACE ')
1183 CALL CLDISC('MESDIN',10)
1184 CALL MESH(NLX,NLY,NLZ,SPACE)
1185 C
1186 C BUILDING IS CALLED IN
1187 C
1188 CALL IN3D (CESPAC,'CIVILD')
1189 CALL DRAWIT (CESPAC)
1190 CALL OPDISC('ASVTOR',12)
1191 40 READ(12,60,END=50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
1192 CALL OPDISC('SPOSA',11)
1193 50 READ(11,60,END=90)J,XPOS(J),ZPOS(J),ANGLE(J),FNAME(J)(1:12)
1194 60 FORMAT(15,3F8.2,A12)
1195 CALL BOX(P,X(J),Y(J),Z(J))
1196 XWORK = XPOS(J)
1197 ZWORK = ZPOS(J)
1198 CALL TURN3D(P,ANGLE(J),0.0,0.0,2,R)
1199 CALL HERSH(FNAME(J)(1:12),6,2,60.0,0)
1200 CALL TRANSP(G,T)

```

49.

```
1201      CALL TURN3D(T,270.0,0.0,0.0,1,U)
1202      CALL JOIN(R,U)
1203      W$NAME = F$NAME(J)
1204      CALL IN3D (V,W$NAME)
1205      CALL JOIN(U,V)
1206      CALL SHIFT3 (V,XWORK,0.0,ZWORK)
1207      CALL DRAWIT (V)
1208      C      CALL DRA*3D(U,1.0,XWORK,0.0,ZWORK,1)
1209      GOTO 40
1210      90      CONTINUE
1211      CALL CLDISC("W$POSA",11)
1212      CALL CLDISC("W$VTOR",12)
1213
1214
1215      RETURN
1216      END
1217      C...
1218      C...
1219      C....
1220      C      FILE ORDER "POSCLASH4.FOR"
```

[illegible]

0000	III	SSSS	F	7777	A	A	X
000	I	S	F	7	A	A	X
000	I	S	F	7	AAAA	A	X
000	I	SSS	FFFF	7	A	A	X
000	I	S	F	7	A	A	X
000	I	S	F	7	A	A	X
0000	III	SSSS	FFFF	7	AAA	A	X

999	999	111	111	8888	000	000
9 9 9	9 9 9	1 1 1	1 1 1	8 8 8	0 0 0	0 0 0
9 9 9	9 9 9	1 1 1	1 1 1	8 8 8	0 0 0	0 0 0
9999	9999	1 1 1	1 1 1	8888	0 0 0	0 0 0
9 9 9	9 9 9	1 1 1	1 1 1	8 8 8	0 0 0	0 0 0
9 9 9	9 9 9	1 1 1	1 1 1	8 8 8	0 0 0	0 0 0
999	999	1 1 1	1 1 1	8888	000	000

Printer - LPAO: on 9-NOV-1987 12:15 from queue LPAO.

```

##### Digital Equipment Corporation - VAX/VMS Version V4.5 #####

```

51.

```

1  C  "DISPLAY.FOR"
2  C  THIS IS A PROGRAM FOR DISPLAY OF WHOLE DESIGNES
3  C  SCENE TO ENABLE THE USER TO OBSERVE THE LAYOUT
4  C  FROM ANY REQUESTED POSITION
5  C
6  C
7  C
8  C  INTEGER NWS
9  C  COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
10 C  &FNAME(77)
11 C  REAL P(500),R(2000),O(2000),T(2000),U(2000)
12 C  REAL CESPAC(10000)
13 C  INTEGER SELECT,DESEL,ALPHA,GRAPH1
14 C  CHARACTER*12 FNAME
15 C  CHARACTER*12 WSKAME
16 C  DATA SELECT/"40033/"
17 C  DATA DESEL/"40433/"
18 C  DATA ALPHA/"30/"
19 C  DATA GRAPH1/"35/"
20 C  DATA XPOS,ZPOS/154*999.0/
21 C  DATA ANGLE/77*0.0/
22 C  CALL START
23 C  CALL FACTOR(1.0)
24 C  CALL FORMAT (81.1,59.4)
25 C  CALL FRAME(-55.0,29.0,-35.0,20.0)
26
27
28 3  FORMAT("Program for display of Industr. Bay in required
29 & elevation with detailed work Stations")
30
31 5  WRITE(6,5)ALPHA
32   FORMAT(A2)
33   WRITE(6,5)SELECT
34   WRITE(6,3)
35   WRITE(6,5)DESEL
36   WRITE(6,5)GRAPH1
37   WRITE(6,10)
38 10  FORMAT("Please enter the DISTINC, ROTATN, ELEVTR")
39   READ(5,*) DISTINC, ROTATN, ELEVTR
40   WRITE(6,20)
41 20  FORMAT ("Please enter the PICPLA(ZOOM) FACTOR")
42   READ(5,*) ZOOM
43   CALL NEWPAG
44   CALL BELL
45   CONTINUE
46   CALL PEYE (0.0,0.0,0.0,DISTINC,ROTATN,ELEVTR)
47   CALL PLAVE (ZOOM)
48  C  CALL MESH(MLX,MLY,MLZ,SPACE)
49   CALL UPDISC("WSVOLD",10)
50   NWS=1
51 50  READ(10,70,END=90)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
52 70  FORMAT(15,3F8.2,A12)
53   NWS=NWS+1
54   GOTO 50
55 90  CALL CLDISC("WSVOLD",10)
56   NWS = NWS-1
57   CALL PRESIT (NWS)
58
59   CALL NCLOSE
60   CALL FINISH
61   STOP

```

52.

```

61      END
62      C...
63      SUBROUTINE PRESIT (NLS)
64      C
65      C      THIS IS A SUBROUTINE FOR SHOWING THE PRESENT SITUATION
66      C
67      REAL P(500),R(5000),G(2000),T(2000),U(2000),V(5000)
68      REAL CESPAC(10000)
69      INTEGER NLS
70      COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
71      &FNAME(77)
72      INTEGER SELECT,DESEL, ALPHA,GRAPH1
73      CHARACTER*12 FNAME
74      CHARACTER*12 WSNAME
75      DATA SELECT/'40033'/
76      DATA DESEL/'40433'/
77      DATA ALPHA/'30'/
78      DATA GRAPH1/'35'/
79      C      PRINTING THE PRESENT SITUATION OF LAYOUT DEVELOPMENT
80      WRITE(6,10)ALPHA
81      10      FORMAT('+',A2,S)
82      WRITE(6,10)SELECT
83      WRITE(6,20)
84      20      FORMAT(' LAYOUT...The existing situation of development')
85      WRITE(6,10)DESEL
86      WRITE(6,10)GRAPH1
87      CALL BELL
88      CALL OPDISC('MESDIR',10)
89      NLX =DIR('NLX ')
90      NLY =DIR('NLY ')
91      NLZ =DIR('NLZ ')
92      SPACE =DIR('SPACE ')
93      CALL CLDISC('MESDIR',10)
94      CALL MESH(NLX,NLY,NLZ,SPACE)
95      C
96      C      BUILDING IS CALLED IN
97      C
98      CALL IN3D (CESPAC,'CIVILD')
99      CALL DRAWIT (CESPAC)
100     CALL OPDISC('MSYTOR',12)
101     40     READ(12,60,END=50)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
102     CALL OPDISC('MSPOSA',11)
103     50     READ(11,60,END=90)J,XPOS(J),ZPOS(J),ANGLE(J),FNAME(J)(1:12)
104     60     FORMAT(15,3F8.2,A12)
105     CALL BOX(P,X(J),Y(J),Z(J))
106     WSNAME = FNAME(J)
107     XWORK = XPOS(J)
108     ZWORK = ZPOS(J)
109     CALL MESH(FNAME(J)(1:12),6,2,60,0,0)
110     CALL TRANSP(0,1)
111     CALL TURN3DCT,270.0,0.0,0.0,1,0)
112     CALL JOIN(P,0)
113     CALL IN3D(V,WSNAME)
114     CALL JOIN(U,V)
115     CALL TURN3D(V,ANGLE(J),0.0,0.0,2,R)
116     CALL SHIFTE (XWORK,0.0,ZWORK)
117     CALL DRAWIT (R)
118     C      CALL DRAW3D(U,1.0,XWORK,0.0,ZWORK,1)
119     GOTO 40
120     90     CONTINUE

```

53.

```
121      CALL CLDISC(*SPOSA*,11)
122      CALL CLDISC(*SVTOR*,12)
123
124
125      RETURN
126      END
127
128      C
129      C...
130      SUBROUTINE MESH(NLX,NLY,NLZ,SPACE)
131      REAL A(1000)
132      CALL GRIL3D(A,NLX,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,SPACE,.0,.0)
133      CALL DRAWIT(A)
134      CALL GRIL3D(A,NLY,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,SPACE,.0)
135      CALL DRAWIT(A)
136      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLY-1)*SPACE,.0,.0,.0,SPACE)
137      CALL DRAWIT(A)
138      CALL GRIL3D(A,NLY,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,.0,SPACE,.0)
139      CALL DRAWIT(A)
140      CALL GRIL3D(A,NLX,.0,.0,.0,.0,.0,FLOAT(NLZ-1)*SPACE,SPACE,.0,.0)
141      CALL DRAWIT(A)
142      CALL GRIL3D(A,NLZ,.0,.0,.0,.0,FLOAT(NLX-1)*SPACE,.0,.0,.0,.0,SPACE)
143      CALL DRAWIT(A)
144      RETURN
145      END
146      C...
147      C...
148      C...
149      C...
150      C
151      C...
152      C      FILE UNDER 'DISPLAY'
```

BBB BBB	000000	BBB BBB	11
BBB BBB	000000	BBB BBB	11
BB BB 00	00 BB BB	1111	
BB BB 00	00 BB BB	1111	
BB BB 00	00 BB BB	11	
BB BB 00	00 BB BB	11	
BBB BBB BB	00 00 BBBB BB	11	
BBB BBB BB	00 00 BBBB BB	11	
BB BB 00	00 BB BB	11	
BB BB 00	00 BB BB	11	
BB BB 00	00 BB BB	11	
BB BB 00	00 BB BB	11	
BBB BBB BB	000000	BBB BBB BB	111111
BBB BBB BB	000000	BBB BBB BB	111111

M	M	FFFFF	EEEE	EEEE	DODD	
MM	MM	F	E	E	O	O
M	M	F	E	E	D	D
M	M	FFFF	EEEE	EEEE	O	O
M	M	F	E	E	O	D
M	M	F	E	E	O	D
M	M	F	EEEE	EEEE	ODDD	

J	000	BBB	1	1	666	777				
J	0	0	B	B	11	11	6	7		
J	0	0	B	B	1	1	6	7		
J	0	0	BBB	1	1	666	7			
J	J	0	0	B	B	1	1	6	6	7
J	J	0	0	B	B	1	1	6	6	7
JJJ	000	BBB	111	111	666	7				

) queued to SYSSPRINT on 9-NOV-1987 12:16 by user BOB1, UIC [RESM0012,BOB1], under account RESM0012, after LPA0: on 9-NOV-1987 12:17 from queue LPA0.

[illegible]

55

```

1 C THIS IS A MANUAL FEED PROGRAM "MFEE0.FOR"
2 C FEEDING INFORMATION ABOUT POSITION OF WORK STATION
3 C ACCORDING TO TECHNOLOGICAL ORDER/LINE
4 C
5 C THE PROGRAM IS ALSO SIMULATING THE DR. CARRIES
6 C PROGRAM FOR TECHNOLOGICAL POSITIONING OF WORK STATIONS
7 C
8 C THE PROGRAM IS FEEDING INFORMATION INTO A FILE "TECHORD"
9 C (IN TECH. LINE ...1,2,3,4, ECT....!!!)
10 C
11 C
12 C
13 C FROM THIS DISK THE INFORMATION ARE FEAD INTO THE
14 C AUTOMATIC POSITIONING PROGRAM "POSCLASH"
15 C
16 C
17 C
18 C INTEGER ANS
19 C CHARACTER *12 WNAME (200),WS
20 C CALL START
21 C OUTPUT OF EXISTING DATA FILE
22 C THE LINE IS NOT CHANGING (MUST REMAIN IN A TECHNOLOGICAL
23 C ORDER / IN A LINE)
24 C INFORMATION HAS TO BE REC IN FORMAT line No. contra Tag.No.
25 C
26 C
27 5 CONTINUE
28 C WRITE (6,10)
29 10 FORMAT (" LIST OF M/C AND EQUIPMENT IN TECHNOLOGICAL ORDER'//)
30 C WRITE (6,20) " Line", "Work Sto Number"
31 20 FORMAT (A5,1A,A10)
32 50 CONTINUE
33 C CALL OPDISC ("TECHORD",11)
34 60 CONTINUE
35 C READ (11,130,END=135) N,WSNAME(N)(1:12)
36 130 FORMAT (15,A12)
37 C WRITE (6,132) N,WSNAME(N)(1:12)
38 132 FORMAT (15,2A,A12)
39 C
40 C GOTO 60
41 135 C WRITE(6,137)
42 137 C FORMAT (" THERE IS NOTHING MORE IN THE FILE'//)
43 C CALL CLDISC ("TECHORD",11)
44 C
45 C EXTENDING THE FILE
46 C
47 138 C WRITE (6,140)
48 140 C FORMAT (/ " Do you wish to extend or change the file - YE or NO'//)
49 C READ (5,150)ANS
50 150 C FORMAT (A2)
51 C IF (ANS.EQ."NO".OR.ANS.EQ."N") GOTO 500
52 C IF (ANS.EQ."YE".OR.ANS.EQ."Y") GOTO 170
53 C
54 C ERROR MESSAGE
55 C
56 C WRITE(6,160)
57 160 C FORMAT (" Please enter your response again! Use CAPITALS!")
58 C GOTO 138
59 C
60 C EXTENDING THE FILE

```

56.

```

61 C
62 170 CONTINUE
63 WRITE (6,172)
64 172 FORMAT (' To run program requested type the prefix letter'/
65 &' for adding a new Work Station at the end type _A_'/
66 &' for inserting Work Station above a W.S. type _I_'/
67 &' for deleting any Work Station type _R_')
68 READ (5,174) ACTION
69 174 FORMAT (A1)
70 IF (ACTION.EQ.'A') GO TO 175
71 IF (ACTION.EQ.'I') GO TO 300
72 IF (ACTION.EQ.'R') GO TO 400
73 WRITE (5,160)
74 GO TO 170
75 175 CONTINUE
76 C
77 C FEEDING IN INFORMATION ABOUT THE POSIT OF W.S. LINE OR
78 C ADDING A NEW WORK STATION AT THE END OF LINE
79 C (ADDING TO THE LINE EX: ...3,4,5,...ADDING 6,7,8 ETC)
80 C
81 WRITE (6,180)
82 180 FORMAT(' Please enter line No. and W.S.No to end type 200')
83 READ (5,130) N,WSNAME(N)(1:12)
84 IF (N.EQ.200) GOTO 210
85 C
86 C OUTPUT OF THE LATEST DATA TO DISC AND TERMINAL
87 C
88 CALL UPDISC ('TECHORD',11)
89 190 READ (11,130,END=200)I,WSNAME(I)(1:12)
90 GOTO 190
91 200 WRITE(11,130)N,WSNAME(N)(1:12)
92 CALL CLDISC ('TECHORD',11)
93 GO TO 175
94 210 CONTINUE
95 C
96 C PRINT THE DEVELOPED LIST OF W.S. ON THE VDU
97 C
98 GO TO 5
99 C
100 C INSERTING A NEW W.S. INTO THE EXISTING LINE
101 C
102 300 CONTINUE
103 CALL UPDISC ('TEMP,DAT',10)
104 CALL UPDISC ('TECHORD',11)
105 WRITE (6,180)
106 READ (5,130) N,WS(1:12)
107 310 READ (11,130,END=330)I,WSNAME(I)(1:12)
108 IF (N.NE.I) GO TO 320
109 WRITE(10,130)N,WS
110 320 J=I
111 IF (I.GE.N) J=J+1
112 WRITE (10,130) J,WSNAME(I)(1:12)
113 GO TO 310
114 330 CONTINUE
115 CALL CLDISC ('TEMP,DAT',10)
116 CLOSE (UNIT=11,DISPOSE='DELETE')
117 CALL UPDISC ('TEMP,DAT',10)
118 CALL UPDISC ('TECHORD,DAT',11)
119 340 READ (10,130,END=350)N,WSNAME(N)(1:12)
120 WRITE (11,130) N,WSNAME(N)(1:12)

```

```

121      GO TO 340
122 350   CALL CLDISC ('TECHORD.DAT',11)
123      CLOSE (UNIT=10,DISPOSE='DELETE')
124      CONTINUE
125  C
126  C   PRINT THE DEVELOPED LIST OF W.S. ON THE VDU
127  C
128      GO TO 5
129 400   CONTINUE
130  C
131  C   RETYPING/DELETING AN EXISTING W.S. AND REPOSITIONING
132  C   THE LINE OF WORK STATION
133  C
134      CALL OPDISC ('TEMP.DAT',10)
135      CALL CLDISC ('TECHORD',11)
136      WRITE (6,405)
137 405   FORMAT (' Type position and W.S. which has to be deleted')
138      READ (5,130) N,WS(1:12)
139 410   READ (11,130,END=430)K,WSNAME(K)(1:12)
140      IF(N.EQ.K) GO TO 410
141      J=K
142      IF (K.GT.N) J=J-1
143      WRITE (10,130) J,WSNAME(K)(1:12)
144      GO TO 410
145 430   CONTINUE
146      CALL CLDISC ('TEMP.DAT',10)
147      CLOSE (UNIT=11,DISPOSE='DELETE')
148      CALL OPDISC ('TEMP.DAT',10)
149      CALL OPDISC ('TECHORD.DAT',11)
150 440   READ (10,130,END=450)N,WSNAME(N)(1:12)
151      WRITE (11,130) N,WSNAME(N)(1:12)
152      GO TO 440
153 450   CALL CLDISC ('TECHORD.DAT',11)
154      CLOSE (UNIT=10,DISPOSE='DELETE')
155      CONTINUE
156  C
157  C   PRINT THE DEVELOPED LIST OF W.S. ON THE VDU
158  C
159      GO TO 5
160 500   CONTINUE
161      STOP
162      END
163  C
164  C
165  C....
166  C   FILE 'MFEED'
167  C

```

W	W	SSSS	V	V	TTTT	000	TTTT	000
W	W	S	V	V	T	0	0	0
W	W	S	V	V	T	0	0	0
W	W	SSS	V	V	T	0	0	0
W	W	S	V	V	T	0	0	0
W	W	S	V	V	T	0	0	0
W	W	SSSS	V	V	T	000	T	000

66) queued to SYS\$PRINT on 9-NOV-1987 12:16 by user B081, BIC [RESM0012,B081], under account RESM0012; printer _LPA0: on 9-NOV-1987 12:16 from queue LPA0.

[illegible]

```

1  C  PROGRAM/SUBROUTINE WSVIOTO
2  C  (WORK STATION (VOLUMES) TO TECHNOLOGICAL ORDER)
3  C
4  C  THIS SUBROUTINE IS RETRIEVING WORK STATION REQUESTED
5  C  FOR A SUGGESTED PRODUCTION LINE FROM THE "WSVOLD" FILE
6  C  AND REORGANISES THEM IN TECHNOLOGICAL ORDER-LINE(I.E. FOR
7  C  PRODUCTION OR PRODUCT ORIENTATED LAYOUT OR GROUP
8  C  TECHNOLOGY ORIENTATED LAYOUT).
9  C
10
11  REAL X,Y,Z,XPOS,ZPOS,ANGLE
12  INTEGER J,K,N
13  COMMON/LCWS/X(77),Y(77),Z(77),XPOS(77),ZPOS(77),ANGLE(77),
14  &FNAME(77)
15  CHARACTER*12 FNAME
16  CHARACTER*12 WSNNAME(77)
17
18  CALL START
19
20  C
21  C  FIRST NAME OF W.S. IN TECHNOLOGICAL ORDER IS RETRIEVED
22  C
23  CALL OPDISC ("WSVTOR",12)
24  CALL OPDISC ("TECHORD",11)
25  20  CONTINUE
26  READ (11,50,END=400)N,WSNNAME(N)(1:12)
27  50  FORMAT (15,A12)
28
29  CONTINUE
30  CALL OPDISC ("WSVOLD",10)
31  60  CONTINUE
32  READ (10,80,END=100)J,X(J),Y(J),Z(J),FNAME(J)(1:12)
33  80  FORMAT (15,3F8.2,A12)
34
35  C
36  C  COMPARE LIST OF W.S.VOL. WITH TECHNOLOGICAL ORDER
37  C
38  IF (WSNNAME(N)(1:12).EQ.FNAME(J)(1:12)) GOTO 100
39  IF (WSNNAME(N)(1:12).NE.FNAME(J)(1:12)) GOTO 90
40  90  CONTINUE
41  GOTO 60
42  100 CONTINUE
43  WRITE (12,150) N,X(J),Y(J),Z(J),FNAME(J)(1:12)
44  150 FORMAT (15,3F8.2,A12)
45  CALL CLDISC ("WSVOLD",10)
46
47  GOTO 20
48  400 CONTINUE
49  CALL CLDISC ("TECHORD",11)
50  CALL CLDISC ("WSVTOR",12)
51  C
52  C  READ ALL CREATED LINE OF W.S.VOL. IN TECHNOLOGICAL ORDER
53  C
54  CALL OPDISC ("WSVTOR",12)
55
56  K = 1
57  450 CONTINUE
58  READ (12,470,END=550) K,X(K),Y(K),Z(K),FNAME(K)(1:12)
59  470 FORMAT (15,3F8.2,A12)
60  WRITE (6,480)K,X(K),Y(K),Z(K),FNAME(K)(1:12)

```

60.

```
61 480 FORMAT (15,3F8.2,1X,A12)
62      K = K+1
63      GOTO 450
64 550 CONTINUE
65      CALL CDDISC ('4SVTOR',12)
66      C      RETURN
67      STOP
68      END
```

666	999	111	111	9999	000	000
6	9	9	1	1	9	9
6	9	9	1	1	9	9
6666	9999	1	1	9999	0	0
6	6	9	1	1	9	9
6	6	9	1	1	9	9
666	999	1	1	9999	000	0

000	000	111	W	W
0 0	0 0	1	W	W
0 00	0 00	1	W	W
0 0 0	0 0 0	1	W	W
00 0	00 0	1	W	W
0 0	0 0	11	W	W
000	000	1	W	W

୧୧୧୧୧	୧୧୧୧୧୧୧୧	୦୦୦୦୦୦	୧୧୧୧୧୧୧୧
୧୧୧୧୧	୧୧୧୧୧୧୧୧	୦୦୦୦୦୦	୧୧୧୧୧୧୧୧
୧୧	୧୧	୦୦	୧୧
୧୧	୧୧	୦୦	୧୧
୧୧	୧୧	୦୦	୧୧
୧୧	୧୧	୦୦	୧୧
୧୧	୧୧୧୧୧୧୧୧	୦୦	୧୧୧୧୧୧୧୧
୧୧	୧୧୧୧୧୧୧୧	୦୦	୧୧୧୧୧୧୧୧
୧୧	୧୧	୦୦	୧୧
୧୧	୧୧	୦୦	୧୧
୧୧୧୧	୧୧	୦୦	୧୧
୧୧୧୧	୧୧	୦୦	୧୧
୧୧୧୧	୧୧	୦୦	୧୧
୧୧	୧୧୧୧୧୧୧୧	୦୦୦୦୦୦	୧୧୧୧୧୧୧୧
୧୧	୧୧୧୧୧୧୧୧	୦୦୦୦୦୦	୧୧୧୧୧୧୧୧

[illegible]

0 62.

```
1 C.....THIS IS PROGRAM "M100.FOR"
2 C      FOR BASIC CAPACITY CALCULATION FOR FACTORY LAYOUT PLANNING
5
6 C...
7     INTEGER ACTION
8     WRITE(6,10)
9     FORMAT(' CAFLAP MASTER PROGRAM'/)
10 C...Functions of the program are:
11 C...-to enable to enter and run individual programs separately
12 C...-to change sequences/order of execution
13 C...-to ease interaction between programs
14 C...
15     WRITE(6,20)
16     20  FORMAT(' MENU of the CAFLP master program'/)
17     WRITE(6,110)
18     110  FORMAT(' A  VOLUME OF MATERIAL HANDLING(VOLMH)')
19     WRITE(6,120)
20     120  FORMAT(' B  NUMBER OF WORK STATIONS (NOKS)')
21     WRITE(6,130)
22     130  FORMAT(' C  MANUFACTURING AREA-in sq.M-(MFAREA)')
23     WRITE(6,140)
24     140  FORMAT(' D  TOTAL LENGTH OF INDUSTRIAL BAY-in M-(BAYLGH)')
25     WRITE(6,30)
26     30  FORMAT(' To run the program requested type the prefix letter
27 &...To finish type XX ')
28     40  READ(5,50)ACTION
29     50  FORMAT(A1)
30     IF (ACTION.EQ.'A')GOTO 210
31     IF (ACTION.EQ.'B')GOTO 220
32     IF (ACTION.EQ.'C')GOTO 230
33     IF (ACTION.EQ.'D')GOTO 240
34     IF (ACTION.EQ.'X')GOTO 280
35     WRITE(6,60)
36     60  FORMAT(' PROGRAM IS NOT SELECTED PLEASE TRY AGAIN')
37     GOTO 40
38     210  CONTINUE
39     CALL VOLMH
40     220  CONTINUE
41     CALL NOKS
42     230  CONTINUE
43     CALL MFAREA
44     240  CONTINUE
45     CALL BAYLGH
46     280  CONTINUE
47     STOP
48     END
49 C...
50     SUBROUTINE VOLMH
51 C      FACTORY LAYOUT PLANNING-VOLUME OF MATERIAL HANDLING
52 C      THE FOLLOWING PROGRAM CALCULATES A VOLUME OF MATERIAL ,W.I.P.
53 C      AND PRODUCT
54 C      IN UNIT LOADS(UNL) PASSING THROUGH A FACTORY/INDUSTRIAL BAY
55 C      THIS PROGRAM IS AN ENTRY PROGRAM
56     10  FORMAT('FACTORY LAYOUT PLANNING-VOLUME OF MATERIAL HANDLING')
57 C      STEP 1 CALCULATES THE NUMBER OF PARTS PER UNIT LOAD(NPPUNL)
58 C      VOLUME OF UNIT LOAD IN CUBIC METERS AND VOLUME OF PARTS
59 C      TO BE MACHINED IN THE BATCH )IN CUBIC METERS IS TO BE DECIDED
60 C      /CALCULATED BY PRODUCTION DEPT.PRIOR THIS PROGRAM STARTS.
61     WRITE(6,20)
```


63.

```

62 20  FORMAT(' PLEASE ENTER VOLUME OF UNL (VOLUNL) IN CU METERS')
63      WRITE(6,30)
64 30  FORMAT(' PLEASE ENTER VOLUME OF PART(VOLPT) IN CU METERS')
65 C   VOLUMES TO BE ENTERED VIA KEYBOARD
66      READ(5,*)VOLUNL,VOLPT
67      NPPUNL=VOLUNL/VOLPT
68 C   NOW THE SYSTEM WILL PRINT IN COLUMNS THE ABOVE DATA
69      WRITE(6,40)
70 40  FORMAT(4X,'VOLUNL',7X,'VOLPT',8X,'NO PARTS PER UNL')
71      WRITE(6,50)VOLUNL,VOLPT,NPPUNL
72 50  FORMAT(5X,F5.3,3X,F11.8,F16.2)
73 C
74 C... STEP 2 . CALCULATE THE NUMBER OF UNIT LOAD GOING THROUGH BAY
75 C... PER YEAR(NOUNLPHY),SO WE HAVE TO ENTER PRODUCTION PROGRAMME
76 C... IN PARTS PER YEAR(PRODNPRG)
77 C
78      WRITE(6,60)
79 60  FORMAT(' ENTER THE PRODN PROGRAMME IN PARTS PER YEAR(PPRG)')
80      READ(1,*)PPRG
81      NUNLPHY=PPRG/NPPUNL
82      WRITE(6,70)
83 70  FORMAT(3X,'PRODN PRG.',4X,'NO PARTS PER UNL',9X,'NO UNL PER YR')
84      WRITE(6,80)PPRG,NPPUNL,NUNLPHY
85 80  FORMAT(2X,F12.1,3X,F10.1,15X,F12.2)
86 C   THIS THE BEGINNING OF PROGRAM VOLM3
87 C
88 C   STEP3-CALCULATE NUMBER OF UNIT LOADS GOING THROUGH
89 C   THE INDUSTRIAL BAY PER HOUR(UNLPH).
90 C   THE PRODUCTION YEAR HAS NUMBER OF WORKING HOURS GIVEN
91 C   BY LOCAL CONDITIONS. THIS CAN BE ALSO
92 C   EXPRESSED BY YEARLY CAPACITY OF A WORK STATION (EFWSH)
93 C   AVERAGE YEARLY CAPACITY OF A WORK STATION FOR 48HRS WEEK
94 C   AND ONE SHIFT
95 C   IS 2000 HOURS(OF COURSE THIS HAS TO BE AMENDED ACCORDING
96 C   TO YOUR LOCAL
97 C   CONDITION...LOCAL CONDITION INCLUDE HOURS CONVENTION
98 C   (NUMBER OF WORKING HOURS PER WEEK AND NUMBER OF SHIFTS).
99 C
100      WRITE(1,90)
101 90  FORMAT(' ENTER PRODUCTION YEAR  NUMBER OF HOURS- (EFWSH)')
102      READ(5,*)EFWSH
103      UNLPH=NUNLPHY/EFWSH
104      WRITE(6,100)UNLPH
105 100  FORMAT(' THE TOTAL NUMBER OF UNIT LOAD GOING THROUGH THE INDUSTRIAL
106      & BAY PER HOUR IS',35X,F6.2)
107      RETURN
108      END
109 C   THIS THE END OF PROGRAM 'EXVOLM3'
110 C...
111 C
112 C   SUBROUTINE HORS
113 C   PROGRAM NUMBER OF WORK STATION NEEDED(NOWS)
114 C
115      WRITE(6,200)
116 200  FORMAT(' CALCULATE NUMBER OF WORK STATION NEEDED USING UNL')
117 C
118 C   THIS CALCULATION HAS AN ADVANTAGE FOR ANY FUTURE
119 C   CALCULATION BECAUSE
120 C   OF SPACES CONSIDERATION(PRODUCT SPACES ARE ALWAYS
121 C   CALCULATED FROM UNIT LOADS)

```

64.

```

118 C
119 C STEP 1-NUMBER OF STANDARD HOURS PER UNIT LOAD HAS TO BE CALCULATED
120 C
121 WRITE(6,210)
122 210 FORMAT(' PLEASE ENTER NUMBER OF STANDARD HOURS PER PART (SHPPM)')
123 WRITE(6,220)
124 220 FORMAT(' PLEASE ENTER NUMBER OF PARTS PER UNIT LOAD(NPPUL)')
125 READ(5,*)SHPPM,NPPUL
126 SHPUL=SHPPM*NPPUL
127 WRITE(6,230)SHPUL
128 230 FORMAT(' NUMBER OF STD HOURS PER UNIT LOAD(SHPUL)IS',
129 62X,F7.2)
130 C
131 C STEP 2- NUMBER OF WORK STATION FOR THE PARTICULAR PRODUCTION
132 C PROGRAMME IS CALCULATED (ON BASIS OF UNIT LOADS)
133 C
134 WRITE(6,240)
135 240 FORMAT(' PLEASE ENTER NUMBER OF UNIT LOADS PER HOUR(UNLPH)')
136 READ(5,*)UNLPH
137 NOW=SHPUL*UNLPH
138 WRITE(6,260)NOW
139 260 FORMAT(' THE NUMBER OF WORK STATIONS NEEDED IS',2X,F7.3)
140 RETURN
141 END
142 C...
143 SUBROUTINE MFAREA
144 C
145 C
146 C PROGRAM FOR CALCULATION OF THEORETICAL MANUFACTURING AREA
147 C (AREA FOR ALL WORK STATION MODULES REQUESTED...MANUFACTURING SPACE)
148 C IN SQUARE METERS.
149 C
150 WRITE(6,300)
151 300 FORMAT(' CALCULATE THEORETICAL MANUFACTURING AREA IN SQ.METERS')
152 C THE AREA IS GIVING APPROXIMATE AREA NEEDED-FOR "STUDY" AND "PROGRAMME"
153 C AND INDICATE THE SIZE OF AN "ENDLESS STRAIGHT" INDUSTRIAL BAY
154 C
155 WRITE(6,310)
156 310 FORMAT(' PLEASE ENTER NUMBER OF WORK STATION SUGGESTED(NOWS)')
157 READ(5,*)NOWS
158 WRITE(6,320)
159 320 FORMAT('PLEASE ENTER AVERAGE AREA PER WORK STATION (WSAA)')
160 C THE AVERAGE AREA PER WORK STATION HAS TO BE ESTIMATED ACCORDING
161 C/TO EXPERIENCE IN SIMILAR PRODUCTION AND WORKSHOP...OR INFORMATION
162 C IS TAKEN FROM W.S.CARDS(MANUFACTURING MODULES)
163 C
164 READ(5,*)WSAA
165 MFARE=NOWS*WSAA
166 WRITE(6,330)MFARE
167 330 FORMAT(' MANUFACTURING AREA(MFAREA)IN SQ.METERS IS',3X,F7.2)
168 RETURN
169 END
170 C...
171 SUBROUTINE BAYLGW
172 C
173 C This is"BAYLG"program for computation of a total length
174 C of "CONTINUOUS" industrial bay.
175 C Data :MFAREA is received from the program MFAREA
176 C BAYAD is determined width of bay according to following
177 C quantitative requirements

```

65.

```


178 C      -size of Product
179 C      -size of an average Work Station
180 C      -size of Aisles-Material Handling areas
181 C      -system of Material Handling
182 C      and is usually 6,9,12,15,18,21,24, etc, meters
183 C
184       WRITE(6,400)
185 400    FORMAT(' Calculate Length of "Continuous" industrial bay(BAYLG)')
186 C
187 C      The determination of sizes of the Bay is useful for graphical
188 C      design of Work Station in position in the bay and for decision
189 C      regarding dimensions of the industrial Hall(Plot needed).
190 C      Maximum length of a bay should not exceed length 198 m.
191 C
192       WRITE(6,410)
193 410    FORMAT(' Please enter the size of Manufacturing Area in Sq.m' )
194       READ(5,*)SFAREA
195       WRITE(6,420)
196 420    FORMAT(' Please enter dimension of bay width(BAYWD) in meters' )
197       READ(5,*)BAYWD
198       BAYLG=SFAREA/BAYWD
199       WRITE(6,430)BAYLG
200 430    FORMAT(' Total length of "Continuous" Bay(BAYLG)in m. is',3X,F7.2)
201       RETURN
202       ENL
203 C...
204 C...
205 C      FILE UNDER THE NAME "P100.FOR"

```




APPENDIX III

D r a w i n g N o . 1 .

Sheets 1 to 6

M/C NAME	M/C NO	CARD NO	POSITION	PAGE NO
GARRETT	17229248	18	CD(03-04)	001
01	CLASS NO. 17229248	07	MANUFACTURER. RICHARD GARRETT	
02	DESCRIPTION. NC DRILL	08	ORDER REF.	
03	COMPONENT-SUB-SYS.DIM/M PUNCHED CARD READER (0.76,0.63,1.45)	09	OTHER INFORMATION.	
04	STATIC LOAD/KN 14	10	DYNAMIC LOAD/KN	
05	TECHNOLOGICAL SPEC.	11	TEMPLATE FOR MSL001.	
06	REMARKS NO ANCHORING FOUNDATIONS			

M/C NAME	M/C NO	CARD NO	POSITION	PAGE NO
R. GARRETT	17229248	18	CD (03-04)	002



KEY:

 , MAINTENANCE SPACE

 : MAN SPACE

M/C NAME	M/C NO	CARD NO	POSITION	PAGE NO
R. GARRETT	17229248	18	CD(03-04)	003

SPECIFICATIONS.

A MACHINE			
01	Maximum workpiece dimensions (WxDxH)	mm	38
02	Maximum workpiece Weight	Kgs	
03	Front to back table travel	mm	370
04	Left to right table travel	mm	610
05	Vertical slide travel	mm	685
06	Table feed rate	mm/min	
07	Outside dimensions (WxDxH)	/m	2.1x1.6x1.6
08	Weight	kgs	
09			
10			
11			
B POWER SUPPLY.			
01	Output voltage (no load)	V	380
02	Maximum machine current		1.76
03	Machine control system		YES
04	Maximum input		
05	Outside dimensions (WxDxH)	mm	
06	Weight	Kgs	
07			
08			
C DIELECTRIC FLUID SUPPLY.			
01	Dielectric fluid	COOLANT	
02	Tank capacity	L	30
03	Filter element		YES
04	Outside dimensions (WxDxH)	/m	0.5x0.3x0.2
05	Weight	Kgs	
06			



D CONTROL		
01	Control axes	X, Y, Z
02	Interpolation	
03	Minimum command unit	
04	Table position display	mm
05	Block No. display	DIGITAL
06	Program capacity	NO
07	Input method	TAPE
08	Mirror Image	YES
09	X Y axis change	YES
10	Single block feed	YES
11	Dry run	YES
12	Machine Lock	YES
13	Backlash compensation	YES
14	Memory call	NO
15	Self diagnostic FCN	NO
16	Automatic positioning function	ON TAPE
17	Inch/mm display	NO
18	Outside dimensions (WxDxH)	/m 0.7x0.6x1.4
19	Weight	Kgs
20		
21		
E REMARKS		
01		
02		
03		
04		
05		

M/C NAME	M/C NO	CARD NO	POSITION	PAGE NO
R. GARRETT	17229248	18	CD(03-04)	004

	MAINTANANCE CRETERIA	TIME INTERVALS				REMARKS
		DAILY	WRLY	HTHLY	YRLY	
A	MECHANICAL					PLACE X IN APPROPRIATE TIME SCALE <u>NOTE:</u> OVERHAULL ONCE EVERY YEAR
A1	CHECK & EXAMINE					
01	BEARINGS				X	
02	DRIVE BELTS				X	
03	SAFETY DEVICES			X		
04	M/C CALIBRATION			X		
05	TABLE ALIGNMENT			X		
06	MOUNTING BOLTS				X	
07	HOSE & PIPES			X		
08						
A2	CLEAN & LUBRICATE					
01	MOVING PARTS	X				
02	MOVING SURFACES	X				
03						
04						
A3	REPLACE					
01	DRIVE BELTS				X	
02	BEARINGS				X	
03						
04						
05						
B	ELECTRICAL					
B1	CHECK & EXAMINE					
01	CONTACTORS			X		
02	AUTOMATIC CONTROLS			X		
03	FUSES			X		
04	BRUSHES			X		
05	CHARGE COILS			X		
06						
B2	CLEAN					
01	CONTACT POINTS			X		
02						
03	REPLACE					
04						
05						
C	HYDRAULIC					
C1	CHECK & EXAMINE					
01	OIL LEVEL		X			
02	OIL FILTERS		X			
03	PIPES & VESSELS			X		
04	PUMP BEARINGS				X	
05						
C2	CLEAN					
01	OIL FILTERS			X		
02						
C3	REPLACE					
01	OIL			X		
02	OIL FILTERS				X	
03						

M/C NAME	M/C NO	CARD NO	POSITION	PAGE NO
R. GARRETT	17229248	18	CD(03-04)	005

		A	B	C
		TYPE	CONSUMPTION /MONTH	QUALITY
001	OIL	SHELL VIERRA OIL 69	DEPENDS ON USAGE	GOOD
002	GREASE	ALVANIA GREASE NO. 2	DEPENDS ON USAGE	GOOD
003	COOLANT	MINERAL OIL	DEPENDS ON USAGE	GOOD
004	HYD. OIL	/	/	/
005				



KEY:

- ① : OIL
- ② : GREASE
- ③ : COOLANT

M/C NAME	M/C NO.	CARD NO.	POSITION	PAGE NO.
R.GARRETT	1722924B	18	CD(03-04)	006

INSTALATION DETAILS

A MACHINE DETAILS				D HANDLING REQUIREMENTS			
01	MANUFACTURER	R.GARRETT		01	Crane Maximum Lift	kg	
02	MACHINE TYPE	NC DRILL		02	Fork Lift Truck		
03	MACHINE MODEL	TD.251S		03	Others		
04				E AUXILLIARIES			
05				01	Water		YES
B MACHINE DIMENSIONS				02	Power		YES
				03	Lubricating Oil		YES
				04	Coolant		YES
				05	Gas		NO
				06	Waste Removal		YES
C FLOOR REQUIREMENTS				F OTHERS			
01	Type of Floor	CONCRETE					
02	Method of Fixing						
DRAWING OF FOUNDATION FLOOR							

NO ANCHORING FOUNDATIONS


D r a w i n g N o . 2 .



D r a w i n g N o . 3 .

ELTRON (LONDON) LTD.

DETAIL LAYOUT II



ELTRON (LONDON) LTD.

DETAIL LAYOUT II

